EMERSON™
Industrial Automation

User Guide

Mentor MP

High performance DC drive
25A to 7400A, 480V to 690V
Two or four quadrant operation

Part Number: 0476-0000-04
Issue: 4

CONTROL TECHNIQUES

www.controltechniques.com

General Information

The manufacturer accepts no liability for any consequences resulting from inappropriate, negligent or incorrect installation or adjustment of the optional operating parameters of the equipment or from mismatching the variable speed drive with the motor.

The contents of this guide are believed to be correct at the time of printing. In the interests of a commitment to a policy of continuous development and improvement, the manufacturer reserves the right to change the specification of the product or its performance, or the contents of the guide, without notice.

All rights reserved. No parts of this guide may be reproduced or transmitted in any form or by any means, electrical or mechanical including photocopying, recording or by an information storage or retrieval system, without permission in writing from the publisher.

Drive software version

This product is supplied with the latest software version. If this drive is to be connected to an existing system or machine, all drive software versions should be verified to confirm the same functionality as drives of the same model already present. This may also apply to drives returned from a Control Techniques Service Centre or Repair Centre. If there is any doubt please contact the supplier of the product.

The software version of the drive can be checked by looking at Pr **11.29** (**di14**/**0.49**) and Pr **11.34**. This takes the form of xx.yy.zz where Pr **11.29** (**di14**/**0.49**) displays xx.yy and Pr **11.34** displays zz. (e.g. for software version 01.01.00, Pr **11.29** (**di14**/**0.49**) = 1.01 and Pr **11.34** displays 0).

Environmental statement

Control Techniques is committed to minimising the environmental impacts of its manufacturing operations and of its products throughout their life cycle. To this end, we operate an Environmental Management System (EMS) which is certified to the International Standard ISO 14001. Further information on the EMS, our Environmental Policy and other relevant information is available on request, or can be found at www.greendrives.com.

The electronic variable-speed drives manufactured by Control Techniques have the potential to save energy and (through increased machine/process efficiency) reduce raw material consumption and scrap throughout their long working lifetime. In typical applications, these positive environmental effects far outweigh the negative impacts of product manufacture and end-of-life disposal.

Nevertheless, when the products eventually reach the end of their useful life, they must not be discarded but should instead be recycled by a specialist recycler of electronic equipment. Recyclers will find the products easy to dismantle into their major component parts for efficient recycling. Many parts snap together and can be separated without the use of tools, while other parts are secured with conventional fasteners. Virtually all parts of the product are suitable for recycling.

Product packaging is of good quality and can be re-used. Large products are packed in wooden crates, while smaller products come in strong cardboard cartons which themselves have a high recycled fibre content. If not re-used, these containers can be recycled. Polythene, used on the protective film and bags for wrapping product, can be recycled in the same way. Control Techniques' packaging strategy prefers easily-recyclable materials of low environmental impact, and regular reviews identify opportunities for improvement.

When preparing to recycle or dispose of any product or packaging, please observe local legislation and best practice.

REACH legislation

EC Regulation 1907/2006 on the Registration, Evaluation, Authorisation and restriction of Chemicals (REACH) requires the supplier of an article to inform the recipient if it contains more than a specified proportion of any substance which is considered by the European Chemicals Agency (ECHA) to be a Substance of Very High Concern (SVHC) and is therefore listed by them as a candidate for compulsory authorisation.

For current information on how this requirement applies in relation to specific Control Techniques products, please approach your usual contact in the first instance. Control Techniques position statement can be viewed at:

http://www.controltechniques.com/REACH

Contents

1 Safety Information

1.1 Warnings, Cautions and Notes

⚠️ **WARNING**
A Warning contains information which is essential for avoiding a safety hazard.

⚠️ **CAUTION**
A Caution contains information which is necessary for avoiding a risk of damage to the product or other equipment.

NOTE

A Note contains information which helps to ensure correct operation of the product.

1.2 Electrical safety - general warning

The voltages used in the drive can cause severe electrical shock and/or burns, and could be lethal. Extreme care is necessary at all times when working with or adjacent to the drive.

Specific warnings are given at the relevant places in this Guide.

1.3 System design and safety of personnel

The drive is intended as a component for professional incorporation into complete equipment or system. If installed incorrectly, the drive may present a safety hazard.

The drive uses high voltages and currents, carries a high level of stored electrical energy, and is used to control equipment which can cause injury.

System design, installation, commissioning / start-up and maintenance must be carried out by personnel who have the necessary training and experience. They must read this safety information and this guide carefully.

The STOP and START controls or electrical inputs of the drive must not be relied upon to ensure safety of personnel. They do not isolate dangerous voltages from the output of the drive or from any external option unit. The supply must be disconnected by an approved electrical isolation device before gaining access to the electrical connections.

The drive is not intended to be used for safety-related functions.

Careful consideration must be given to the function of the drive which might result in a hazard, either through its intended behaviour or through incorrect operation due to a fault. In any application where a malfunction of the drive or its control system could lead to or allow damage, loss or injury, a risk analysis must be carried out, and where necessary, further measures taken to reduce the risk - for example, an over-speed protection device in case of failure of the speed control, or a fail-safe mechanical brake in case of loss of motor braking.

1.4 Environmental limits

Instructions within the supplied data and information within the *Mentor MP User Guide* regarding transport, storage, installation and the use of the drive must be complied with, including the specified environmental limits. Drives must not be subjected to excessive physical force.

1.5 Access

Access must be restricted to authorized personnel only. Safety regulations which apply at the place of use must be complied with.

1.6 Fire protection

The drive enclosure is not classified as a fire enclosure. A separate fire enclosure must be provided.

1.7 Compliance with regulations

The installer is responsible for complying with all relevant regulations, such as national wiring regulations, accident prevention regulations and electromagnetic compatibility (EMC) regulations. Particular attention must be given to the cross-sectional areas of conductors, the selection of fuses and other protection, and protective ground (earth) connections.

The *Mentor MP User Guide* contains instructions for achieving compliance with specific EMC standards.

Within the European Union, all machinery in which this product is used must comply with the following directives:

2006/42/EC: Safety of machinery

2004/108/EC: Electromagnetic compatibility

1.8 Motor

Ensure the motor is installed in accordance with the manufacturer's recommendations. Ensure the motor shaft is not exposed.

Low speeds may cause the motor to overheat because the cooling fan becomes less effective. The motor should be installed with a protection thermistor. If necessary, an electric forced ventilation fan should be used.

The values of the motor parameters set in the drive affect the protection of the motor. The default values in the drive should not be relied upon.

It is essential that the correct value is entered into Pr **5.07** (**SE07, 0.28**), *Motor rated current*. This affects the thermal protection of the motor.

1.9 Adjusting parameters

Some parameters have a profound effect on the operation of the drive. They must not be altered without careful consideration of the impact on the controlled system. Measures must be taken to prevent unwanted changes due to error or tampering.

1.10 Electrical installation

1.10.1 Electric shock risk

The voltages present in the following locations can cause severe electric shock and may be lethal:

- AC supply cables and connections
- Output cables and connections
- Many internal parts of the drive, and external option units

Unless otherwise indicated, control terminals are single insulated and must not be touched.

1.10.2 Stored charge

The drive contains capacitors that remain charged to a potentially lethal voltage after the AC supply has been disconnected. If the drive has been energized, the AC supply must be isolated at least ten minutes before work may continue.

2   Product information

Table 2-1   Model to frame size cross reference

Model			Frame
480V EN/IEC cULus	**575V EN/IEC cULus to 600V**	**690V EN/IEC**	
MP25A4(R)	MP25A5(R)		1A
MP45A4(R)	MP45A5(R)		
MP75A4(R)	MP75A5(R)		
MP105A4(R)	MP105A5(R)		1B
MP155A4(R)	MP155A5(R)		
MP210A4(R)	MP210A5(R)		
MP350A4(R)	MP350A5(R)	MP350A6(R)	2A
MP420A4(R)			
	MP470A5(R)	MP470A6(R)	
MP550A4(R)			
MP700A4(R)	MP700A5(R)	MP700A6(R)	2B
MP825A4(R)	MP825A5(R)	MP825A6(R)	
MP900A4(R)			
MP1200A4	MP1200A5	MP1200A6	2C
MP1850A4	MP1850A5	MP1850A6	
MP1200A4R	MP1200A5R	MP1200A6R	2D
MP1850A4R	MP1850A5R	MP1850A6R	

2.1   Ratings

The power ratings for the 480V, 575V and 690V configurations are shown in Table 2-2, Table 2-3 and Table 2-4.

The continuous current ratings given are for a maximum ambient temperature of 40°C (104°F) and an altitude of 1000m. For operation at higher temperatures and altitudes de-rating is required.

For further information see Chapter 12 *Technical data* on page 145.

Table 2-2   480V current ratings

Model	AC input current	DC output current		Typical motor power	
	Continuous	Continuous	150% overload	@ 400Vdc	@ 500Vdc
	A	A	A	kW	hp
MP25A4(R)	22	25	37.5	9	15
MP45A4(R)	40	45	67.5	15	27
MP75A4(R)	67	75	112.5	27	45
MP105A4(R)	94	105	157.5	37.5	60
MP155A4(R)	139	155	232.5	56	90
MP210A4(R)	188	210	315	75	125
MP350A4(R)	313	350	525	125	200
MP420A4(R)	376	420	630	150	250
MP550A4(R)	492	550	825	200	300
MP700A4(R)	626	700	1050	250	400
MP825A4(R)	738	825	1237.5	300	500
MP900A4(R)	805	900	1350	340	550
MP1200A4(R)	1073	1200	1800	450	750
MP1850A4(R)	1655	1850	2775	700	1150

Table 2-3   575V current ratings

Model	AC input current	DC output current		Typical motor power (With Vdc = 630V)	
	Continuous	Continuous	150% overload		
	A	A	A	kW	hp
MP25A5(R)	22	25	37.5	14	18
MP45A5(R)	40	45	67.5	25	33
MP75A5(R)	67	75	112.5	42	56
MP105A5(R)	94	105	157.5	58	78
MP155A5(R)	139	155	232.5	88	115
MP210A5(R)	188	210	315	120	160
MP350A5(R)	313	350	525	195	260
MP470A5(R)	420	470*	705	265	355
MP700A5(R)	626	700	1050	395	530
MP825A5(R)	738	825*	1237.5	465	620
MP1200A5(R)	1073	1200	1800	680	910
MP1850A5(R)	1655	1850	2775	1045	1400

* For this rating at 575V, 150% overload time is 20s at 40°C and 30s at 35°C.

Table 2-4   690V current ratings

Model	AC input current	DC output Current		Typical motor power (With Vdc = 760V)	
	Continuous	Continuous	150% Overload		
	A	A	A	kW	hp
MP350A6(R)	313	350	525	240	320
MP470A6(R)	420	470*	705	320	425
MP700A6(R)	626	700	1050	480	640
MP825A6(R)	738	825*	1237.5	650	850
MP1200A6(R)	1073	1200	1800	850	1150
MP1850A6(R)	1655	1850	2775	1300	1750

* For this rating at 690V, 150% overload time is 20s at 40°C and 30s at 35°C.

Maximum continuous input current

The values of maximum continuous input current are given to aid the selection of cables and fuses. These values are stated for worst-case condition.

> **NOTE**
>
> For current ratings above 1850A then parallel connection of the drives is required. However, this function is not implemented on firmware versions V01.05.01 and earlier.

2.1.1 Typical short-term overload limits

The maximum percentage overload limit changes depending on the selected motor.

Variations in motor rated current will result in changes in the maximum possible overload as detailed in the *Mentor MP Advanced User Guide*.

Figure 2-1 can be used to determine the maximum overload duration available for overloads between 100% and 150%. For example the maximum overload available for a period of 60 seconds is 124%.

Figure 2-1 Maximum overload duration available

NOTE

Overload of 150% for 30s is available up to a maximum of 10 repetitions per hour.

2.2 Model number

The way in which the model numbers for the Mentor MP range are formed is described in Figure 2-2.

Figure 2-2 Model number

MP 1 2 0 0 A 4 R

Mentor product line
MP : Mentor Platform

Continuous armature current rating (A)

Voltage rating
4 = 480V 24V to 480V -20% +10%
5 = 575V 500V to 575V -10% +10%
6 = 690V 500V to 690V -10% +10%

R - 4 quadrant operation
Blank - 2 quadrant operation

2.3   Compatible encoders

Table 2-5   Encoders compatible with Mentor MP

Encoder type	Pr 3.38 (Fb07, 0.77) setting
Quadrature incremental encoders with or without marker pulse	Ab (0)
Frequency and direction incremental encoders with or without marker pulse	Fd (1)
Forward / reverse incremental encoders with or without marker pulse	Fr (2)

2.4   Nameplate description

Figure 2-3   Typical drive rating label

2.4.1   Output current

The continuous output current ratings given on the rating label are for maximum 40°C (104°F) and 1000m altitude. Derating is required for higher ambient temperatures >40°C (104°F) and higher altitude. For derating information, refer to section 12.1.12 *Altitude* on page 150.

2.4.2   Input current

The input current is affected by the supply voltage, frequency and load inductance. The input current given on the rating label is the typical input current.

2.5 Drive features and options

Figure 2-4 Drive features and options on size 1

Figure 2-5 Drive features and options for size 2

* A SMARTCARD is provided as standard. For further information, refer to Chapter 9 *SMARTCARD operation* on page 81.

2.5.1   Options available for Mentor MP

All Solutions Modules are color-coded in order to make identification easy. The following table shows the color-code key and gives further details on their function.

Table 2-6   Solutions Module identification

Type	Solutions Module	Color	Name	Further Details
Feedback		Light Green	SM-Universal Encoder Plus	**Universal Feedback interface** Feedback interface for the following devices: **Inputs** • Incremental encoders • SinCos encoders • SSI encoders • EnDat encoders **Outputs** • Quadrature • Frequency and direction • SSI simulated outputs
		Brown	SM-Encoder Plus	**Incremental encoder interface** Feedback interface for incremental encoders without commutation signals. No simulated encoder outputs available
		Dark Brown	SM-Encoder Output Plus	**Incremental encoder interface** Feedback interface for incremental encoders without commutation signals. Simulated encoder output for quadrature, frequency and direction signals
		N/A	15-way D-type converter	**Drive encoder input converter** Provides screw terminal interface for encoder wiring and spade terminal for shield
		N/A	Single ended encoder interface (15V or 24V)	**Single ended encoder interface** Provides an interface for single ended ABZ encoder signals, such as those from hall effect sensors. 15V and 24V versions are available.
Automation (I/O Expansion)		Yellow	SM-I/O Plus	**Extended I/O interface** Increases the I/O capability by adding the following to the existing I/O in the drive: • Digital inputs x 3 • Digital I/O x 3 • Analog inputs (voltage) x 2 • Analog output (voltage) x 1 • Relay x 2
		Yellow	SM-I/O 32	**Extended I/O interface** Increase the I/O capability by adding the following to the existing I/O in the drive: • High speed digital I/O x 32 • +24V output
		Dark Yellow	SM-I/O Lite	**Additional I/O** 1 x Analog input (± 10V bi-polar or current modes) 1 x Analog output (0 to 10V or current modes) 3 x Digital input and 1 x Relay
		Dark Red	SM-I/O Timer	**Additional I/O with real time clock** As per SM-I/O Lite but with the addition of a Real Time Clock for scheduling drive running
		Turquoise	SM-I/O PELV	**Isolated I/O to NAMUR NE37 specifications** For chemical industry applications 1 x Analog input (current modes) 2 x Analog outputs (current modes) 4 x Digital input / outputs, 1 x Digital input, 2 x Relay outputs
		Olive	SM-I/O 120V	**Additional I/O conforming to IEC 61131-2 120Vac** 6 digital inputs and 2 relay outputs rated for 120Vac operation
		Cobalt Blue	SM-I/O 24V Protected	**Additional I/O with overvoltage protection up to 48V** 2 x Analog outputs (current modes) 4 x Digital input / outputs, 3 x Digital inputs, 2 x Relay outputs

Table 2-6   Solutions Module identification

Type	Solutions Module	Color	Name	Further Details
Automation (Applications)		Moss Green	SM-Applications Plus	**Applications Processor (with CTNet)** 2nd processor for running pre-defined and /or customer created application software with CTNet support. Enhanced performance over SM-Applications
		White	SM-Applications Lite V2	**Applications Processor** 2nd processor for running pre-defined and /or customer created application software. Enhanced performance over SM-Applications Lite
		Golden brown	SM-Register	**Applications Processor** 2nd processor for running position capture functionality with CTNet support.
Fieldbus		Purple	SM-PROFIBUS DP-V1	**Profibus option** PROFIBUS DP adapter for communications with the drive
		Medium Grey	SM-DeviceNet	**DeviceNet option** Devicenet adapter for communications with the drive
		Dark Grey	SM-INTERBUS	**Interbus option** Interbus adapter for communications with the drive
		Light Grey	SM-CANopen	**CANopen option** CANopen adapter for communications with the drive
		Beige	SM-Ethernet	**Ethernet option** 10 base-T / 100 base-T; Supports web pages, SMTP mail and multiple protocols: DHCP IP addressing; Standard RJ45 connection
		Brown Red	SM-EtherCAT	**EtherCAT option** EtherCAT adapter for communications with the drive

Table 2-7   Keypad identification

Keypad	Name	Further Details
	SM-Keypad	**LED keypad option** Keypad with a LED display
	MP-Keypad	**LCD keypad option** Keypad with an alpha-numeric LCD display with Help function

Table 2-8   Serial comms lead

Serial comms lead	Name	Further Details
	CT Comms cable	CT EIA (RS) -232 (4500-0087) CT USB (4500-0096)

Table 2-9   External field control

External field controller	Name	Further Details
	FXMP25	For external control of field windings up to 25A, with field reversal capability. For further information, please see the *FXMP25 User Guide*.

2.6 Items supplied with the drive

The drive is supplied with a printed manual, a SMARTCARD, a safety information booklet, the Certificate of Quality, an accessory kit box including the items shown in Table 2-10, and a CD ROM containing all related product documentation and software tools.

Table 2-10 Parts supplied with the drive

Description	Size 1	Size 2A / 2B	Size 2C / 2D
Control connectors			
Tacho connector			
Relay connectors			
UL warning label		CAUTION Risk of Electric Shock Power down unit 10minutes before removing cover	
UL warning label for heatsink temperature			
Grounding bracket			
Terminal cover grommets			
Terminal shrouds			
Terminal shroud base covers			
M4 Screws			
Mounting feet bracket			

3   Mechanical Installation

3.1   Safety

WARNING Follow the instructions

The mechanical and electrical installation instructions must be adhered to. Any questions or doubt should be referred to the supplier of the equipment. It is the responsibility of the owner or user to ensure that the installation of the drive and any external option unit, and the way in which they are operated and maintained, comply with the requirements of the Health and Safety at Work Act in the United Kingdom or applicable legislation and regulations and codes of practice in the country in which the equipment is used.

WARNING Competence of the installer

The drive must be installed by professional assemblers who are familiar with the requirements for safety and EMC. The assembler is responsible for ensuring that the end product or system complies with all the relevant laws in the country where it is to be used.

WARNING If the drive has been used at high load levels for a period of time, the heatsink can reach temperatures in excess of 70°C (158°F). Human contact with the heatsink should be prevented.

WARNING Enclosure

The drive is intended to be mounted in an enclosure which prevents access except by trained and authorized personnel, and which prevents the ingress of contamination. It is designed for use in an environment classified as pollution degree 2 in accordance with IEC 60664-1. This means that only dry, non-conducting contamination is acceptable.

WARNING The drive enclosure is not classified as a fire enclosure. A separate fire enclosure must be provided.

WARNING Many of the drives in this product range weigh in excess of 15kg (33lb). Use appropriate safeguards when lifting these models.
See section 3.4 *Mounting method* on page 17.

3.2   Planning the installation

The following considerations must be made when planning the installation:

3.2.1   Access

Access must be restricted to personnel only. Safety regulations which apply at the place of use must be complied with.

3.2.2   Environmental protection

The drive must be protected from:

- moisture, including dripping water or spraying water and condensation. An anti-condensation heater may be required, which must be switched off when the drive is running
- contamination with electrically conductive material
- contamination with any form of dust which may restrict the fan, or impair airflow over various components
- temperature beyond the specified operating and storage ranges
- corrosive gasses

3.2.3   Cooling

The heat produced by the drive must be removed without its specified operating temperature being exceeded. Note that a sealed enclosure gives much reduced cooling compared with a ventilated one, and may need to be larger and/or use internal air circulating fans.

For further information, refer to section 3.6.2 *Enclosure sizing* on page 26.

3.2.4   Electrical safety

The installation must be safe under normal and fault conditions. Electrical installation instructions are given in Chapter 4 *Electrical installation* on page 32.

3.2.5   Electromagnetic compatibility

If it is necessary to meet strict emission limits, or if it is known that electromagnetically sensitive equipment is located nearby, then full precautions must be observed. The use of an external EMC filter may be required at the drive inputs, which must be located very close to the drives.

Space must be made available for the filters and allowance made for carefully segregated wiring. Both levels of precautions are covered in Table 12-42 *Drive power stage terminals on size 2 drives* on page 164.

3.2.6   Hazardous areas

The drive must not be located in a classified hazardous area unless it is installed in an approved enclosure and the installation is certified.

3.3 Terminal cover removal

> ⚠️ **WARNING**
> Isolation device
> The AC supply must be disconnected from the drive using an approved isolation device before any cover is removed from the drive or before any servicing work is performed.

> ⚠️ **WARNING**
> Stored charge
> The drive contains capacitors that remain charged to a potentially lethal voltage after the AC supply has been disconnected. If the drive has been energized, the AC supply must be isolated at least ten minutes before work may continue.

3.3.1 Removing the terminal covers

The drive is installed with one control terminal cover.

Figure 3-1 Removing the control terminal cover (size 1 shown)

To remove the terminal cover, undo the screw and slide the terminal cover downwards.

When replacing the terminal covers the screw should be tightened with a maximum torque of 1 Nm (0.7 lb ft).

3.3.2 Removing the finger-guard and break-outs

Figure 3-2 Removing the finger-guard break-outs

Place finger-guard on a flat solid surface and hit relevant break-outs with hammer as shown (1). Continue until all required break-outs are removed (2). Remove any flash / sharp edges once the break-outs are removed.

3.3.3 Installation and removal of a Solutions Module

⚠ **CAUTION** Please power down the drive before removing / installing the Solutions Module. Failure to do so may cause damage to product

Figure 3-3 Installation and removal of the Solutions Module

Solutions Module in slot 1

Solutions Module in slot 2

Solutions Module in slot 3

1. To install the Solutions Module, press down in the direction shown above until it clicks into place.
2. To remove the Solutions Module, press inwards at the points shown (A) and pull in the direction shown (B).
3. The drive has the facility for all three Solutions Module slots to be used at the same time, as illustrated.

NOTE

It is recommended that the Solutions Module slots are used in the following order: slot 3, slot 2 and slot 1.

Mentor MP User Guide

Issue: 4   www.controltechniques.com

Figure 3-4   Removal and installation of a keypad

To fit, align the MP-Keypad and press gently in the direction shown until it clicks into position (A).

To remove, while pressing the tabs inwards (B), gently lift the MP-Keypad in the direction indicated (C).

NOTE

The keypad can be installed / removed while the drive is powered up and running a motor, providing that the drive is not operating in keypad mode.

3.4　Mounting method

The Mentor MP can only be surface mounted.

> ⚠ **WARNING**
> If the drive has been used at high load levels for a period of time, the heatsink can reach temperatures in excess of 70°C (158°F). Human contact with the heatsink should be prevented.

> ⚠ **WARNING**
> Many of the drives in this product range weigh in excess of 15kg (33lb). Use appropriate safeguards when lifting these models.

Figure 3-5　Overall size 1A dimensions

1.　The two outer holes must be used for mounting the Mentor MP.

> **NOTE**
>
> With the SMARTCARD installed to the drive, the depth measurement increases by 7.6mm (0.30 in).

> **NOTE**
>
> Fans are only installed to the MP75A4(R) and MP75A5(R).

Figure 3-6   Overall size 1B dimensions

1.   The two outer holes must be used for mounting the Mentor MP.

NOTE

With the SMARTCARD installed to the drive, the depth measurement increases by 7.6mm (0.30 in).

Figure 3-7   Installing the mounting feet bracket on size 1 drives

The bottom mounting bracket (1) should be installed to the back plate first with the screws fully tightened. The drive should then be lowered onto the bracket and slotted in. The top mounting bracket (2) should then be slotted into the drive and the top holes marked for mounting (380mm [14.96 in] from the centre of the holes on the bottom mounting bracket). Once the holes have been drilled, fix the top mounting bracket accordingly and tighten the screws.

It is not necessary to tighten the bottom mounting brackets with the drive in place. The brackets are designed to clamp the drive heatsink against the back plate.

Figure 3-8   Overall size 2A / 2B dimensions

NOTE

With the SMARTCARD installed to the drive, the depth measurement increases by 7.6mm (0.30 in).

Figure 3-9   Size 2C front view and mounting dimensions

Figure 3-10   Size 2C back-plate and mounting detail

NOTE

1.   M10 eye-bolts can be inserted in the location shown for lifting the drive. These are not supplied with the drive.

NOTE

With the SMARTCARD installed in the drive, the depth measurement increases by 7.6mm (0.30 in).

Mentor MP User Guide

Issue: 4   www.controltechniques.com

21

Figure 3-11   Size 2D front view and mounting dimensions

Figure 3-12   Size 2D back-plate and mounting detail

NOTE

1.   M10 eye-bolts can be inserted in the location shown for lifting the drive. These are not supplied with the drive.

NOTE

With the SMARTCARD installed to the drive, the depth measurement increases by 7.6mm (0.30 in).

Figure 3-13   Mounting methods of size 2C / 2D air duct

The Mentor MP size 2C and 2D air duct can be turned 180° to suit the customers infrastructure.

<div style="border:1px solid black; display:inline-block; padding:2px 8px;">**NOTE**</div>

There is no seal provided with this product for sealing off the gap around the air duct when mounted.

3.5   Installing and removing the terminal shrouds

Figure 3-14   Installing the terminal shrouds on size 1 drives

1.   Thread the AC supply and DC output connectors through the grommets provided and connect them to the drive.
2.   Place the terminal shroud over the top of the connectors and click into place (3).

Figure 3-15   Removing the terminal shrouds on size 1 drives

1.   Insert the screwdriver as shown.
2.   Lever in the direction shown to unclip the terminal shroud and remove.

Figure 3-16   Installing the terminal shrouds on size 2 drives

1.   Assemble the cable to the busbar.
2.   Place the terminal shroud base cover underneath the cable in the orientation shown.
3.   Place the terminal shroud over the cable in the orientation shown, slide the terminal shroud on to the base cover in the direction shown until it clicks in to place.
4.   For all power connections slide in the terminal shroud sub-assembly in the direction as shown.
5.   Insert the 2 x M4 x 16 screws using a pozi drive screwdriver.

NOTE

To remove the terminal shrouds, please reverse the process above.

3.6 Enclosure

3.6.1 Enclosure layout

Please observe the clearances in the diagram below taking into account any appropriate notes for other devices / auxiliary equipment when planning the installation.

Figure 3-17 Enclosure layout

3.6.2 Enclosure sizing

Refer to section 12.1.2 *Typical short-term overload limits* on page 145 for drive losses.

Add the dissipation figures for each drive that is to be installed in the enclosure.

Add the power dissipation figures for each EMC filter that is to be installed in the enclosure.

Calculate the total heat dissipation (in Watts) of any other equipment to be installed in the enclosure.

Add the figures of all of the above to get a total heat dissipation figure (in Watts) for the equipment in the enclosure.

Calculating the size of a sealed enclosure

The enclosure transfers internally generated heat into the surrounding air by natural convection. The larger the surface area of the enclosure walls, the better is the dissipation capability. Only the surfaces of the enclosure that are not in contact with a wall or floor can dissipate heat.

Calculate the minimum required unobstructed surface area A_e for the enclosure from:

$$A_e = \frac{P}{k(T_{int} - T_{ext})}$$

Where:

A_e Unobstructed surface area in m^2 (1 m^2 = 10.9 ft^2)

T_{ext} Maximum expected temperature in ^oC outside the enclosure

T_{int} Maximum permissible temperature in ^oC inside the enclosure

P Power in Watts dissipated by all heat sources in the enclosure

k Heat transmission coefficient of the enclosure material in $W/m^2/^oC$

Example

To calculate the size of an enclosure for the following:

- Two MP25A4 models operating under full load conditions
- Maximum ambient temperature inside the enclosure: 40°C
- Maximum ambient temperature outside the enclosure: 30°C

Dissipation of each drive: 125W

Dissipation from other heat generating equipment in the enclosure. 11W (max).

Total dissipation: 2 x (125 + 11) = 272W

The enclosure is to be made from painted 2mm (0.079in) sheet steel having a heat transmission coefficient of 5.5 W/m^2/°C. Only the top, front, and two sides of the enclosure are free to dissipate heat.

The value of 5.5 W/m^2/°C can generally be used with a sheet steel enclosure (exact values can be obtained by the supplier of the material). If in any doubt, allow for a greater margin in the temperature rise.

Figure 3-18   Enclosure having front, sides and top panels free to dissipate heat

Insert the following values:

T_{int}	40°C
T_{ext}	30°C
k	5.5
P	272W

The minimum required heat conducting area is then:

$$A_e = \frac{272W}{5.5(40-30)}$$

$$= 4.945 \text{ m}^2 \text{ (53.90 ft}^2\text{)} \quad (1 \text{ m}^2 = 10.9 \text{ ft}^2)$$

Estimate two of the enclosure dimensions - the height (**H**) and depth (**D**), for instance. Calculate the width (W) from:

$$W = \frac{A_e - 2HD}{H+D}$$

Inserting **H** = 2m and **D** = 0.6m, obtain the minimum width:

$$W = \frac{4.945 - (2 \times 2 \times 0.6)}{2 + 0.6}$$

$$= 0.979 \text{ m (38.5 in)}$$

If the enclosure is too large for the space available, it can be made smaller only by attending to one or all of the following:

*   Reducing the ambient temperature outside the enclosure, and/or applying forced-air cooling to the outside of the enclosure
*   Reducing the number of drives in the enclosure
*   Removing other heat-generating equipment

Calculating the air-flow in a ventilated enclosure

The dimensions of the enclosure are required only for accommodating the equipment. The equipment is cooled by the forced air flow.

Calculate the minimum required volume of ventilating air from:

$$V = \frac{3kP}{T_{int} - T_{ext}}$$

Where:

V	Air-flow in m^3 per hour (1 m^3/hr = 0.59 ft^3/min)
T_{ext}	Maximum expected temperature in °C *outside* the enclosure
T_{int}	Maximum permissible temperature in °C *inside* the enclosure
P	Power in Watts dissipated by *all* heat sources in the enclosure
k	Ratio of $\dfrac{P_o}{P_l}$

Where:

P_0	is the air pressure at sea level
P_l	is the air pressure at the installation

Typically use a factor of 1.2 to 1.3, to allow also for pressure-drops in dirty air-filters.

Example

To calculate the size of an enclosure for the following:

*   Three MP45A4 models operating under full load conditions
*   Maximum ambient temperature inside the enclosure: 40°C
*   Maximum ambient temperature outside the enclosure: 30°C

Dissipation of each drive: 168W

Dissipation from other heat generating equipment. 15 W

Total dissipation: 3 x (168 + 15) = 549W

Insert the following values:

T_{int}	40°C
T_{ext}	30°C
k	1.3
P	549W

Then:

$$V = \frac{3 \times 1.3 \times 549}{40-30}$$

$$= 214.1 \text{ m}^3\text{/hr (126.3 ft}^3 \text{ /min)} \quad (1 \text{ m}^3/ \text{ hr} = 0.59 \text{ ft}^3\text{/min)}$$

3.7   Heatsink fan operation

Mentor MP drive rated 75A and above are ventilated by internally supplied fans.

Ensure the minimum clearances around the drive are maintained to allow the air to flow freely.

The drive controls the fan operation based on the temperature of the heatsink and the drives thermal model system.

3.8   IP rating (Ingress Protection)

> ⚠️ **WARNING**
> IP rating
>
> It is the installer's responsibility to ensure that any enclosure which allows access to drives from frame sizes 2A to 2D while the product is energized, provides protection against contact and ingress to the requirements of IP20.

An explanation of IP rating is provided in section 12.1.13 *IP rating* on page 150.

3.9 Electrical terminals

3.9.1 Location of the power and ground terminals

Figure 3-19   Location of the power and ground terminals on size 1 drives

Figure 3-20   Location of the power and ground terminals on size 2A and 2B drives

Figure 3-21   Location of the power and ground terminals on size 2C and 2D drives

3.9.2   Terminal sizes and torque settings

> ⚠ **WARNING**
> To avoid a fire hazard and maintain validity of the UL listing, adhere to the specified tightening torques for the power and ground terminals. Refer to the following tables.

3.9.3   Torque settings

Table 3-1   Drive control, status relay and encoder terminal data

Model	Connection type	Torque setting
All	Plug-in terminal block	0.5 Nm 4.5 lb in

Table 3-2   Drive auxiliary and machine armature terminal data

Model	Connection type	Torque setting
All	Terminal block	0.5 Nm 4.5 lb in

Table 3-3   Drive power stage terminals on size 1 drives

Model	Connection type	Torque setting
All	M8 stud	10 Nm 89.0 lb in

Table 3-4   Drive power stage terminals on size 2 drives

Model	Connection type	Torque setting
Size 2A	M10 stud	15 Nm (133.0 lb in)
Size 2B		
Size 2C	M12 stud	30 Nm (266.0 lb in)
Size 2D		

3.10 Routine maintenance

The drive should be installed in a cool, clean, well ventilated location. Contact of moisture and dust with the drive should be prevented.

Regular checks of the following should be carried out to ensure drive / installation reliability are maximized:

Environment	
Ambient temperature	Ensure the enclosure temperature remains at or below maximum specified
Dust	Ensure the drive remains dust free – check that the heatsink and drive fan are not gathering dust. The lifetime of the fan is reduced in dusty environments.
Moisture	Ensure the drive enclosure shows no signs of condensation
Enclosure	
Enclosure door filters	Ensure filters are not blocked and that air is free to flow
Electrical	
Screw connections	Ensure all screw terminals remain tight
Crimp terminals	Ensure all crimp terminals remains tight – check for any discoloration which could indicate overheating
Cables	Check all cables for signs of damage

Safety Information	Product information	Mechanical Installation	Electrical installation	Getting started	Basic parameters	Running the motor	Optimization	SMARTCARD operation	Onboard PLC	Advanced parameters	Technical data	Diagnostics	UL information

Mentor MP User Guide
Issue: 4   www.controltechniques.com   **31**

4   Electrical installation

Many cable management features have been incorporated into the product and accessories, this chapter shows how to optimize them. Key features include:

- EMC compliance
- Product rating, fusing and cabling information
- External suppressor resistor details (selection / ratings)

WARNING

Electric shock risk
The voltages present in the following locations can cause severe electric shock and may be lethal:
- AC supply cables and connections
- DC cables, and connections
- Many internal parts of the drive, and external option units
Unless otherwise indicated, control terminals are single insulated and must not be touched.

WARNING

Isolation device
The AC supply must be disconnected from the drive using an approved isolation device before any cover is removed from the drive or before any servicing work is performed.

WARNING

STOP function
The STOP function does not remove dangerous voltages from the drive, the motor or any external option units.

WARNING

Drives are suitable for use on supplies of installation category III and lower, according to IEC 60664-1. This means they may be connected permanently to the supply at its origin in a building, but for outdoor installation additional over-voltage suppression (transient voltage surge suppression) must be provided to reduce category IV to category III.

4.1 Electrical connections

Refer to Figure 4-1 and Figure 4-2 to understand the function of the different power connections

Figure 4-1   Power connections for 480V drive

1.   End user must provide 230 / 115Vac supply for the internal fans on frame sizes C and D, see section 4.12 on page 49.

* For fuse ratings refer to section 4.6 *Cable and fuse size ratings* on page 38.

**For further information on EMC filters, see section 4.9.3 *EMC filter information* on page 47.

Figure 4-2   Power connections for 575V / 600V / 690V drives

1. End user must provide 230 / 115Vac supply for the internal fans on frame sizes C and D, see section 4.12 on page 49.

* For fuse ratings refer to section 4.6 *Cable and fuse size ratings* on page 38.

** The transformer must have zero phase delay.

4.2 Ground connections

The drive must be connected to the system ground of the AC supply. The ground wiring must conform to local regulations and codes of practice.

> ⚠️ **WARNING**
>
> Where there is a possibility of temporary condensation or corrosion occurring, the ground connection should be protected from corrosion by suitable jointing compound.

> ⚠️ **WARNING**
>
> Ground loop impedance
>
> The ground loop impedance must conform to the requirements of local safety regulations.
>
> The drive must be grounded by a connection capable of carrying the prospective fault current until the protective device (fuse, etc,) disconnects the AC supply.
>
> The ground connections must be inspected and tested at appropriate intervals.

Figure 4-3   Location of ground connection on size 1 drives

Figure 4-4   Location of ground connections on size 2A / 2B drives

Figure 4-5   Location of ground connections on size 2C / 2D drives

4.3 AC supply requirements

The standard drive is rated for a nominal supply voltage up to 480Vrms.

An optional rating of 575Vrms is available for size 1 drives.

An optional rating of 575Vrms and 690Vrms is available for size 2 drives.

> **⚠ WARNING**
> Grounded delta supplies exceeding 575V are not permitted for drives up to and including 210A. Grounded delta supplies exceeding 600V are not permitted for drives rated 350A and above.

4.3.1 Supply types

Drives rated for supply voltages of up to 575V (rated up to 210A) and 600V (350A and above), are suitable for use with any supply type i.e. TN-S, TN-C-S, TT, IT with grounding at any potential i.e neutral, centre or corner ("Grounded delta").

Grounded delta supplies >575V are not permitted for drives rated up to and including 210A. Grounded delta supplies >600V are not permitted for drives rated 350A and above.

4.3.2 Supply fault current

The maximum fault current level of the supply to all circuits is 100kA subject to the capability of the semiconductor fuse fitted.

4.3.3 MOV ground disconnect

The facility for disconnecting the jumper (link) between varistors and ground is provided for special circumstances, where a sustained high voltage may be present between lines and ground, for example during a high potential test or in certain situations with IT supplies and multiple generators. If the jumper (link) is disconnected then the immunity of the drive to high voltage impulses is reduced. It is then only suitable for use with supplies having overvoltage category II, i.e. not for connection at the origin of the low voltage supply within a building.

Figure 4-6 Removing the MOV ground connection on size 1 drives

The method for disconnecting the MOV ground connection on size 1 drives is shown below:

1. Remove the M4 x 16 screw using T20 Torx driver.
2. Remove the M4 x 12 screw using T20 Torx driver.
3. Remove the plate.
4. Re-fit the M4 x 12 screw using T20 Torx driver and tighten to a torque of 0.6 Nm (0.44 lb ft).
5. Fit a M4 x 16 **nylon screw** (not supplied) and tighten to a torque of 0.25 Nm (0.18 lb ft).

> **⚠ WARNING**
> The M4 x 16 screw (1) should not be re-used if the plate (3) is not re-installed. Instead a nylon screw should be used.

Figure 4-7 Removing the MOV ground connection on size 2A / 2B drives

The method for disconnecting the MOV ground connection on size 2A / 2B drives is shown below:

1. Remove the M4 x 30 screw using T20 Torx driver .

If re-fitting the M4 x 30 screw using T20 Torx driver, the screw must be tightened to a torque of 2.5Nm (1.84 lb ft).

Figure 4-8 Removing the MOV ground connection on size 2C / 2D drives

The method for disconnecting the MOV ground connection on size 2C / 2D drives is shown in Figure 4-8 above:

1. Remove the M4 x 30 screw using T20 Torx driver .

If re-fitting the M4 x 30 screw using T20 Torx driver, the screw must be tightened to a torque of 2.5Nm (1.84 lb ft).

4.3.4 Main AC supply (L1, L2, L3)

Table 4-1 Three phase AC supply

Specification	Product voltage variant		
	480V	**575V**	**690V**
Maximum nominal supply	480V	575V	690V
Tolerance	+10%		
Minimum nominal supply	24V	500V	
Tolerance	-20%	-10%	

4.4 Line reactors

The Mentor MP, in common with all naturally commutated thyristor drives, causes voltage notches at the input supply terminals. In order to avoid disturbance to other equipment using the same supply, the addition of external line inductance is strongly recommended in order to restrict the depth of the notches imposed on the shared supply. This is generally not necessary where a dedicated transformer is used to supply the drive.

The following recommendations for added line inductance, have been calculated based on the power drive systems standard: EN 61800-3:2004 "Adjustable speed electrical power drive systems – Part 3: EMC requirements and specific test methods".

NOTE

The current ratings specified in Table 4-2 are for typical motor currents where the motor current ripple is no more than 50% of drive rating.

Table 4-2 Minimum required line inductance for a typical application (50% ripple content)

Drive rated current A	System voltage				Typical current rating A	Maximum current rating A
	400V μH	**480V** μH	**575V** μH	**690V** μH		
25	220	260	320		21	22
45	220	260	320		38	40
75	220	260	320		63	67
105	220	260	320		88	94
155	160	190	230		130	139
210	120	140	170		176	188
350	71	85	110	120	293	313
420	59	71			351	375
470			80	91	393	420
550	45	54			460	492
700	36	43	53	61	586	626
825			45	52	690	738
900	28	33			753	805
1200	21	25	31	36	1004	1073
1850	18	23	29	32	1548	1655

NOTE

1. The above assumes the supply has 1.5% impedance.
2. Assumes a minimum supply rating of 5kA and a maximum rating of 60kA.

4.4.1 Auxiliary AC supply and connections

Table 4-3 Terminal functions

Terminals	Function
E1, E3	Supply for control electronics and field controller.
L11, L12	Field on / off. When L11 and L12 are open the supply is disconnected to the field regulator so there will be no field current.
F+, F-	Field supply to the motor.
MA1, MA2	These terminals are used to provide feedback from the motor armature terminals. This is required when the user has a contactor in the main DC armature connection. When the contactor is opened the drive will still be receiving armature feedback. This allows the field regulator to function correctly when the contactor is open.

Table 4-4 Line to line supply

Specification	Value
Maximum nominal supply	480V
Tolerance	+10%
Minimum nominal supply	208V
Tolerance	-10%

Each drive has an onboard field controller with the following current ratings.

Table 4-5 Current ratings

Model			Maximum auxiliary supply input current A	Maximum continuous field current rating A
MP25A4(R)	MP25A5(R)			
MP45A4(R)	MP45A5(R)			
MP75A4(R)	MP75A5(R)			
MP105A4(R)	MP105A5(R)		13	8
MP155A4(R)	MP155A5(R)			
MP210A4(R)	MP210A5(R)			
MP350A4(R)	MP350A5(R)	MP350A6(R)		
MP420A4(R)				
	MP470A5(R)	MP470A6(R)		
MP550A4(R)				
MP700A4(R)	MP700A5(R)	MP700A6(R)		
MP825A4(R)	MP825A5(R)	MP825A6(R)	23	20
MP900A4(R)				
MP1200A4	MP1200A5	MP1200A6		
MP1850A4	MP1850A5	MP1850A6		
MP1200A4R	MP1200A5R	MP1200A6R		
MP1850A4R	MP1850A5R	MP1850A6R		

4.4.2 Supply requirements

Maximum supply in-balance: 2% negative phase sequence (equivalent to 3% voltage in-balance between phases)

Frequency range: 45 to 65Hz (maximum rate of frequency change is 7Hz/s).

4.5 Control 24Vdc supply

The 24Vdc input has three main functions.

- It can be used to supplement the drive's own internal 24V when multiple SM-Universal Encoder Plus, SM-Encoder Output Plus, SM-I/O Plus, or SM-I/O 32 modules are being used and the current drawn by these modules is greater than the drive can supply. (If too much current is drawn from the drive, the drive will initiate a 'PS.24V' trip)

- It can be used as a back-up power supply to keep the control circuits of the drive powered up when the line power supply is removed. This allows any fieldbus modules, application modules, encoders or serial communications to continue to operate.
- It can be used to commission the drive when the line power supply is not available, as the display operates correctly. However, the drive will be in the UV trip state unless the line power supply is enabled, therefore diagnostics may not be possible. (Power down save parameters are not saved when using the 24V back-up power supply input.)

The working voltage range of the 24V power supply is as follows:

Maximum continuous operating voltage:	30.0V
Minimum continuous operating voltage:	19.2V
Nominal operating voltage:	24.0V
Minimum start up voltage:	21.6V
Maximum power supply requirement at 24V:	60W
Recommended fuse:	3 A, 50Vdc

Minimum and maximum voltage values include ripple and noise. Ripple and noise values must not exceed 5%.

4.6 Cable and fuse size ratings

⚠️ **WARNING**

The selection of the correct fuse is essential to ensure the safety of the installation

Maximum continuous input currents are given in section 2.1 *Ratings* on page 6 to aid the selection of fuses and cabling. The maximum input current is dependent on the ripple content of the output current. A value of 100% ripple has been assumed for the given ratings.

The cable sizing selected when installing a Mentor MP must comply with the local wiring regulations. The information provided in this section is provided for guidance purposes only.

The power terminals on Mentor MP frame size 1 drives have been designed to accommodate a maximum cable size of 150mm^2 (350kcmil) with a temperature of 90°C (194°F).

The power terminals on Mentor MP frame size 2A drives have been designed to accommodate a maximum cable size of 2 x 150mm^2 (2 x 350kcmil) with a temperature of 75°C (167°F).

The power terminals on Mentor MP frame size 2B drives have been designed to accommodate 2 x 240mm^2 with a temperature of 90°C (194°F). The use of cables sized using the US national electrical code as shown in Table 4-8 requires the use of a terminal adaptor.

The power terminals on Mentor MP frame size 2C and 2D drives have been designed for use with busbars. The drive can be used with cables as shown in Table 4-8 with the use of a terminal adaptor.

The actual cable size depends on a number of factors including:

- Actual maximum continuous current
- Ambient temperature
- Cable support, method and grouping
- Cable voltage drop

In applications where the motor used is of a reduced rating, the cable sizing selected can be appropriate for that motor. To protect the motor and the output cabling the drive must be programmed with the correct motor rated current.

NOTE

When using reduced cable sizes, the branch circuit protection fuse rating needs to be reduced in line with the cable size selected.

The following table shows typical cable sizes based on USA and International standards, assuming 3 conductors per raceway/conduit, an ambient temperature of 40°C (104°F) and applications with high output current ripple content.

Table 4-6 Typical cable sizes for size 1 drives

Model		IEC 60364-5-52[1]		UL508C/NEC[2]	
		Input	Output	Input	Output
MP25A4(R)	MP25A5(R)	2.5mm^2	4mm^2	8 AWG	8 AWG
MP45A4(R)	MP45A5(R)	10mm^2	10mm^2	4 AWG	4 AWG
MP75A4(R)	MP75A5(R)	16mm^2	25mm^2	1 AWG	1/0 AWG
MP105A4(R)	MP105A5(R)	25mm^2	35mm^2	1/0 AWG	1/0 AWG
MP155A4(R)	MP155A5(R)	50mm^2	70mm^2	3/0 AWG	4/0 AWG
MP210A4(R)	MP210A5(R)	95mm^2	95mm^2	300kcmil	350kcmil

NOTE

1. The maximum cable size is defined by the power terminal housing using 90°C (194°F) rated cables as per Table A.52-5 of the standard.
2. Assumes the use of 75°C rated cables, as per Table 310.16 of the National Electrical Code.

The use of higher temperature rated cable would allow a reduction on the minimum recommended cable size for Mentor MP shown above. For high temperature cable sizing, please refer to the data supplied by the manufacturer of the high temperature cable.

Table 4-7   Auxiliary wiring for size 1 drives

Frame size	Maximum input current	Continuous output current	IEC 60364-5-52 Table A52-4 Column B2 — Column B2 derated by 0,87 of PVC at 40		UL 508C	
			E1, E3 size	F+, F- , L11 & L12 size	E1, E3 size	F+, F- , L11 & L12 size
	A	A	mm²	mm²	mm²	mm²
1	13	8	2.5	1.5	14 AWG	14 AWG

Notes for IEC 60364:

IEC 60364-5-52 use installation method B2, table A.52-4 for three loaded conductors, PVC insulation 30°C and apply derating factor for 40°C from table A.52-14 (0.87 for PVC).

Notes for UL508C:

Either 60°C or 75°C cable can be used. Ampacities as per table 40.3 as described in the UL508C standard.

Table 4-8   Typical cable sizes for size 2 drives

Model			Maximum input current	Continuous output current	IEC 60364-5-52 Table A52-12 Column 5 derated by 0.91 for 40°C XLPE cables (IEC 60364-5-52 table A52-14) and 0.77 for cables bunching (IEC 60364-5-52 table A52-17 item 4) — 90°C cables at 40°C ambient		US National Electrical Code — 75°C cable at 40°C ambient	
					Input size mm²	Output size mm²	Input cables Kcmil	Output cables Kcmil
			A	A				
MP350A4(R)	MP350A5(R)	MP350A6(R)	313	350	120	150	350	400
MP420A4(R)			375	420	150	185	400	500
	MP470A5(R)	MP470A6(R)	420	470	185	240	500	600
MP550A4(R)			492	550	300	2 x 185	2 x 300	2 x 350
MP700A4(R)	MP700A5(R)	MP700A6(R)	626	700	2 x 150	2 x 150	2 x 500	2 x 600
MP825A4(R)	MP825A5(R)	MP825A6(R)	738	825	2 x 185	2 x 240	2 x 600	3 x 350
MP900A4(R)			805	900	2 x 185	2 x 240	3 x 350	3 x 400
MP1200A4(R)	MP1200A5(R)	MP1200A6(R)	1073	1200	2 x 300	3 x 240	3 x 600	4 x 400
MP1850A4(R)	MP1850A5(R)	MP1850A6(R)	1655	1850	4 x 240	4 x 300	*	*

* Values are beyond the mechanical design of the drive. At this power level it may be prudent to consider bus-bars.

Notes for IEC 60364:

NOTE

1. IEC 60364-5-52 table A 52-12 F method column 5 = Single core cable in free air.
2. IEC 60364-5-52 table A52-14 correction factor for ambient air temperature others than 30°C.
3. IEC 60364-5-52 table A52-17 item 4 correction factor for groups of more than one circuit or more than one multi-core cable placed on a single layer on a perforated tray.

NOTE

Notes for US National Electrical Code:
1. Table 310.17 allowable ampacities of single-insulated conducted rated 0 through 2000V in free air, based on ambient air temperature of 30°C (87°F).
2. Derating factor of 0.88 is applied for 40°C to the 75°C cable column. Table 310.17 is based on 30°C (86°F) ambient air temperature.
3. NEC 2005 edition table 310.15(B)(2)(a) shows the adjustment factors for more than three current-carrying conductors in a race way or cable, for 4-6 current-carrying conductors 0.80 derating factor is applied.

Table 4-9   Auxiliary wiring for size 2 drives

Frame size	Maximum input current	Continuous output current	IEC 60364-5-52 Table A52-4 Column B2 — Column B2 derated by 0,87 of PVC at 40		UL 508C	
			E1, E3 size	F+, F- , L11 & L12 size	E1, E3 size	F+, F- , L11 & L12 size
	A	A	mm²	mm²	mm²	mm²
2	23	20	6	4	10 AWG	10 AWG

Notes for IEC 60364:

IEC 60364-5-52 use installation method B2, table A.52-4 for three loaded conductors, PVC insulation 30°C and apply derating factor for 40°C from table A.52-14 (0.87 for PVC).

Notes for UL508C: Either 60°C or 75°C cable can be used. Ampacities as per table 40.3 as described in the UL508C standard.

4.6.1 Ferraz Shawmut fuses

Ferraz Shawmut fuses are recommended for the Mentor MP.

Table 4-10 Ferraz Shawmut semiconductor fusing for size 1 drives

Model	International			USA		
	Description	Catalogue number	Ref number	Description	Catalogue number	Ref number
Field fuses	10 x 38mm Ferrule	FR10GB69V12.5	H330011	10 x 38mm Ferrule	FR10GB69V12.5	H330011
MP25A4	22 x 58mm Ferrule	FR22GC69V32	A220915	A50QS Series American Round Fuse	A50QS60-4	A218937
MP25A5						
MP45A4		FR22GC69V63	X220912	A50QS Series American Round Fuse	A50QS80-4	L201513
MP45A5						
MP75A4		FR22GC69V100	W220911	A50QS Series American Round Fuse	A50QS125-4	K218417
MP75A5						
MP25A4R		FR22GC69V32	A220915	A70QS Series American Round Fuse	A70QS60-4	H219473
MP25A5R						
MP45A4R		FR22GC69V63	X220912	A70QS Series American Round Fuse	A70QS80-4	X212816
MP45A5R						
MP75A4R		FR22GC69V100	W220911	A70QS Series American Round Fuse	A70QS125-4	Q216375
MP75A5R						
MP105A4	Size 30 Square Body Fuse	PC30UD69V160EF	M300092	A50QS Series American Round Fuse	A50QS175-4	A222663
MP105A5						
MP155A4		PC30UD69V200EF	N300093	A50QS Series American Round Fuse	A50QS250-4	W211251
MP155A5						
MP210A4		PC30UD69V315EF	Q300095	A50QS Series American Round Fuse	A50QS350-4	T215343
MP210A5						
MP105A4R	Size 70 Square Body Fuse	PC70UD13C160EF	T300604	A70QS Series American Round Fuse	A70QS175-4	A223192
MP105A5R						
MP155A4R		PC70UD13C200EF	V300605	A70QS Series American Round Fuse	A70QS250-4	L217406
MP155A5R						
MP210A4R		PC70UD12C280EF	L300712	A70QS Series American Round Fuse	A70QS350-4	M211266
MP210A5R						

NOTE

A50QS series are only rated up to 500Vac.

Table 4-11 Ferraz Shawmut branch circuit protection fusing for size 1 drives

Model		International			USA
		Description	Catalogue number	Ref number	Catalogue number
Auxiliary		21 x 57mm Cylindrical	HSJ15	D235868	AJT10
MP25A4	MP25A5	22 x 58mm Ferrule	FR22GG69V25	N212072	AJT30
MP45A4	MP45A5		FR22GG69V50	P214626	AJT45
MP75A4	MP75A5		FR22GG69V80	Q217180	AJT70
MP25A4R	MP25A5R		FR22GG69V25	N212072	AJT30
MP45A4R	MP45A5R		FR22GG69V50	P214626	AJT45
MP75A4R	MP75A5R		FR22GG69V80	Q217180	AJT70
MP105A4	MP105A5	NH 00 Knife Blade	NH00GG69V100	B228460	AJT125
MP155A4	MP155A5	NH 1 Knife Blade	NH1GG69V160	F228487	AJT175
MP210A4	MP210A5		NH1GG69V200	G228488	AJT225
MP105A4R	MP105A5R	NH 00 Knife Blade	NH00GG69V100	B228460	AJT125
MP155A4R	MP155A5R	NH 1 Knife Blade	NH1GG69V160	F228487	AJT175
MP210A4R	MP210A5R		NH1GG69V200	G228488	AJT225

Table 4-12   Ferraz Shawmut DC protection fusing for size 1 drives

Model	International			USA		
	Description	Catalogue number	Ref number	Description	Catalogue number	Ref number
MP25A4R	20 x 127mm Cylindrical	FD20GB100V32T	F089498	A70QS Series American Round Fuse	A70QS60-4	H219473
MP25A5R						
MP45A4R	36 x 127mm Cylindrical	FD36GC100V80T	A083651	A70QS Series American Round Fuse	A70QS80-4	X212816
MP45A5R						
MP75A4R	20 x 127mm Cylindrical	FD20GC100V63T x 2 connected in parallel.	F083656 x 2 connected in parallel.	A70QS Series American Round Fuse	A70QS125-4	Q216375
MP75A5R						
MP105A4R	Size 120 Square Body	D120GC75V160TF	R085253	A70QS Series American Round Fuse	A70QS175-4	A223192
MP105A5R						
MP155A4R	Size 121 Square Body	D121GC75V250TF	Q085252	A70QS Series American Round Fuse	A70QS250-4	L217406
MP155A5R						
MP210A4R	Size 122 Square Body	D122GC75V315TF	M085249	A70QS Series American Round Fuse	A70QS350-4	M211266
MP210A5R						

NOTE

DC fusing is required on four quadrant (R) drives only.

Table 4-13   Ferraz Shawmut semiconductor fusing for size 2 drives

Model	International			USA		
	Description	Catalogue number	Ref number	Description	Catalogue number	Ref number
Field fuses	10 x 38mm Ferrule	FR10GB69V25	L330014	10 x 38mm Ferrule	FR10GB69V25	L330014
MP350A4	Square Body Fuses	PC30UD69V500TF	W300399	American Round Fuses Form 101 Range A70QS	A50QS450-4 A7OQS450-4	EQ16871 F214848
MP350A4R		PC71UD11V500TF	F300523		A7OQS450-4	F214848
MP350A5 MP350A6		PC31UD69V500TF	T300006		A70QS450	F214848
MP350A5R MP350A6R		PC72UD13C500TF	D300498			
MP420A4		PC32UD69V630TF	M300069		A50QS600-4 A70QS600-4	Q219457 Y219993
MP420A4R		PC272UD13C630TF	W300721		A70QS600-4	Y219993
MP470A5 MP470A6 MP470A5R MP470A6R		PC272UD13C700TF	X300722		2 x A70QS400 in parallel	J214345 (x2)
MP550A4		PC33UD69V700TF	Y300079		A50QS700-4 A70QS700-4	N223181 E202772
MP550A4R		PC272UD13C700TF	X300722		A70QS700-4	E202772
MP700A4		PC32UD69V1000TF	S300074		A50QS900-4 2 x A70QS500-4 in parallel	R212282 A218431 (x2)
MP700A4R		PC72UD10C900TF	G300869		2 x A70QS500 in parallel.	A218431 (x2)
MP700A5 MP700A6		PC32UD69V1000TF	S300074			
MP700A5R MP700A6R		PC73UD12C900TF	T300512			
MP825A4		PC32UD69V1100TF	M300759		A50QS1200-4 2 x A70QS600-4 in parallel	C217904 Y219993 (x2)
MP825A5 MP825A6		PC33UD69V1100TF	C300083		2 x A7OQS600-4 in parallel	Y219993 (x2)
MP825A4R MP825A5R MP825A6R		PC73UD95V800TFB	W300514			
MP900A4		PC33UD69V1250TF	D300084		A50QS1200-4 2 x A70QS600-4 in parallel	C217904 Y219993 (x2)
MP900A4R		PC73UD95V800TFB	W300514		2 x A70QS600-4 in parallel	Y219993 (x2)
MP1200A4		PC33UD60V1600TF	Z300586		2 x A5OQS800-4 in parallel. 2 x A70QS800-4 in parallel	C202287 (x2) Z213830 (x2)
MP1200A4R		PC273UD11C16CTF	J302228		2 x A70QS800-4 in parallel	Z213830 (x2)
MP1200A5 MP1200A6		PC232UD69V16CTD	W300215			
MP1200A5R MP1200A6R		PC273UD11C16CTF	J302228			
MP1850A4		**7,5 URD 44 PPSAF 2200	**K235184		2 x A5OQS1000-4 in parallel. *3 x A7OQS700-4 in parallel	B217391 (x2) *E202772 (x3)
MP1850A4R					*3 x A7OQS700-4 in parallel	*E202772 (x3)
MP1850A5 MP1850A6						
MP1850A5R MP1850A6R						

NOTE

A50QS series are only rated up to 500Vac.

*Application overload limited to infrequent overloads to avoid fuse wear out

**Fuse limits applications to those operating at rated current. No cyclic overloads permitted.

Table 4-14   Ferraz Shawmut branch circuit protection fusing for size 2 drives

Model		International			USA		
		Description	Catalogue number	Ref number	Description	Catalogue number	Ref number
Auxiliary		25A 600Vac High Speed Class J	HSJ205	G235871J	25A 600Vac High Speed Class J	AJT25R	X21160J
MP350A4(R)	MP350A5(R) MP350A6(R)	General purpose IEC (square body)	NH2GG69V355	Y228503	General purpose US (round body)	A6D400R	B216776
MP420A4(R)			NH3GG69V400	D228508		A6D500R	P217294
MP470A5(R) MP470A6(R)			NH4GG69V630-8 NH4AGG69V630-8	E215537 W222107		A6D600R	T217804
MP550A4 (R)			NH4GG69V630-8 NH4AGG69V630-8	E215537 W222107			
MP700A4(R)	MP700A5(R) MP700A6(R)		NH4GG69V800-8 NH4AGG69V800-8	K216554 M222858		A4BQ800	Z219373
MP825A4(R) MP825A5(R) MP825A6(R)			NH4GG69V800-8 NH4AGG69V800-8	K216554 M222858			
MP900A4R)		General purpose IEC (round body)	MF76GG69V1250	E302753		A4BQ1000	P216282
MP1200A4(R)	MP1200A5(R) MP1200A6(R)					A4BQ1200	R216790
MP1850A4(R)	MP1850A5(R) MP1850A6(R)		MF114GG69V2000	G302755		A4BQ2000	B223101

NOTE

USA fuses are only rated up to 600Vac.

Table 4-15   Ferraz Shawmut DC protection fusing for size 2 drives

Model	International			USA		
	Description	Catalogue number	Ref number	Description	Catalogue number	Ref number
MP350A4R	Square Body fuse	D123GB75V630TF	C098557	American round fuse	A70QS600-4	Y219993
MP350A5R MP350A6R					A100P600-4	A217373
MP420A4R		D123GB75V800TF	J220946		A70QS800-4	Z213830
MP470A5R MP470A6R		D2122GD75V900TF	T220955	American round fuses 2 in parallel	A100P1000-4 (x2)	Y217371 (x2)
MP550A4R					A70QS450-4 (x2)	F214848 (x2)
MP700A4R		D2123GB75V12CTF	D098558		A70QS600-4 (x2)	Y219993 (x2)
MP700A5R MP700A6R				American round fuse	A100P1200-4	N218397
MP825A4R				American round fuses 2 in parallel	A70QS800-4 (x2)	Z213830 (x2)
MP825A5R MP825A6R				American round fuse	A100P1200-4	N218397
MP900A4R		D2123GB75V14CTF	B090483	American round fuses 3 in parallel	A70QS600-4 (x3)	Y219993 (x3)
MP1200A4R	Square Body fuses 3 in parallel	PC73UD13C630TF (x3)	Q300509 (x3)	American round fuses 3 in parallel	A70QS700-4 (x3)	E202772 (x3)
MP1200A5R MP1200A6R					A100P700-4 (x3)	T223163 (x3)
MP1850A4R	Square Body fuses 4 in parallel	PC73UD13C700TF (x4)	R300510 (x4)	American round fuses 5 in parallel	A70QS600-4 (x5)	Y219993 (x5)
MP1850A5R MP1850A6R					A100P600-4 (x5)	A217373 (x5)

NOTE

The use of the A100P series fuses is limited to applications with L/R time constants of 30ms or less.

DC fusing is only required on four quadrant (R) drives.

4.6.2   Alternative fusing

Please refer to section 12.2.2 *Alternative fusing* on page 157.

Table 4-16 Mentor MP size 1 drive thyristor I²t rating for semiconductor fusing

Model		Thyristor I²t (A²s)
Field fuses		400
MP25A4	MP25A5	1030
MP45A4	MP45A5	3600
MP75A4	MP75A5	15000
MP25A4(R)	MP25A5(R)	1030
MP45A4(R)	MP45A5(R)	3600
MP75A4(R)	MP75A5(R)	15000
MP105A4	MP105A5	
MP155A4	MP155A5	
MP210A4	MP210A5	
MP105A4(R)	MP105A5(R)	80000
MP155A4(R)	MP155A5(R)	
MP210A4(R)	MP210A5(R)	

Table 4-17 Mentor MP size 2 drive thyristor I²t ratings for semiconductor fusing

Model			Thyristor I²t (A²s)
Field fuses			400
MP350A4(R)	MP420A4(R)	MP550A4(R)	320000
MP350A6(R)	MP470A5(R)	MP470A6(R)	281000
MP700A4(R)	MP825A4(R)	MP900A4(R)	1050000
MP700A6(R)	MP825A5(R)	MP825A6(R)	1200000
MP1200A4(R)	MP1200A5(R)	MP1200A6(R)	2720000
MP1850A4(R)	MP1850A5(R)	MP1850A6(R)	

4.6.3 Internal field fuses

The internal field fuses provide protection to the field controller. The fuses can rupture if there is a fault in the field circuit. The user should check the internal field fuses if the drive is tripping field loss (FdL) and the field controller is enabled.

⚠️ **WARNING** Isolate the power before removing the internal field fuses.

Figure 4-9 Removing the internal field fuses

Insert a flat-head screwdriver into the groove as shown above and lever downwards to remove the fuse cover. Refer to section 4.6.1 *Ferraz Shawmut fuses* on page 40 for fuse types.

4.7 External suppressor resistor

The Mentor MP range of drives provide internal suppression of the voltage overshoots created by commutation of the thyristors in the power stage during the operation of the product. The internal suppression is suitable for typical applications using recommended line reactors as defined in section 4.4 *Line reactors* on page 37. The Mentor MP drives provide the facility to allow for extra suppression for applications at the boundaries of the drive's operating area. Applications which may require an external suppression resistor to be installed have some or all the following characteristics:

1. Supplies rated ≥10kA with less than the recommend line reactance.
2. High line-to-line voltage

The recommended external suppressor resistor selections are shown in Table 4-18.

Table 4-18 Recommended external suppressor resistors

Model	Resistance kΩ	Power rating W	Voltage rating V	Isolation voltage Vrms
MP25A4(R)				
MP45A4(R)				
MP75A4(R)				
MP105A4(R)	8.2	150	1100	2500
MP155A4(R)				
MP210A4(R)				
MP25A5(R)				
MP45A5(R)				
MP75A5(R)				
MP105A5(R)	15	150	1400	2500
MP155A5(R)				
MP210A5(R)				
MP350A4(R)				
MP420A4(R)				
MP550A4(R)				
MP700A4(R)				
MP825A4(R)	4.1	300	1100	2500
MP900A4(R)				
MP1200A4(R)				
MP1850A4(R)				
MP350A5(R) MP350A6(R)				
MP470A5(R) MP470A6(R)				
MP700A5(R) MP700A6(R)				
MP825A5(R) MP825A6(R)	8.6	300	1600	2500
MP1200A5(R) MP1200A6(R)				
MP1850A5(R) MP1850A6(R)				

The following diagram shows the location of the external suppressor resistor terminals above the L1 and L2 terminals:

Figure 4-10   Location of external suppressor resistor terminals on size 1 drives

To external suppression resistor

Figure 4-11   Location of external suppressor resistor terminals on size 2 drives

To external suppression resistor

Figure 4-12   Removal of bucket suppressor terminals cover on size 2C and 2D

1. Remove the 2 x M4 x 16 screws using a pozi drive screwdriver.
2. Remove the bucket suppressor terminal cover.

Shielded cable should be used for bucket suppressor connections. For UL applications the cable should comply with UL1063 in accordance with UL508a.

For applications where the external suppressor resistance is chosen to be less than the recommended value for reasons of economy, it is essential that the resistance is not less than the minimum resistance shown in Table 4-19. However selecting a resistance less than the recommended value requires a more complex installation. The power rating of the resistor can be selected by the user according to the dissipation required for the application, up to a maximum of the values specified in Table 4-19.

Table 4-19   Minimum allowable external suppression resistance

Model		Resistance Ω
MP25A4(R)	MP25A5(R)	500 (maximum 150W)
MP45A4(R)	MP45A5(R)	
MP75A4(R)	MP75A5(R)	
MP105A4(R)	MP105A5(R)	
MP155A4(R)	MP155A5(R)	
MP210A4(R)	MP210A5(R)	
MP350A4(R)	MP350A5(R) MP350A6(R)	500 (maximum 300W)
MP420A4(R)	MP470A5(R) MP470A6(R)	
MP550A4(R)		
MP700A4(R)	MP700A5(R) MP700A6(R)	
MP825A4(R)	MP825A5(R) MP825A6(R)	
MP900A4(R)		
MP1200A4(R)	MP1200A5(R) MP1200A6(R)	
MP1850A4(R)	MP1850A5(R) MP1850A6(R)	

> **WARNING**
> Overload Protection
> When using an external suppressor resistor of a resistance or power rating less than the recommended rating, it is essential that an overload protection device is incorporated in the resistor circuit (refer to Figure 4-13).

> **WARNING**
> External suppressor resistor protection parameter settings
> The software provided by the Mentor MP provides overload protection. Failure to correctly configure Pr **11.62**, Pr **11.63** and Pr **11.64**, as described in the *Mentor MP Advanced User Guide* could lead to the resistor being overloaded.

Figure 4-13   Protection circuit for an external suppression resistor

4.8   Ground leakage

The ground leakage current depends on whether an external EMC filter is installed. Ground leakage currents for external EMC filters can be obtained from the manufacturers data sheet for the filter being used.

With no external EMC filter:

    <1mA

4.8.1   Use of residual current device (RCD)

There are three common types of ELCB / RCD:

1. AC - detects AC fault currents
2. A - detects AC and pulsating DC fault currents (provided the DC current reaches zero at least once every half cycle)
3. B - detects AC, pulsating DC and smooth DC fault currents
   - Type's A and AC should never be used with Mentor MP drives.
   - Type B must be used with all Mentor MP drives.

> **WARNING**
> Only type B ELCB / RCD are suitable for use with Mentor MP drives.

If an external EMC filter is used, a delay of at least 50ms should be incorporated to ensure spurious trips are not seen. The leakage current is likely to exceed the trip level if all of the phases are not energized simultaneously.

> **NOTE**
> The installer of the drive is responsible for ensuring compliance with the EMC regulations that apply where the drive is to be used.

4.9   EMC (Electromagnetic compatibility)

The Mentor MP meets immunity requirements (specified in Table 12-43 *Immunity compliance* on page 164) with no special precautions.

> **NOTE**
> Some special measures may be required in certain applications where the control cables are long or pass outside the building. See section 4.9.4 *Surge immunity of control circuits - long cables and connections outside a building* on page 47.

Radio frequency noise emission can occur from any of the power connections i.e. main and auxiliary A.C connections, armature and field output terminals.

For many applications in heavy industrial environments the noise emission is not sufficient to cause interference to other equipment.

When radio frequency emission must be limited the method used should be chosen to suit the situation.

4.9.1   Power drive systems standard

Compliance with the EMC standard for power drive systems (PDS) IEC 61800-3, EN 61800-3:2004 category C3

To meet this standard a standard armature filter and a standard field filter must be installed. See Table 4-20 *Mentor MP and EMC filter cross references* on page 47 for EMC filter cross references.

Shielded cables must be used for the field and armature and the shields must be clamped to ground at both ends. The standard is met for cable lengths up to 100m.

4.9.2   Generic standard and PDS category C2

Compliance with the generic emission standards for industrial environments category IEC 61000-6-4 and EN 61000-6-4:2007, and the PDS standard category C2.

To meet this standard a standard field filter and a high performance armature filter must be installed. See Table 4-20 *Mentor MP and EMC filter cross references* on page 47 for EMC filter cross references.

Shielded cables must be used for the field and armature and the shields must be clamped to ground at both ends. The standard is met for cable lengths up to 100m.

4.9.3 EMC filter information

Refer to Figure 4-1 on page 33 for the location of the optional EMC filter. See Table 4-20 for EMC filters that can be sourced directly from Epcos and Schaffner.

> **⚠ CAUTION**
> It is essential that line reactors be connected between the filter terminals and the power input terminals, as shown in Figure 4-1. Failure to observe this requirement could result in destruction of the thyristors.

Table 4-20   Mentor MP and EMC filter cross references

Model	Manufacturers part number					
	Schaffner armature standard	Schaffner armature high performance	Epcos armature high performance	Schaffner standard field filter	Epcos standard field filter
MP25A4(R)	FN3270H-80-35	FN3258-75-52	B84143-A66-R105	FN3280H-8-29	W62400-T1262D004
MP45A4(R)					
MP75A4(R)			*B84143-A90-R105		
MP105A4(R)	FN3270H-200-99	FN3258H-180-40	B84143BO250S080		
MP155A4(R)					
MP210A4(R)					
MP350A4(R)		FN3359-800-99		FN3280H-8-29	
MP420A4(R)					
MP550A4(R)					
MP700A4(R)					
MP825A4(R)					
MP900A4(R)					
MP1200A4(R)		FN3359-1600-99			
MP1850A4(R)					

* This filter is required if the input current to the Mentor MP will be greater than 66 Amperes.

Table 4-21   Emission compliance

Model	Filter		
	None	Field: Standard Armature: Standard	Field: Standard Armature:High performance
MP25A4(R)	C4	C3	C2
MP45A4(R)			
MP75A4(R)			
MP105A4(R)			
MP155A4(R)			
MP210A4(R)			
MP350A4(R)			
MP420A4(R)			
MP550A4(R)			
MP700A4(R)			
MP825A4(R)			
MP900A4(R)			
MP1200A4(R)			
MP1850A4(R)			

Key (shown in decreasing order of permitted emission level):

C4   EN 61800-3:2004 second environment, restricted distribution (Additional measures may be required to prevent interference)

C3   EN 61800-3:2004 second environment, unrestricted distribution

C2   Industrial generic standard EN 61000-6-4:2007
EN 61800-3:2004 first environment restricted distribution (The following caution is required by EN 61800-3:2004)

> **⚠ CAUTION**
> This is a product of the restricted distribution class according to IEC 61800-3. In a residential environment this product may cause radio interference in which case the user may be required to take adequate measures.

C1   Residential generic standard EN 61000-6-3:2007
EN 61800-3:2004 first environment unrestricted distribution

EN 61800-3:2004 defines the following:

* The first environment is one that includes residential premises. It also includes establishments directly connected without intermediate transformers to a low-voltage power supply network which supplies buildings used for residential purposes.
* The second environment is one that includes all establishments other than those directly connected to a low-voltage power supply network which supplies buildings used for residential purposes.
* Restricted distribution is defined as a mode of sales distribution in which the manufacturer restricts the supply of equipment to suppliers, customers or users who separately or jointly have technical competence in the EMC requirements of the application of drives.

4.9.4 Surge immunity of control circuits - long cables and connections outside a building

The input/output ports for the control circuits are designed for general use within machines and small systems without any special precautions.

In applications where they may be exposed to high-energy voltage surges, some special measures may be required to prevent malfunction or damage. Surges may be caused by lightning or severe power faults in association with grounding arrangements which permit high transient voltages between nominally grounded points. This is a particular risk where the circuits extend outside the protection of a building.

As a general rule, if the circuits are to pass outside the building where the drive is located, or if cable runs within a building exceed 30m, some additional precautions are advisable. One of the following techniques should be used:

1. Galvanic isolation, i.e. do not connect the control 0V terminal to ground. Avoid loops in the control wiring, i.e. ensure every control wire is accompanied by its return (0V) wire.
2. Shielded cable with additional power ground bonding. The cable shield may be connected to ground at both ends, but in addition the

ground conductors at both ends of the cable must be bonded together by a power ground cable (equipotential bonding cable) with cross-sectional area of at least 10mm^2, or 10 times the area of the signal cable shield, or to suit the electrical safety requirements of the plant. This ensures that fault or surge current passes mainly through the ground cable and not in the signal cable shield. If the building or plant has a well-designed common bonded network this precaution is not necessary.

3. Additional over-voltage suppression - for the analog and digital inputs and outputs, a zener diode network or a commercially available surge suppressor may be connected in parallel with the input circuit as shown in Figure 4-14 and Figure 4-15.

Figure 4-14   Surge suppression for digital and unipolar inputs and outputs

Figure 4-15   Surge suppression for analog and bipolar inputs and outputs

Surge suppression devices are available as rail-mounting modules, e.g. from Phoenix Contact:

Unipolar TT-UKK5-D/24 DC
Bipolar TT-UKK5-D/24 AC

These devices are not suitable for encoder signals or fast digital data networks because the capacitance of the diodes adversely affects the signal. Most encoders have galvanic isolation of the signal circuit from the motor frame, in which case no precautions are required. For data networks, follow the specific recommendations for the particular network.

4.10   Serial communications connections

The Mentor MP has a serial communications port (serial port) as standard supporting two wire EIA(RS)-485 communications. See Table 4-22 for the connection details for the RJ45 connector.

Figure 4-16   Serial communications port

Table 4-22   RJ45 connections

Pin	Function
1	120Ω Termination resistor
2	RX TX
3	0V isolated
4	+24V (100 mA)
5	0V isolated
6	TX enable
7	RX\ TX\
8	RX\ TX\(if termination resistors are required, jumper (link) to pin 1)
Shell	0V isolated

The communications port applies a two-unit load to the communications network. Connectors 2, 3, 7 and shield must always be made to the serial communications port. Shielded cable must be used at all times.

4.10.1   Isolation of the serial communications port

The serial PC communications port is double insulated and meets the requirements for SELV in EN 50178:1998.

> **⚠ WARNING**
> In order to meet the requirements for SELV in IEC 60950 (IT equipment) it is necessary for the control computer to be grounded. Alternatively, when a lap-top or similar device is used which has no provision for grounding, an isolation device must be incorporated in the communications lead.

An isolated serial communications lead has been designed to connect the drive to IT equipment (such as lap-top computers), and is available from the supplier of the drive. See Table 4-23 for details.

Table 4-23   Isolated serial comms lead details

Part number	Description
4500-0087	CT EIA232 Comms cable
4500-0096	CT USB Comms cable

The "isolated serial communications" lead has reinforced insulation as defined in IEC 60950 for altitudes up to 3,000m.

NOTE

When using the CT EIA232 Comms cable the available baud rate is limited to 19.2k baud.

4.10.2   Multi-drop network

The drive can be used on a 2 wire EIA485 multi-drop network using the drive's serial communications port when the following guidelines are adhered to.

Connections
The network should be a daisy chain arrangement and not a star, although short stubs to the drive are allowed.

The minimum connections are pins 2 (RX TX), 3 (isolated 0V), 7 (RX\ TX\) and the shield.

Pin 4 (+24V) on each drive can be connected together but there is no power sharing mechanism between drives and therefore the maximum power available is the same as a single drive. (If pin 4 is not linked to the other drives on the network and has an individual load then the maximum power can be taken from pin 4 of each drive.)

Termination resistors
If a drive is on the end of the network chain then pins 1 and 8 should be linked together. This will connect an internal 120Ω termination resistor between RXTX and RX\TX\. (If the end unit is not a drive or the user wishes to use their own termination resistor, a 120Ω termination resistor should be connected between RXTX and RX\TX\ at the end unit.)

If the host is connected to a single drive then termination resistors should not be used unless the baud rate is high.

CT Comms cable
The CT Comms cable can be used on a multi-drop network but should only be used occasionally for diagnostic and set up purposes. The network must also be made up entirely of Mentor MPs.

If the CT Comms cable is to be used, then pin 6 (TX enable) should be connected on all drives and pin 4 (+24V) should be linked to at least 1 drive to supply power to the converter in the cable.

Only one CT Comms cable can be used on a network.

4.11 Shield connections

These instructions must be followed to ensure suppression of radio-frequency emission and good noise immunity in the encoder circuit. It is recommended that the instructions for the connection of the encoder cable be followed closely and, to use the grounding bracket and grounding clamp supplied with the drive, to terminate the shields at the drive.

4.11.1 Motor cables

Use of a motor cable with an overall shield for the armature and field circuits may be needed if there is a critical EMC emissions requirement. Connect the shield of the motor cable to the ground terminal of the motor frame using a jumper (link) that is as short as possible and not exceeding 50mm (2in) long. A full 360° termination of the shield to the terminal housing of the motor is beneficial.

4.11.2 Encoder cable

To get the best results from shielding use cable with an overall shield and separate shields on individual twisted pairs. Refer to section 4.15 *Connecting an encoder* on page 54.

4.11.3 Control cables

It is recommended that signal cables should be shielded. This is essential for encoder cables, and strongly recommended for analog signal cables. For digital signals it is not necessary to use shielded cables within a panel, but this is recommended for external circuits, especially for inputs where a momentary signal causes a change of state (i.e. latching inputs).

4.11.4 Grounding hardware

The drive is supplied with a grounding bracket, to facilitate EMC compliance. This provides a convenient method for direct grounding of cable shields without the use of "pig-tails". Cable shields can be bared and clamped to the grounding bracket using metal clips, clamps or cable ties. Note that the shield must in all cases be continued through the clamp to the intended drive terminal in accordance with the connection details for the specific signal.

Figure 4-17 Fitting of grounding bracket

Loosen the ground connection (2 x M5 x 10) screws using T25 Torx driver and slide the grounding bracket in the direction shown. Once in place, re-tighten the ground connection M5 x 10 screws to 3Nm (2.21 lb ft).

A faston tab is located on the grounding bracket for the purpose of connecting the drive 0V to ground should the user wish to do so.

Figure 4-18 Grounding of signal cable shields using the grounding bracket

4.12 Connecting the fan on size 2C and 2D drives

A supply needs to be connected to the dual fan unit enclosed within the lower duct on Mentor MP size 2C and 2D. The fans can be configured for a 230Vac (factory setting) or 115Vac supply as shown below on the label next to the fan connections. When connecting the fan supply, the screws should be tightened with a maximum torque of 1.2 Nm (0.88 lb ft) to 2 Nm (1.47 lb ft).

Figure 4-19 Fan connection

FAN CONNECTIONS
115V   230V

Table 4-24   Fan supply specification

Fan configuration	Supply specification
230V	230V ±10%
115V	115V ±10%

Cabling should be 300V rated. Rated for at least 3A continuous in line with local wiring regulations. Cabling should be protected 3A non time delay fuses i.e. gG, Class CC or Class J and rated for at least 300V, in accordance with local wiring regulations.

4.13   Control connections

Refer to Figure 4-20 to understand the connection of the different power connections.

4.13.1   General

Table 4-25   The control connections consist of:

Function	Qty	Control parameters available	Terminal number
Differential analog input	1	Destination, offset, invert, scaling	5,6
Single ended analog input	2	Mode, offset, scaling, invert, destination	7,8
Analog output	2	Source, mode, scaling,	9,10
Digital input	3	Destination, invert, logic select	27, 28, 29
Digital input / output	3	Input / output mode select, destination / source, invert, logic select	24, 25, 26
Relay	2	Source, invert	51, 52, 53 61, 62, 63
Drive enable	1	Logic select	31
+10V User output	1		4
+24V User output	1		22
0V common	6		1, 3, 11, 21, 23, 30
+24V External input	1		2

Key:

Destination parameter: Indicates the parameter which is being controlled by the terminal / function

Source parameter: Indicates the parameter being output by the terminal

Mode parameter: Analog - indicates the mode of operation of the terminal, i.e. voltage 0-10V, current 4-20mA etc.

Digital - indicates the mode of operation of the terminal, i.e. positive / negative logic, open collector.

All analog terminal functions can be programmed in menu 7.

All digital terminal functions (including the relays) can be programmed in menu 8.

The setting of Pr **6.04** can cause the function of digital inputs T25 to T27 to change. For more information, refer to section 11.22.5 *Start / stop logic modes* on page 143.

⚠ **WARNING**	If the control circuits are to be connected to other circuits classified as Safety Extra Low Voltage (SELV) (e.g. to a personal computer), an additional isolating barrier must be included in order to maintain the SELV classification.

⚠ **CAUTION**	If any of the digital inputs (including the drive enable input) are connected in parallel with an inductive load (i.e. contactor or motor brake) then suitable suppression (i.e. diode or varistor) should be used on the coil of the load. If no suppression is used then over voltage spikes can cause damage to the digital inputs on the drive.

⚠ **WARNING**	The control circuits are isolated from the power circuits in the drive by basic insulation (single insulation) only. The installer must ensure that the external control circuits are insulated from human contact by at least one layer of insulation (supplementary insulation) rated for use at the AC supply voltage.

⚠ **WARNING**	Status relay contacts are over-voltage category II.

⚠ **WARNING**	A fuse or other over-current protection should be installed to the relay circuit.

Table 4-26   Control connection recommended cable sizes

Terminal	Minimum cable size	Maximum cable size
Machine armature	0.5mm² 20 AWG	5mm² 10 AWG
Auxiliary		
Control I/O		1.31mm² 16 AWG
Encoder		
Tachogenerator		2.5mm² 12 AWG
Status relays		

Figure 4-20   Default terminal functions

* Thermistor disabled by USA defaults.

4.14   General

4.14.1   Control terminal specification

1	0V common
Function	**Common connection for all external devices**

2	+24V external input
Function	**To supply the control circuit without providing a supply to the power stage**
Nominal voltage	+24.0Vdc
Minimum continuous operating voltage	+19.2Vdc
Maximum continuous operating voltage	+30.0Vdc
Minimum start-up voltage	21.6Vdc
Recommended power supply	60W 24Vdc nominal
Recommended fuse	3A, 50Vdc

3	0V common
Function	**Common connection for all external devices**

4	+10V user output
Function	**Supply for external analog devices**
Voltage tolerance	±1%
Nominal output current	10mA
Protection	Current limit and trip @12mA

	Precision reference analog input 1
5	**Non-inverting input**
6	**Inverting input**

Default function	Speed reference
Type of input	Bipolar differential analog (For single-ended use, connect terminal 6 to terminal 3)
Full scale voltage range	±10.0V ±1.5%
Absolute maximum voltage range	+30V, -18V relative to 0V
Working common mode voltage range	±16V
Input resistance	94kΩ
Resolution	14-bit plus sign
Monotonic	Yes
Dead band	None
Jumps	None
Maximum offset	±5mV
Maximum non linearity	±0.05% of Full scale voltage range
Maximum gain asymmetry	±0.2%
Input filter bandwidth single pole	~1kHz
Sampling period	250μs if configured with the destination as Pr **1.36**, Pr **1.37**, Pr **3.19** and Pr **4.08**. 4ms for all other destinations

7	**Analog input 2**

Default function	**Speed reference**
Type of input	Unipolar voltage and current
Mode controlled by...	Pr **7.11**
Operating in Voltage mode	
Full scale voltage range	±10.0V ±0.5%
Maximum offset	±33mV
Absolute maximum voltage	±36V relative to 0V
Input resistance	>94kΩ
Operating in current mode	
Current ranges	0 to 20mA ±5%, 20 to 0mA ±5%, 4 to 20mA ±5%, 20 to 4mA ±5%
Maximum offset	120μA
Absolute maximum voltage	±36V
Equivalent input resistance	~100Ω
Common to all modes	
Resolution	10 bit plus sign
Sampling period	250μs if configured with the destination as Pr **1.36**, Pr **1.37**, Pr **3.19** and Pr **4.08**. 4ms for all other destinations

8	**Analog input 3**

Default function	**Thermistor**
Type of input	Unipolar voltage, unipolar current and thermistor
Input mode controlled by...	Pr **7.15** (**in01, 0.81**)
Operating in Voltage mode	
Voltage range	±10.0V ±0.5%
Maximum offset	±33mV
Absolute maximum voltage range	±36V relative to 0V
Input resistance	>94kΩ
Operating in current mode	
Current ranges	0 to 20mA ±5%, 20 to 0mA ±5%, 4 to 20mA ±5%, 20 to 4mA ±5%
Maximum offset	120μA
Absolute maximum voltage	±36V max
Equivalent input resistance	~100Ω
Operating in thermistor input mode	
Internal pull-up voltage	<5V
Trip threshold resistance	3.3kΩ ±10%
Reset resistance	1.8kΩ ±10%
Short-circuit detection resistance	50Ω ±40%
Common to all modes	
Resolution	10 bit + sign
Sampling period	250μs if configured with the destination as Pr **1.36**, Pr **1.37**, Pr **3.19** and Pr **4.08**. 4ms for all other destinations

9	**Analog output 1**

10	**Analog output 2**

Terminal 9 default function	**Speed feedback**
Terminal 10 default function	**Current feedback**
Type of output	Bipolar single-ended voltage or unipolar single-ended current
Mode controlled by...	
Operating in Voltage mode (default)	
Full scale voltage range	±10V ±5%
Maximum offset	±40mV
Maximum output current	±35mA
Load resistance	1kΩ min
Protection	35mA max. Short circuit protection
Operating in current mode	
Current ranges	0 to 20mA ±5% 4 to 20mA ±5%
Maximum offset	350μA
Open circuit voltage	+15V
Load resistance	600Ω max
Common to all modes	
Resolution	10-bit plus sign
Sampling period	250μs if configured with the destination as Pr **1.36**, Pr **1.37**, Pr **3.19** and Pr **4.08**. 4ms for all other destinations

11	**0V common**
Function	**Common connection for all external devices**

21	**0V common**
Function	**Common connection for all external devices**

22	**+24V user output**
Function	**Supply for external digital devices**
Nominal output current	200mA (including all digital I/O)
Maximum output current	240mA (including all digital I/O)
Protection	Current limit and trip

23	**0V common**
Function	**Common connection for all external devices**

24	Digital I/O 1
25	Digital I/O 2
26	Digital I/O 3

Terminal 24 default function	AT SPEED output
Terminal 25 default function	DRIVE RESET input
Terminal 26 default function	RUN FORWARD input
Type	Positive or negative logic digital inputs, positive or negative logic push-pull outputs or open collector outputs
Input / output mode controlled by...	Pr **8.31**, Pr **8.32** and Pr **8.33**
Operating as an input	
Logic mode controlled by...	Pr **8.29**
Absolute maximum applied voltage range	+30V, -18V relative to 0V
Impedance	6kΩ
Input thresholds	10.0V ±0.8V
Operating as an output	
Open collector outputs selected	Pr **8.30**
Nominal maximum output current	200mA (total including terminal 22)
Maximum output current	240mA (total including terminal 22)
Common to all modes	
Voltage range	0V to +24V
Sampling period	250μs if configured with the destination as Pr **6.35** or Pr **6.36**. 4ms for all other destinations

27	Digital input 4
28	Digital input 5
29	Digital input 6

Terminal 27 default function	RUN REVERSE input
Terminal 28 default function	LOCAL/REMOTE select
Terminal 29 default function	JOG SELECT input
Type of input	Negative or positive logic digital inputs
Logic mode controlled by...	Pr **8.29**
Voltage range	0V to +24V
Absolute maximum applied voltage range	+30V, -18V relative to 0V
Impedance	6kΩ
Input thresholds	10.0V ±0.8V
Sampling period	250μs if configured with the destination as Pr **6.35** or Pr **6.36**. 4ms for all other destinations

30	0V common
Function	Common connection for all external devices

31	ENABLE
Function	Drive enable
Type	Positive or negative logic digital input
Absolute maximum applied voltage range	+30V, -18V relative to 0V
Input threshold	10.0V ±0.8V
Sampling period	4ms

∧ **Drive commissioning output**

Function	Instantaneous armature current feedback
Type of output	Unipolar single-ended voltage
Full scale voltage range	10V ±5% (10V = 2 x Motor rated current)
Maximum offset	7mV
Protection	~25mA max. Short circuit protection to ground (0V).

Model			Full scale range of drive commissioning output
MP25A4(R)	MP25A5(R)		2.29 x Drive rated current (Pr **11.32**)
MP45A4(R)	MP45A5(R)		2.30 x Drive rated current (Pr **11.32**)
MP75A4(R)	MP75A5(R)		2.42 x Drive rated current (Pr **11.32**)
MP105A4(R)	MP105A5(R)		2.29 x Drive rated current (Pr **11.32**)
MP155A4(R)	MP155A5(R)		2.30 x Drive rated current (Pr **11.32**)
MP210A4(R)	MP210A5(R)		2.41 x Drive rated current (Pr **11.32**)
MP350A4(R)	MP350A5(R)	MP350A6(R)	2.73 x Drive rated current (Pr **11.32**)
MP420A4(R)			2.27 x Drive rated current (Pr **11.32**)
	MP470A5(R)	MP470A6(R)	3.34 x Drive rated current (Pr **11.32**)
MP550A4(R)			2.85 x Drive rated current (Pr **11.32**)
MP700A4(R)	MP700A5(R)	MP700A6(R)	2.24 x Drive rated current (Pr **11.32**)
MP825A4(R)	MP825A5(R)	MP825A6(R)	2.46 x Drive rated current (Pr **11.32**)
MP900A4(R)			2.25 x Drive rated current (Pr **11.32**)
MP1200A4(R)	MP1200A5(R)	MP1200A6(R)	3.44 x Drive rated current (Pr **11.32**)
MP1850A4(R)	MP1850A5(R)	MP1850A6(R)	2.23 x Drive rated current (Pr **11.32**)

41	Tachogenerator positive input
42	Tachogenerator negative input

Function	Speed feedback inputs for tachogenerator feedback device
Maximum voltage	300V
Feedback scaling controlled by	Pr **3.51** (**Fb02, 0.72**)
Sampling period	4ms

⚠ **WARNING** Status relay contacts are over-voltage category II.

⚠ **WARNING** A fuse or other over-current protection should be installed to the relay circuit.

51	**Relay 1 common**
52	**Relay 1 normally closed**
53	**Relay 1 normally open**

Default function	Drive OK indicator
Contact voltage rating	240Vac, installation over-voltage category II
Contact maximum current rating	5A AC 240V 5A DC 30V resistive load 0.5A DC 30V inductive load (L/R = 40ms)
Contact minimum recommended rating	12V, 100mA
Default contact position	Closed when power on and drive OK
Sampling period	4ms

61	**Relay 2 common**
62	**Relay 2 normally closed**
63	**Relay 2 normally open**

Default function	Contactor enable
Contact voltage rating	240Vac, installation over-voltage category II
Contact maximum current rating	5A AC 240V 5A DC 30V resistive load 0.5A DC 30V inductive load (L/R = 40ms)
Contact minimum recommended rating	12V, 100mA
Default contact position	Closed when AC or DC contactor is required to be closed.
Sampling period	4ms

NOTE

The relays are not UL rated when used with inductive loads.

Feedback device connections
Ab, Fd, Fr encoders

A	**Channel A, Frequency or Forward inputs**
A\	**Channel A\, Frequency\ or Forward\ inputs**
B	**Channel B, Direction or Reverse inputs**
B\	**Channel B\, Direction\ or Reverse\ inputs**
Z	**Marker pulse channel Z**
Z\	**Marker pulse channel Z**

Type	EIA 485 differential receivers
Maximum input frequency	500kHz
Line loading	<2 unit loads
Line termination components	100Ω for 2 - 5V range (switchable)
Working common mode range	+12V to –7V
Absolute maximum applied voltage relative to 0V	±25V
Absolute maximum applied differential voltage	±25V

+	**+ supply**
0V	**0V**

4.15 Connecting an encoder

Additional measures to prevent unwanted emission of radio frequency noise are only required where the installation is subject to specific requirements for radio frequency emission.

Encoder connections:

To ensure suppression of radio frequency emission, observe the following:

- Use an encoder with the correct impedance
- Use a cable with individually shielded twisted pairs.
- Connect the cable shields to 0V at both the drive and the encoder, using the shortest possible links (pig-tails).
- The cable should not be interrupted. If interruptions are unavoidable, ensure the absolute minimum length of "pig-tail" in the shield connections at each interruption. Use a connection method that provides substantial metallic clamps for the cable shield terminations.

The above applies where the encoder body is isolated from the motor and where the encoder circuit is isolated from the encoder body. Where there is no isolation between the encoder circuits and motor body, and in case of doubt, the following additional requirements must be observed to give the best possible noise immunity.

- The shields must be directly clamped to the encoder and to the drives grounding bracket. This may be achieved by clamping of the individual shields or by providing an additional overall shield that is clamped.

NOTE

The recommendations of the encoder manufacturer should also be adhered to for the encoder connections.

NOTE

In order to guarantee maximum noise immunity for any application double shielded cable as shown should be used.

In some cases single shielding of each pair of differential signals cables, or a single overall shield with individual shield on the thermistor connections is sufficient. In these cases all the shields should be connected to ground and 0V at both ends.

If the 0V is required to be left floating a cable with individual shields and an overall shield must be used.

Figure 4-21 and Figure 4-22 illustrate the preferred construction of cable and the method of clamping. The outer sheath of the cable should be stripped back enough to allow the clamp to be installed. The shield must not be broken or opened at this point. The clamps should be installed close to the drive or feedback device, with the ground connections made to a ground plate or similar metallic ground surface.

Figure 4-21   Feedback cable, twisted pair

Figure 4-22 Feedback cable connections

Table 4-27 Encoder types

Pr 3.38 (Fb07, 0.77) setting	Description
Ab (0)	Quadrature incremental encoder with or without marker pulse
Fd (1)	Incremental encoder with frequency pulses and direction, with or without marker pulse
Fr (2)	Incremental encoder with forward pulses and reverse pulses, with or without marker pulse

5 Getting started

This chapter introduces the user interfaces, menu structure and security level of the drive.

5.1 Understanding the display

There are two types of keypad available for the Mentor MP. The SM-Keypad has an LED display, and the MP-Keypad has an LCD display.

5.1.1 SM-Keypad (LED)

The display consists of two horizontal rows of 7 segment LED displays.

The upper display shows the drive status or the current menu and parameter number being viewed.

The lower display shows the parameter value or the specific trip type.

Figure 5-1 SM-Keypad

5.1.2 MP-Keypad (LCD)

The display consists of three lines of text.

The top line shows the drive status or the current menu and parameter number being viewed on the left, and the parameter value or the specific trip type on the right.

The lower two lines show the parameter name or the help text.

Figure 5-2 MP-Keypad

NOTE

The red stop ⊘ button is also used to reset the drive.

5.2 Keypad operation

Control buttons

The keypad consists of:

1. Joypad - used to navigate the parameter structure and change parameter values.
2. Mode button - used to change between the display modes – parameter view, parameter edit, status.
3. Three control buttons - used to control the drive if keypad mode is selected.
4. Help button (MP-Keypad only) - displays text briefly describing the selected parameter.

The Help button toggles between other display modes and parameter help mode. The up and down functions on the joypad scroll the help text to allow the whole string to be viewed. The right and left functions on the joypad have no function when help text is being viewed.

The display examples in this section show the SM-Keypad, seven segment, LED display. The examples are the same for the MP-Keypad, The exceptions is that the information displayed on the lower row on the SM-Keypad is displayed on the right hand side of the top row on the MP-Keypad.

Figure 5-3   Display modes

* Can only be used to move between menus if L2 access has been enabled Pr **11.44** (**SE14, 0.35**)
Time-out defined by Pr **11.41 (default value = 240s).

Figure 5-4   Mode examples

> ⚠ **WARNING**
> Do not change parameter values without careful consideration; incorrect values may cause damage or a safety hazard.

NOTE

When changing the values of parameters, make a note of the new values in case they need to be entered again.

NOTE

For new parameter-values to apply after the AC supply to the drive is interrupted, new values must be saved (section 5.8 *Saving parameters* on page 61).

5.3 Menu 0 (sub block)

Menu 0 can be accessed by 2 methods:

1. Pr **11.44** (**SE14, 0.35**) = 0. Sub block mode.
2. Pr **11.44** (**SE14, 0.35**) <>0. Linear mode.

Menu 23 contains the parameters to allow menu 0 to be customized in sub block mode. The first sub block is a user defined area (USEr) which is configured by the parameters in menu 22. As default there are no parameters configured to the user sub block and so it is empty. The next 7 sub blocks are pre-defined. Access to the pre-defined blocks is enabled or disabled by Pr **23.03** to Pr **23.09**.

Movement between sub blocks is achieved with the left and right keys.

Pr **23.01** contains all the sub block headers.

Table 5-1 and Figure 5-5 show the result of the direction keys when Pr **11.44** (**SE14, 0.35**) is set to L1 (0). When Pr **11.44** (**SE14, 0.35**)is not 0 the left and right keys will allow access to the advance parameter set and menu 0 will become a linear menu.

Table 5-1 Keypad navigation

Starting location	Action	Finishing location
Header	Right	Next header
	Left	Previous header
	Up	First parameter in header block
	Down	Last parameter in header block
Parameter	Right	Next header
	Left	Previous header
	Up	Next parameter in header block
	Down	Previous parameter in header block

When moving to the user block header, the user block header is only displayed if there are some valid parameters in the block. When moving between pre-defined header blocks the pre-defined header block is only displayed if the pre-defined block is enabled.

When moving between parameters within a block, only valid parameters are displayed.

Figure 5-5 Sub block navigation

Coding

The coding defines the attributes of the parameter as follows.

Coding	Attribute
{X.XX}	Copied Mneu 0 or advanced parameter
Bit	1 bit parameter: 'On' or 'OFF' on the display
Bi	Bipolar parameter
Uni	Unipolar parameter
Txt	Text: the parameter uses text strings instead of numbers.
SP	Spare: not used
FI	Filtered: some parameters which can have rapidly changing values are filtered when displayed on the drive keypad for easy viewing.
DE	Destination pointer parameter: This parameter can be used to set up the location (i.e. menu/parameter number) where the destination data is to be routed.
VM	Variable maximum: the maximum of this parameter can vary.
DP	Decimal place: indicates the number of decimal places used by this parameter.
ND	No default: when defaults are loaded (except when the drive is manufactured or on EEPROM failure) this parameter is not modified.
RA	Rating dependant: this parameter is likely to have different values and ranges with drives of different voltage and current ratings. Parameters with this attribute will not be transferred to the destination drive by a SMARTCARD when the rating of the destination drive is different from the source drive if the drive voltage ratings are different or the file is a parameter file. However, the value will be transferred if only the current rating is different and the file is a differences from default type file.
NC	Not copied: not transferred to or from SMARTCARD during copying.
NV	Not visible: not visible on the keypad.
PT	Protected: cannot be used as a destination.
US	User save: saved in drive EEPROM when the user initiates a parameter save.
RW	Read/write: can be written by the user.
RO	Read only: can only be read by the user
BU	Bit default one/unsigned: Bit parameters with this flag set to one have a default of one (all other bit parameters have a default of zero. Non-bit parameters are unipolar if this flag is one.
PS	Power-down save: parameter automatically saved in drive EEPROM when the under volts (UV) trip occurs. Power-down save parameters are also saved in the drive when the user initiates a parameter save.

23.01	**Sub block headers**							
RO	Txt	NC					PT	BU
⇕	USEr (0), SEt UP (1), diAGnoS (2), triPS (3), SP LOOP (4), Fb SP (5), SintEr (6), inPut (7)			⇒	USEr (0)			

Defines the sub block headers. Can be used by the MP-Keypad to display the same strings as the SM-Keypad.

23.02	Bianry sum of pre-defined sub block enables

RO	NC				PT	BU
↕	0 to 127		⇨		0	

The OR of Pr **23.03** to Pr **23.09**. To be used by the MP-Keypad.

Parameter	Value
23.03	1
23.04	2
23.05	4
23.06	8
23.07	16
23.08	32
23.09	64

23.03 - 23.09	Pre-defined sub block enable

RW	Bit					US	BU
↕	0 to1		⇨			1	

When this parameter is set to 1 the associated pre-defined sub block is accessible. When this parameter is 0 the associated pre-defined block is bypassed.

Parameter	Description	Display
23.03	Set up	SEt UP
23.04	Diagnostic	diAGnoS
23.05	Trips	triPS
23.06	Speed loop	SP LOOP
23.07	Serial interface	SintEr
23.08	Speed feedback	Fb SP
23.09	IO	InPut

5.4 Pre-defined sub blocks

Menu 0	Parameter	Description	Display
0.01 to **0.20**		Configured by Pr **22.01** to Pr **22.20**	

Set-up

Menu 0	Parameter	Description	Display
0.21	**1.00**	Parameter 0	**SE00**
0.22	**1.07**	Minimum reference clamp	**SE01**
0.23	**1.06**	Maximum reference clamp	**SE02**
0.24	**2.11**	Acceleration rate	**SE03**
0.25	**2.21**	Deceleration rate	**SE04**
0.26	**1.14**	Reference selector	**SE05**
0.27	**5.09**	Armature rated voltage	**SE06**
0.28	**5.07**	Motor rated current	**SE07**
0.29	**5.08**	Base speed	**SE08**
0.30	**11.42**	Parameter copying	**SE09**
0.31	**5.70**	Rated field current	**SE10**
0.32	**5.73**	Rated field voltage	**SE11**
0.33	**5.77**	Enable field control	**SE12**
0.34	**5.12**	Autotune	**SE13**
0.35	**11.44**	Security status	**SE14**

Diagnostic

Menu 0	Parameter	Description	Display
0.36	**1.01**	Speed reference selected	**di01**
0.37	**1.03**	Pre-ramp reference	**di02**
0.38	**2.01**	Post ramp reference	**di03**
0.39	**3.01**	Final speed reference	**di04**
0.40	**3.02**	Speed feedback	**di05**
0.41	**3.04**	Speed controller output	**di06**
0.42	**4.03**	Torque demand	**di07**
0.43	**4.01**	Current magnitude	**di08**
0.44	**5.56**	Field current feedback	**di09**
0.45	**5.02**	Armature voltage	**di10**
0.46	**1.11**	Reference enabled indicator	**di11**
0.47	**1.12**	Reverse selected indicator	**di12**
0.48	**1.13**	Jog selected indicator	**di13**
0.49	**11.29**	Software version	**di14**
0.50	**0.00**	Spare	

Trips

Menu 0	Parameter	Description	Display
0.51	**10.20**	Trip 0	**tr01**
0.52	**10.21**	Trip 1	**tr02**
0.53	**10.22**	Trip 2	**tr03**
0.54	**10.23**	Trip 3	**tr04**
0.55	**10.24**	Trip 4	**tr05**
0.56	**10.25**	Trip 5	**tr06**
0.57	**10.26**	Trip 6	**tr07**
0.58	**10.27**	Trip 7	**tr08**
0.59	**10.28**	Trip 8	**tr09**
0.60	**10.29**	Trip 9	**tr10**

Speed loop

Menu 0	Parameter	Description	Display
0.61	**3.10**	Speed controller proportional gain	**SP01**
0.62	**3.11**	Speed controller integral gain	**SP02**
0.63	**3.12**	Speed controller differential feedback gain	**SP03**
0.64	**0.00**	Spare	
0.65	**0.00**	Spare	

Serial interface

Menu 0	Parameter	Description	Display
0.66	**11.25**	Baud rate	**Si01**
0.67	**11.23**	Serial address	**Si02**
0.68	**0.00**	Spare	
0.69	**0.00**	Spare	
0.70	**0.00**	Spare	

Speed feedback

Menu 0	Parameter	Description	Display
0.71	3.26	Speed feedback selector	**Fb01**
0.72	3.51	Tachometer rating (V/1000rpm)	**Fb02**
0.73	3.53	Tachometer input mode	**Fb03**
0.74	3.52	Tachometer speed feedback	**Fb04**
0.75	3.34	Drive encoder lines per revolution	**Fb05**
0.76	3.36	Encoder supply	**Fb06**
0.77	3.38	Encoder type	**Fb07**
0.78	3.39	Encoder termination select	**Fb08**
0.79	3.27	Encoder speed feedback	**Fb09**
0.80	0.00	Spare	

IO

Menu 0	Parameter	Description	Display
0.81	7.15	Analog input 3 mode	**in01**
0.82	7.01	Analog input 1	**in02**
0.83	7.02	Analog input 2	**in03**
0.84	7.03	Analog input 3	**in04**
0.85	8.01	I/O state 1	**in05**
0.86	8.02	I/O state 2	**in06**
0.87	8.03	I/O state 3	**in07**
0.88	8.04	I state 4	**in08**
0.89	8.05	I state 5	**in09**
0.90	8.06	I state 6	**in10**

For more information on the sub block function please refer to the *Mentor MP Advanced User Guide*.

5.5   Menu 0 (linear)

Menu 0 is used to bring together various commonly used parameters for basic easy set up of the drive.

Appropriate parameters are copied from the advanced menus into menu 0 and thus exist in both locations.

For further information, refer to section 5.3 *Menu 0 (sub block)* on page 58.

Figure 5-6   Menu 0 copying

5.6   Menu structure

The drive parameter structure consists of menus and parameters.

The drive initially powers up in sub menu mode. Once Level 2 access (L2) has been enabled (refer to Pr **11.44** (**SE14, 0.35**)) the left and right buttons are used to navigate between numbered menus.

For further information, refer to section 5.13 *Parameter access level and security* on page 62.

Figure 5-7   Menu structure

The menus and parameters roll over in both directions.

For example:

- If the last parameter is displayed, a further press will cause the display to roll-over and show the first parameter.
- When changing between menus the drive remembers which parameter was last viewed in a particular menu and will display that parameter. The menus and parameters roll over in both directions.

5.7 Advanced menus

The advanced menus consist of groups or parameters appropriate to a specific function or feature of the drive. Menus 0 to 23 can be viewed on both keypads. Menus 40 and 41 are specific to the MP-Keypad (LCD). Menus 70 to 91 can be viewed with an MP-Keypad (LCD) only when an SM-Applications module is installed.

Table 5-2 Advanced menu descriptions

Menu	Description	LED	LCD
0	Commonly used basic set up parameters for quick / easy programming	✓	✓
1	Speed reference	✓	✓
2	Ramps	✓	✓
3	Speed feedback and speed control	✓	✓
4	Torque and current control	✓	✓
5	Motor control including field regulator	✓	✓
6	Sequencer and clock	✓	✓
7	Analog I/O	✓	✓
8	Digital I/O	✓	✓
9	Programmable logic, motorized pot and binary sum	✓	✓
10	Status and trips	✓	✓
11	General drive set-up	✓	✓
12	Threshold detectors and variable selectors	✓	✓
13	Position control	✓	✓
14	User PID controller	✓	✓
15	Solutions Module set-up	✓	✓
16	Solutions Module set-up	✓	✓
17	Solutions Module set-up	✓	✓
18	Application menu 1	✓	✓
19	Application menu 2	✓	✓
20	Application menu 3	✓	✓
21	Second motor parameters	✓	✓
22	Menu 0 set-up - user area	✓	✓
23	Menu 0 sub block control	✓	✓
40	Keypad configuration menu	X	✓
41	User filter menu	X	✓
70	PLC registers	X	✓
71	PLC registers	X	✓
72	PLC registers	X	✓
73	PLC registers	X	✓
74	PLC registers	X	✓
75	PLC registers	X	✓
85	Timer function parameters	X	✓
86	Digital I/O parameters	X	✓
88	Status parameters	X	✓
90	General parameters	X	✓
91	Fast access parameters	X	✓

Key: ✓ = Available

X = Not available

Table 5-3 Menu 40 parameter descriptions

Parameter		Range(⇕)
40.00	Parameter 0	0 to 32767
40.01	Language selection	English (0), Custom (1), French (2), German (3), Spanish (4), Italian (5)
40.02	Software version	999999
40.03	Save to flash	Idle (0), Save (1), Restore (2), Default (3)
40.04	LCD contrast	0 to 31
40.05	Drive and attribute database upload was bypassed	Updated (0), Bypass (1)
40.06	Browsing favourites control	Normal (0), Filter (1)
40.07	Keypad security code	0 to 999
40.08	Communication channel selection	Disable (0), Slot1 (1), Slot2 (2), Slot3 (3), Slave (4), Direct (5)
40.09	Hardware key code	0 to 999
40.10	Drive node ID (Address)	0 to 255
40.11	Flash ROM memory size	4Mbit (0), 8Mbit (1)
40.19	String database version number	0 to 999999
40.20	Screen saver strings and enable	None (0), Default (1), User (2)
40.21	Screen saver interval	0 to 600
40.22	Turbo browse time interval	0 to 200ms
40.23	Product identification	Unidrive SP (0), Commander SK (1), Mentor MP (2), Affinity (4), Digitax ST (5)

Table 5-4 Menu 41 parameter descriptions

Parameter		Range(⇕)
41.00	Parameter 0	0 to 32767
41.01 to 41.50	Browsing filter source F01 to F50	Pr **0.00** to Pr **22.99**
41.51	Browsing favourites control	Normal (0), Filter (1)

5.8 Saving parameters

When changing a parameter in Menu 0, the new value is saved when pressing the (M) Mode button to return to parameter view mode from parameter edit mode.

If parameters have been changed in the advanced menus, then the change will not be saved automatically. A save function must be carried out.

Procedure

1. Enter SAVE in Pr **xx.00**
2. Either:

    • Press the red (🔻)reset button

    • Toggle the reset digital input, or

    • Carry out a drive reset through serial communications by setting Pr **10.38** to 100 (ensure that Pr **xx.00** returns to 0).

5.9 Restoring parameter defaults

Restoring parameter defaults by this method saves the default values in the drive's memory. (Pr **11.44** (**SE14, 0.35**) and Pr **11.30** are not affected by this procedure).

Procedure

1. Ensure the drive is not enabled, i.e. terminal 31 is open or Pr **6.15** is OFF (0)
2. Select Eur or USA in Pr **xx.00**.

3. Either:

    - Press the red ⊘ reset button
    - Toggle the reset digital input, or
    - Carry out a drive reset through serial communications by setting Pr **10.38** to 100 (ensure that Pr. **xx.00** returns to 0).

5.10 Differences between European and USA defaults

Pr	Description	Default
2.06	S ramp enable	Eur: OFF (0), USA: On (1)
3.51	Tachometer voltage rating **(Fb02, 0.72)**	Eur: 60.00, USA: 50.00
5.09, **21.09**	Armature rated voltage **(SE06, 0.27)**	480V drive Eur: 440, USA:500
5.28	Field weakening compensation disable	Eur: OFF (0), USA On (1)
5.59, **21.08**	Back emf set point	480V drive Eur: 440, USA:500
5.65	Economy timeout	Eur: OFF (0), USA: On (1)
5.70, **21.24**	Rated field current **(SE10, 0.31)**	Size 1: Eur: 2.00, USA: 8.00 Size 2A & B Eur: 3.00, USA: 20.00 Size 2C & D Eur: 5.00, USA 20.00
5.73, **21.23**	Rated field voltage **(SE11, 0.32)**	Eur: 360, USA: 300
5.75	Field voltage mode	Eur: OFF (0), USA: On (1)
7.15	Analog input 3 mode **(in01, 0.81)**	Eur: th (8), USA: VOLt (6)

5.11 Displaying parameters with non-default values only

Select dIS.dEf in Pr **xx.00**, the only parameters that will be visible to the user will be those containing a non-default value. This function does not require a drive reset to become active. To deactivate this function, return to Pr **xx.00** and enter a value of 0.

Please note that this function can be affected by the access level enabled. You must refer to section 5.13 *Parameter access level and security* for more information regarding access level.

5.12 Displaying destination parameters only

Select dIS.dESt in Pr **xx.00**, the only parameters that will be visible to the user will be destination parameters. This function does not require a drive reset to become active. To deactivate this function, return to Pr **xx.00** and enter a value of 0.

Please note that this function can be affected by the access level enabled You must refer to section 5.13 *Parameter access level and security* for further information regarding access levels.

5.13 Parameter access level and security

The parameter access levels determine whether the user has access to Menu 0 (in sub block mode) only or to all of the advanced menus (Menus 1 to 23), in addition to Menu 0 (in linear mode).

The user security determines whether the access to the user is read only or read write.

The user security and the parameter access level can operate independently of each other as shown in Table 5-5 .

Table 5-5 User security and parameter access levels

Parameter access level	User security	Menu 0 status	Advanced menus status
L1	Open	Sub block RW	Not visible
L1	Closed	Sub block RO	Not visible
L2	Open	Linear RW	RW
L2	Closed	Linear RO	RO

RW = Read / write access   RO = Read only access

The default settings of the drive are parameter access level L1 and User Security Open, i.e. read / write access to Menu 0 with the advanced menus, not visible

5.13.1 User security

The user security, when set, prevents write access to any of the parameters (other than Pr **11.44** (**SE14, 0.35**) Access Level) in any menu.

Figure 5-8 User security open

User security open - All parameters: Read / Write access

Pr 0.00	Pr 1.00	....	Pr 22.00	Pr 23.00
Pr 0.01	Pr 1.01	....	Pr 22.01	Pr 23.01
Pr 0.02	Pr 1.02	....	Pr 22.02	Pr 23.02
Pr 0.03	Pr 1.03	....	Pr 22.03	Pr 23.03
		....		
		....		
Pr 0.89	Pr 1.50	....	Pr 22.39	Pr 23.10
Pr 0.90	Pr 1.51	....	Pr 22.40	Pr 23.11

User security closed - All parameters: Read Only access (except Pr **11.44** (**SE14, 0.35**)

Pr 0.00	Pr 1.00	....	Pr 22.00	Pr 23.00
Pr 0.01	Pr 1.01	....	Pr 22.01	Pr 23.01
Pr 0.02	Pr 1.02	....	Pr 22.02	Pr 23.02
Pr 0.03	Pr 1.03	....	Pr 22.03	Pr 23.03
		....		
		....		
Pr 0.49	Pr 1.50	....	Pr 22.39	Pr 23.10
Pr 0.90	Pr 1.51	....	Pr 22.40	Pr 23.11

5.13.2 Setting user security

Enter a value between 1 and 999 in Pr **11.30** and press the Ⓜ button; the security code has now been set to this value. To activate the security, the access level must be set to Loc in Pr **11.44** (**SE14, 0.35**). When the drive is reset, the security code will have been activated and the drive returns to access level L1. The value of Pr **11.30** will return to 0 in order to hide the security code. At this point, the only parameter that can be changed by the user is the access level Pr **11.44** (**SE14, 0.35**).

5.13.3 Unlocking user security

Select a read write parameter to be edited and press the Ⓜ button; the upper display will now show CodE.

Use the arrow buttons to set the security code and press the Ⓜ button. With the correct security code entered, the display will revert to the parameter selected in edit mode. If an incorrect security code is entered the display will revert to parameter view mode.

To lock the user security again, set Pr **11.44** (**SE14, 0.35**) to Loc and press the Ⓜ reset button.

5.13.4 Disabling user security

Unlock the previously set security code as detailed above. Set Pr **11.30** to 0 and press the ⓜ button. The user security has now been disabled, and will not have to be unlocked each time the drive is powered up to allow read / write access to the parameters.

5.14 Serial communications

5.14.1 Introduction

The Mentor MP has a standard 2-wire EIA485 interface (serial communications interface) which enables all drive set-up, operation and monitoring to be carried out with a PC or controller if required. Therefore, it is possible to control the drive entirely by serial communications without the need for a keypad or other control cabling. The drive supports two protocols selected by parameter configuration:

- Modbus RTU
- CT ANSI

Modbus RTU has been set as the default protocol, as it is used with the PC-tools commissioning/start-up software as provided on the CD ROM.

The serial communications port of the drive is a RJ45 socket, which is isolated from the power stage and the other control terminals (see section 4.10 *Serial communications connections* on page 48 for connection and isolation details).

The communications port applies a 2 unit load to the communications network.

USB/EIA232 to EIA485 Communications

An external USB/EIA232 hardware interface such as a PC cannot be used directly with the 2-wire EIA485 interface of the drive. Therefore a suitable converter is required.

Suitable USB to EIA485 and EIA232 to EIA485 isolated converters are available from Control Techniques as follows:
- CT USB Comms cable (CT Part No. 4500-0096)
- CT EIA232 Comms cable (CT Part No. 4500-0087)

When using one of the above converters or any other suitable converter with the Mentor MP, it is recommended that no terminating resistors be connected on the network. It may be necessary to 'link out' the terminating resistor within the converter depending on which type is used. The information on how to link out the terminating resistor will normally be contained in the user information supplied with the converter.

5.14.2 Serial communications set-up parameters

The following parameters need to be set according to the system requirements.

11.24	Serial mode						
RW	Txt					US	
⇕	AnSI (0), rtU (1), Lcd (2)			⇨	rtU (1)		

This parameter defines the communications protocol used by the 485 comms port on the drive. This parameter can be changed via the drive keypad, via a Solutions Module or via the comms interface itself. If it is changed via the comms interface, the response to the command uses the original protocol. The master should wait at least 20ms before sending a new message using the new protocol. (Note: ANSI uses 7 data bits, 1 stop bit and even parity; Modbus RTU uses 8 data bits, 2 stops bits and no parity.)

Comms value	String	Communications mode
0	AnSI	ANSI
1	rtU	Modbus RTU protocol
2	Lcd	Modbus RTU protocol, but with a MP-Keypad only

ANSIx3.28 protocol

Full details of the CT ANSI communications protocol are in the *Mentor MP Advanced User Guide*.

Modbus RTU protocol

Full details of the CT implementation of Modbus RTU are given in the *Mentor MP Advanced User Guide*.

Modbus RTU protocol, but with an MP-Keypad only

This setting is used for disabling communications access when the MP-Keypad is used as a hardware key.

Si01 {0.66/11.25}	Baud rate						
RW	Txt					US	
⇕	300 (0), 600 (1), 1200 (2), 2400 (3), 4800 (4), 9600 (5), 19200 (6), 38400 (7), 57600 (8)*, 115200 (9)*		⇨		19200 (6)		

Used in all comms modes to define the baud rate.

Parameter value	String/baud rate
0	300
1	600
2	1200
3	2400
4	4800
5	9600
6	19200
7	38400
8*	57600
9*	115200

* Only applicable to Modbus RTU mode

This parameter can be changed via the drive keypad, via a Solutions Module or via the comms interface itself. If it is changed via the comms interface, the response to the command uses the original baud rate. The master should wait at least 20ms before sending a new message using the new baud rate.

NOTE

When using the CT EIA232 Comms cable the available baud rate is limited to 19.2k baud.

Si02 {0.67/11.23}	Serial address						
RW	Txt					US	
⇕	0 to 247			⇨	1		

Used to define the unique address for the drive for the serial interface. The drive is always a slave.

ANSI

When the ANSI protocol is used the first digit is the group and the second digit is the address within a group. The maximum permitted group number is 9 and the maximum permitted address within a group is 9. Therefore, Pr **11.23** (**Si02**, **0.67**) is limited to 99 in this mode. The value 00 is used to globally address all slaves on the system, and x0 is used to address all slaves of group x, therefore these addresses should not be set in this parameter.

Modbus RTU

When the Modbus RTU protocol is used addresses between 0 and 247 are permitted. Address 0 is used to globally address all slaves, and so this address should not be set in this parameter.

Mentor MP User Guide
Issue: 4

6   Basic parameters

The pre-defined sub blocks contain commonly used parameters for basic set-up of the Mentor MP. All parameters in the pre-defined sub blocks appear in other menus in the drive. (Denoted by {x.xx} in Table 6-1.)

Table 6-1   Pre-defined sub block parameters

Parameter		Range($\updownarrow$)	Default($\Rightarrow$)	Type					
SE00	Parameter zero {0.21, x.00}	0 to 32,767	0	RW	Uni				
SE01	Minimum reference clamp {0.22, 1.07}	±SPEED_LIMIT_MAX rpm	0.0	RW	Bi			PT	US
SE02	Maximum reference clamp {0.23, 1.06}	SPEED_LIMIT_MAX rpm	1000.0	RW	Bi				US
SE03	Acceleration rate {0.24, 2.11}	0 to MAX_RAMP_RATE s/(SE02 [Pr **0.23**, **1.06**] or Pr **2.39**)	5.000	RW	Uni				US
SE04	Deceleration rate {0.25, 2.21}	0 to MAX_RAMP_RATE s/(SE02 [Pr **0.23**, **1.06**] or Pr **2.39**)	5.000	RW	Uni				US
SE05	Reference selector {0.26, 1.14}	A1.A2 (0), A1.Pr (1), A2.Pr (2), Pr (3), PAd (4), Prc (5), PAd rEF (6)	A1.A2 (0)	RW	Txt				US
SE06	Armature rated voltage {0.27, 5.09}	0 to ARMATURE_VOLTAGE_MAX Vdc	For 480V drive: 440 Eur 500 USA For 575V drive: 630 Eur 630 USA For 690V drive: 760 Eur 760 USA	RW	Uni	RA			US
SE07	Motor rated current {0.28, 5.07}	0 to RATED_CURRENT_MAX A	RATED_CURRENT_MAX	RW	Uni	RA			US
SE08	Base speed {0.29, 5.08}	0.0 to 10,000.0 rpm	1000.0	RW	Uni				US
SE09	Parameter copying {0.30, 11.42}	nonE (0), rEAd (1), ProG (2), Auto (3), boot (4)	nonE (0)	RW	Txt			*	NC
SE10	Rated field current {0.31, 5.70}	0 to FIELD_CURRENT_SET_MAX	Size 1: Eur 2A, USA 8A Size 2A/B: Eur 3A, USA 20A Size 2C/D: Eur 5A, USA 20A	RW	Uni			PT	US
SE11	Rated field voltage {0.32, 5.73}	0 to 500 Vdc	Eur: 360, USA: 300	RW	Uni			PT	US
SE12	Enable field control {0.33, 5.77}	OFF (0) or On (1)	OFF (0)	RW	Txt				US
SE13	Autotune {0.34, 5.12}	0 to 3	0	RW	Uni		NC		
SE14	Security status {0.35, 11.44}	L1 (0), L2 (1), Loc (2)	L1 (0)	RW	Txt			PT	US
di01	Speed reference selected {0.36, 1.01}	±MAX_SPEED_REF rpm		RO	Bi		NC	PT	
di02	Pre-ramp reference {0.37, 1.03}	±MAX_SPEED_REF rpm		RO	Bi		NC	PT	
di03	Post ramp reference {0.37, 1.03}	±SPEED_MAX rpm		RO	Bi		NC	PT	
di04	Final speed reference {0.39, 3.01}	±SPEED_MAX rpm		RO	Bi	FI	NC	PT	
di05	Speed feedback {0.40, 3.02}	±SPEED_MAX rpm		RO	Bi	FI	NC	PT	
di06	Speed controller output {0.41, 3.04}	±TORQUE_PRODUCT_ CURRENT_MAX rpm		RO	Bi	FI	NC	PT	
di07	Torque demand {0.42, 4.03}	±TORQUE_PROD_ CURRENT_MAX %		RO	Bi	FI	NC	PT	
di08	Current magnitude {0.43, 4.01}	0 to DRIVE_CURRENT_MAX A		RO	Uni	FI	NC	PT	
di09	Field current feedback {0.44, 5.56}	±50.00A		RO	Bi	FI	NC	PT	
di10	Armature voltage {0.45, 5.02}	±ARMATURE_VOLTAGE_ MAX V		RO	Bi	FI	NC	PT	
di11	Reference enabled indicator {0.46, 1.11}	OFF (0) or On (1)		RO	Bit		NC	PT	
di12	Reverse selected indicator {0.47, 1.13}	OFF (0) or On (1)		RO	Bit		NC	PT	
di13	Jog selected indicator {0.48, 1.14}	OFF (0) or On (1)		RO	Bit		NC	PT	
di14	Software version {0.49, 11.29}	1.00 to 99.99		RO	Uni		NC	PT	
tr01	Trip 0 {0.51, 10.20}	0 to 229		RO	Txt		NC	PT	
tr02	Trip 1 {0.52, 10.21}			RO	Txt		NC	PT	
tr03	Trip 2 {0.53, 10.22}			RO	Txt		NC	PT	
tr04	Trip 3 {0.54, 10.23}			RO	Txt		NC	PT	
tr05	Trip 4 {0.55, 10.24}			RO	Txt		NC	PT	
tr06	Trip 5 {0.56, 10.25}			RO	Txt		NC	PT	
tr07	Trip 6 {0.57, 10.26}			RO	Txt		NC	PT	
tr08	Trip 7 {0.58, 10.27}			RO	Txt		NC	PT	
tr09	Trip 8 {0.59, 10.28}			RO	Txt		NC	PT	
tr10	Trip 9 {0.60, 10.29}			RO	Txt		NC	PT	
SP01	(Kp1) Speed controller proportional gains {0.61, 3.10}	0.0000 to 6.5535 (1 / (rad/s))	0.0300	RW	Uni				US
SP02	(Ki1) Speed controller integral gains {0.62, 3.11}	0.00 to 655.35 (s / (rad/s))	0.10	RW	Uni				US
SP03	(Kd1) Speed controller differential feedback gains {0.63, 3.12}	0.00000 to 0.65535 (1/s / (rad/s))	0.00000	RW	Uni				US
Si01	Serial comms baud rate {0.61, 11.25}	300 (0), 600 (1), 1200 (2), 2400 (3), 4800 (4), 9600 (5), 19200 (6), 38400 (7), 57600 (8)**, 115200 (9)**	19200 (6)	RW	Txt				US
Si02	Serial comms address {0.67, 11.23}	0 to 247	1	RW	Uni				US
Fb01	Speed feedback selector {0.71, 3.26}	drv (0), Slot1 (1), Slot2 (2), Slot3 (3), tACHO (4), Est SPEED (5)	Est SPEED (5)	RW	Txt				US
Fb02	Tachometer voltage rating {0.72, 3.51}	0 to 300.00 V/1000 rpm	Eur: 60.00, USA: 50.00	RW	Uni				US
Fb03	Tachometer input mode {0.73, 3.53}	DC (0), DC Filt (1), AC (2)	DC (0)	RW	Txt				US
Fb04	Tachometer speed feedback {0.74, 3.52}	±SPEED_MAX rpm		RO	Bi	FI	NC	PT	
Fb05	Drive encoder lines per revolution {0.75, 3.34}	1 to 50,000	1,024	RW	Uni				US

Parameter		Range(⇕)	Default(⇨)	Type					
Fb06	Drive encoder supply voltage {0.76, 3.36}	5V (0), 8V (1), 15V (2), 24V (3)	5V (0)	RW	Txt				US
Fb07	Drive encoder type {0.77, 3.38}	Ab (0), Fd (1), Fr (2)	Ab (0)	RW	Txt				US
Fb08	Drive encoder termination select {0.78, 3.39}	0 to 2	1	RW	Uni				US
Fb09	Drive encoder speed feedback {0.79, 3.27}	±10,000.0 rpm		RW	Bi	FI	NC	PT	US
in01	Analog input 3 mode {0.81, 7.15}	0-20 (0), 20-0 (1), 4-20.tr (2), 20-4.tr (3), 4-20 (4), 20-4 (5), VOLt (6), th.SC (7), th (8), th. diSp (9)	th (8)	RW	Txt				US
in02	Analog input 1 {0.82, 7.01}	±100.00 %		RO	Bi		NC	PT	
in03	Analog input 2 {0.83, 7.02}	±100.0 %		RO	Bi		NC	PT	
in04	Analog input 3 {0.84, 7.03}	±100.0 %		RO	Bi		NC	PT	
in05	T24 digital I/O 1 state {0.85, 8.01}			RO	Bit		NC	PT	
in06	T25 digital I/O 2 state {0.86, 8.02}			RO	Bit		NC	PT	
in07	T26 digital I/O 3 state {0.87, 8.03}	OFF (0) or On (1)		RO	Bit		NC	PT	
in08	T27 digital input 4 state {0.88, 8.04}			RO	Bit		NC	PT	
in09	T28 digital input 5 state {0.89, 8.05}			RO	Bit		NC	PT	
in10	T29 digital input 6 state {0.90, 8.06}			RO	Bit		NC	PT	

* Modes 1 and 2 are not user saved, Modes 0, 3 and 4 are user saved.

** Only applicable to Modbus RTU mode.

Key:

Coding	Attribute
{X.XX}	Copied Menu 0 or advanced parameter
RW	Read/write: can be written by the user
RO	Read only: can only be read by the user
Bit	1 bit parameter: 'On' or 'OFF' on the display
Bi	Bipolar parameter
Uni	Unipolar parameter
Txt	Text: the parameter uses text strings instead of numbers.
FI	Filtered: some parameters which can have rapidly changing values are filtered when displayed on the drive keypad for easy viewing.
DE	Destination: This parameter selects the destination of an input or logic function.
RA	Rating dependent: this parameter is likely to have different values and ranges with drives of different voltage and current ratings. Parameters with this attribute will not be transferred to the destination drive by SMARTCARDs when the rating of the destination drive is different from the source drive and the file is a parameter file. However, the value will be transferred if only the current rating is different and the file is a differences from default type file.
NC	Not copied: not transferred to or from SMARTCARDS during copying.
PT	Protected: cannot be used as a destination.
US	User save: parameter saved in drive EEPROM when the user initiates a parameter save.
PS	Power-down save: parameter automatically saved in drive EEPROM when the under volts (UV) trip occurs. Power-down save parameters are also saved in the drive when the user initiates a parameter save.

6.1 Full descriptions

6.1.1 Parameter x.00

SE00 {x.00}	Parameter zero							
RW	Uni							
⇕	0 to 32,767				⇨	0		

Pr **x.00** is available in all menus and has the following functions.

Value	String	Action
0	No Act	No action
1	SAUE	Save parameters
2	rEAd 1*	Transfer SMART card data block 1 to the drive
3	PrOg 1*	Transfer drive parameters as difference from default to SMART card block number 1
4	rEAd 2*	Transfer SMART card data block 2 to the drive
5	PrOg 2*	Transfer drive parameters as difference from default to SMART card block number 2
6	rEAd 3*	Transfer SMART card data block 3 to the drive
7	PrOg 3*	Transfer drive parameters as difference from default to SMART card block number 3
8	diS.diFF	Display non-default values only
9	diS.dESt	Display destination parameters only
10	Eur	Load European defaults
11	USA	Load USA defaults
12	rES OP	Reset all Solution Modules
1000	1000	Save parameters
1070	1070	Reset all Solution Modules
1233	1233	Load European defaults
1244	1244	Load USA defaults
1255	1255	Load European defaults (excluding menus 15 to 20)
1256	1256	Load USA defaults (excluding menus 15 to 20)
2001	2001*	Transfer drive parameter to a card and create a bootable difference from default SMART card block with data block number 1 and clear parameter 11.42. If data block 1 exists it is over written.
3yyy	3yyy*	Transfer drive parameters to SMART card block number yyy
4yyy	4yyy*	Transfer drive parameters as difference from default to SMART card block number yyy
5yyy	5yyy*	Transfer Onboard Applications Lite ladder program to SMART card block number yyy
6yyy	6yyy*	Transfer SMART card data block yyy to the drive
7yyy	7yyy*	Erase SMART card data block yyy
8yyy	8yyy*	Compare drive data with SMART card block yyy
9555	9555*	Clear SMART card warning suppression flag
9666	9666*	Set SMART card warning suppression flag
9777	9777*	Clear SMART card read-only flag
9888	9888*	Set SMART card read-only flag
9999	9999*	Erase SMART card
12000**	12000**	Display non-default values only
12001**	12001**	Display destination parameters only

* See Chapter 9 *SMARTCARD operation* on page 81 for more information of these functions.

** These functions do not require a drive reset to become active. All other functions require a drive reset to initiate the function.

6.1.2 Parameter x.00 reset

When an action is started by setting Pr **x.00** to one of the above values and initiating a drive reset this parameter is cleared when the action is completed successfully. If the action is not started, e.g. because the drive is enabled and an attempt is made to load defaults, etc., Pr **x.00** is not cleared and no trip is produced. If the action is started and then fails for some reason a trip is always produced and Pr **x.00** is not cleared. It should be noted that parameter saves etc. can also be initiated with the copying parameter (Pr **11.42** (**SE09**, **0.30**)). If actions that can be initiated by either parameter are started and then completed successfully Pr **x.00** is cleared and Pr **11.42** (**SE09**, **0.30**) is cleared if it has a value of less than 3.

It should be noted that there could be some conflict between the actions of Pr **x.00** and Pr **11.42** (**SE09**, **0.30**) *Parameter copying* when the drive is reset. If Pr **11.42** (**SE09**, **0.30**) has a value of 1 or 2 and a valid action is required from the value of Pr **x.00** then only the action required by Pr **x.00** is performed. Pr **x.00** and Pr **11.42** (**SE09**, **0.30**) are then reset to zero. If Pr **11.42** (**SE09**, **0.30**) has a value of 3 or 4 it will operate correctly causing parameters to be save to a SMARTCARD each time a parameter save is performed.

6.1.3 Set-up

SE01 {0.22, 1.07}	Minimum reference clamp						
RW	Bi					PT	US
↕	±SPEED_LIMIT_MAX rpm	⇨			0.0		

(When the drive is jogging, this parameter has no effect.)

Set **SE01** (Pr **0.22**, **1.07**) at the required minimum motor speed for both directions of rotation. The drive speed reference is scaled between **SE01** (Pr **0.22**, **1.07**) and **SE02** (Pr **0.23**, **1.06**).

SE02 {0.23, 1.06}	Maximum reference clamp					
RW	Bi					US
↕	SPEED_LIMIT_MAX rpm	⇨		1000.0		

(The drive has additional over-speed protection.)

Set **SE02** (Pr **0.23**, **1.06**) at the required maximum motor speed for both directions of rotation. The drive speed reference is scaled between **SE01** (Pr **0.22**, **1.07**) and **SE02** (Pr **0.23**, **1.06**).

SE03 {0.24, 2.11}	Acceleration rate					
RW	Uni					US
↕	0 to MAX_RAMP_RATE s/(**SE02** [Pr **0.23**, **1.06**] or Pr **2.39**)	⇨		5.000		

Set **SE03** (Pr **0.03**, **2.11**) at the required rate of acceleration.

Note that larger values produce lower acceleration. The rate applies in both directions of rotation.

SE04 {0.25, 2.21}	Deceleration rate					
RW	Uni					US
↕	0 to MAX_RAMP_RATE s/(**SE02** [Pr **0.23**, **1.06**] or Pr **2.39**)	⇨		5.000		

Set Pr **SE04** (Pr **0.25**, **2.21**) at the required rate of deceleration.

Note that larger values produce lower deceleration. The rate applies in both directions of rotation.

SE05 {0.26, 1.14}	Reference selector					
RW	Txt					US
↕	A1.A2 (0), A1.Pr (1), A2.Pr (2), Pr (3), PAd (4), Prc (5), PAd rEF (6)	⇨		A1.A2 (0)		

Defines how the value of Pr **1.49** is derived as follows:

Value of Pr 1.14	Display String	Pr 1.49
0	A1.A2 (Analog ref 1. Analog ref 2)	*Selected by terminal input
1	A1.Pr (Analog ref 1. Preset speeds)	1
2	A2.Pr (Analog ref 2. Preset speeds)	2
3	Pr (Preset speeds)	3
4	Pad (Keypad reference)	4
5	Prc (Precision reference)	5
6	Pad rEF	6

*Pr **1.41** to Pr **1.44** and Pr **1.52** can be controlled by digital inputs to force the value of Pr **1.49**:

When all bits = 0, Pr **1.49** =1

    Pr **1.41** = 1 then Pr **1.49** = 2
    Pr **1.42** = 1 then Pr **1.49** = 3
    Pr **1.43** = 1 then Pr **1.49** = 4
    Pr **1.44** = 1 then Pr **1.49** = 5
    Pr **1.52** = 1 then Pr **1.49** = 6

The bit parameters with lower numbers have priority over those with higher numbers.

Pr **1.49** and Pr **1.50** then define the reference as follows:

Pr 1.49	Pr 1.50	Reference
1	1	Analog reference 1 (Pr **1.36**)
1	>1	Preset defined by Pr **1.50** (Pr **1.21** to Pr **1.28**)
2	1	Analog reference 2 (Pr **1.37**)
2	>1	Preset defined by Pr **1.50** (Pr **1.21** to Pr **1.28**)
3	x	Preset defined by Pr **1.50** (Pr **1.21** to Pr **1.28**)
4	x	Keypad reference (Pr **1.17**)
5	x	Precision reference (Pr **1.18** and Pr **1.19**)
6	x	Keypad reference only

x = any value

Keypad reference

If Keypad reference is selected the drive sequencer is controlled directly by the keypad keys and the keypad reference parameter (Pr **1.17**) is selected. The sequencing bits, Pr **6.30** to Pr **6.34**, have no effect and jog is disabled.

SE06 {0.27, 5.09}	Armature rated voltage					
RW	Uni			RA		US
↕	0 to ARMATURE_VOLTAGE_MAX Vdc	⇨		For 480V drive: 440 Eur, 500 USA For 575V drive: 630 Eur, 630 USA For 690V drive: 760 Eur, 760 USA		

SE07 {0.28, 5.07}	Motor rated current						
RW	Uni				RA		US
↕	0 to RATED_CURRENT_MAX A		⇨	RATED_CURRENT_MAX			

The rated current should be set at the motor nameplate value for rated current. The value of this parameter is used in the following:

- Current limits
- Motor thermal protection

SE08 {0.29, 5.08}	Base speed						
RW	Uni						US
↕	0.0 to 10,000.0 rpm		⇨	1000.0			

The rated speed defines the base speed of the motor. It is also to determine the speed used in the auto tuning inertia test (see **SE13** [Pr **0.34**, **5.12**]).

SE09 {0.30, 11.42}	Parameter copying						
RW	Txt				NC		*
↕	nonE (0), rEAd (1), ProG (2), Auto (3), boot (4)		⇨	nonE (0)			

* Modes 1 and 2 are not user saved, Modes 0, 3 and 4 are user saved.

If **SE09** (Pr **0.30**, **11.42**) is equal to 1 or 2 this value is not transferred to the EEPROM or the drive. If **SE09** (Pr **0.30**, **11.42**) is set to a 3 or 4 the value is transferred.

Pr String	Pr value	Comment
nonE	0	Inactive
rEAd	1	Read parameter set from the SMARTCARD
ProG	2	Programming a parameter set to the SMARTCARD
Auto	3	Auto save
boot	4	Boot mode

For further information, refer to Chapter 9 *SMARTCARD operation* on page 81.

SE10 {0.31, 5.70}	Rated field current						
RW	Uni					PT	US
↕	0 to FIELD_CURRENT_SET_MAX		⇨	Size 1: Eur 2A, USA 8A Size 2A/B: Eur 3A, USA 20A Size 2C/D: Eur 5A, USA 20A			

This parameter will be set to the field current of the motor and will define the rated field current for the field controller.

SE11 {0.32, 5.73}	Rated field voltage						
RW	Uni					PT	US
↕	0 to 500 Vdc		⇨	Eur: 360, USA: 300			

The maximum voltage the field controller is allowed to generate.

SE12 {0.33, 5.77}	Enable field control						
RW	Txt						US
↕	OFF (0) or On (1)		⇨	OFF (0)			

When this parameter is set to 0 the internal and external field controllers are disabled. Setting the parameter to 1 enables the internal or external field controller.

SE13 {0.34, 5.12}	Autotune						
RW	Uni				NC		
↕	0 to 3		⇨	0			

If this parameter is set to a non-zero value, the drive is enabled and a run command is applied in either direction the drive performs an auto-tune test. All tests that rotate the motor are carried out in the forward direction if **di12** (Pr **0.47**, **1.12**) = 0 or the reverse direction if **di12** (Pr **0.47**, **1.12**) = 1. For example, if the test is initiated by applying run reverse (Pr **6.32** = 1) the test is performed in the reverse direction. The test will not start unless the drive is disabled before the test is initiated by applying the enable or run, i.e. it will not start if the drive is in the stop state. It is not possible to go into the stop state if **di12** (Pr **0.47**, **1.12**) has a non-zero value.

When the test is completed successfully the drive is disabled and will enter the inhibit state. The motor can only be restarted if the enable is removed either from the enable input, or Pr **6.15** is set to zero or from the control word (Pr **6.42**) if it is active.

Value	Autotune function
0	None
1	Static autotune for current loop gains
2	Spinning autotune for motor saturation break points
3	Spinning autotune for inertia measurement

Static autotune for current loop gains
When this operation is performed, the drive will estimate the following, with respect to the selected motor map, and store the values:

Motor constant (Pr **5.15**)
Continuous proportional gain (Pr **4.13**)
Continuous integral gain (Pr **4.14**)
Discontinuous integral gain (Pr **4.34**)
Back EMF set point (Pr **5.59**)
Armature resistance (Pr **5.61**)
Flux loop I gain (Pr **5.72**)

Spinning autotune for motor saturation break points
When this operation is performed, the drive will estimate the following, with respect to the selected motor map, and store the values:

Motor saturation break points (Pr **5.29**, Pr **5.30**), by spinning the motor at 25% of it's *base speed* (Pr **5.06**)
Field current compensation factor (Pr **5.74**)

Spinning autotune for inertia measurement
The drive can measure the total inertia of the load and motor. This is used to set the speed loop gains. See Pr **3.17** *Speed controller setup method* = 1 (bandwidth setup). During the inertia measurement test the drive attempts to accelerate the motor to $^3/_4$ rated speed then back to a standstill. Several attempts may be made, starting with rated torque/16, and then increasing the torque progressively to x$^1/_8$, x$^1/_4$, x$^1/_2$, and x 1 rated torque if the motor cannot be accelerated to the required speed. If the required speed is not achieved on the final attempt the test is aborted and a tuNE 1 trip is initiated. If the test is successful the acceleration and deceleration times are used to calculate the motor and load inertia and a value is written to Pr **3.18** *Motor and load inertia*.

SE14 {0.35, 11.44}	Security status						
RW	Txt					PT	US
⇕	L1 (0), L2 (1), Loc (2)			⇨	L1 (0)		

This parameter controls access via the drive keypad as follows:

Value	String	Action
0	L1	Only menu 0 can be accessed
1	L2	All menus can be accessed
2	Loc	Lock user security when drive is reset. (This parameter is set to L1 after reset.)

The keypad can adjust this parameter even when user security is set.

6.1.4 Diagnostic

di01 {0.36, 1.01}	Speed reference selected						
RO	Bi				NC	PT	
⇕	±MAX_SPEED_REF rpm			⇨			

di02 {0.37, 1.03}	Pre-ramp reference						
RO	Bi				NC	PT	
⇕	±MAX_SPEED_REF rpm			⇨			

di03 {0.38, 2.01}	Post ramp reference						
RO	Bi				NC	PT	
⇕	±SPEED_MAX rpm			⇨			

di04 {0.39, 3.01}	Final speed reference						
RO	Bi	FI			NC	PT	
⇕	±SPEED_MAX rpm			⇨			

This is the final speed demand at the input to the speed regulator formed by the sum of the ramp output and the hard speed reference (if the hard speed reference is enabled). If the drive is disabled this parameter will show 0.0.

di05 {0.40, 3.02}	Speed feedback						
RO	Bi	FI			NC	PT	
⇕	±SPEED_MAX rpm			⇨			

The speed feedback can be taken from the drive encoder port or tachometer or armature voltage or a position feedback module installed in any slot as selected with **Fb01** (Pr **0.71**, **3.26**). **di05** (Pr **0.40**, **3.02**) shows the level of the speed feedback selected for the speed controller. Display filtering is active when this parameter is viewed with one of the drive keypads. The value held in the drive parameter (accessible via comms or an option module) does not include this filter, but is a value that is obtained over a sliding 16ms period to limit the ripple seen in this parameter value. The speed feedback value includes encoder quantization ripple given by the following equation:

Ripple in **di05** (Pr **0.40**, **3.02**) = 60 / 16ms / (ELPR x 4)

Where ELPR is the equivalent encoder lines per revolution as defined overleaf:

Position feedback device	ELPR
Ab	number of lines per revolution
Fd, Fr	number of lines per revolution / 2

For example a 4096 line Ab type encoder gives a ripple level of 0.23rpm.

The 16ms sliding window filter is always applied to the value shown in di05 (Pr 0.40, 3.02), but this sliding window filter is not normally applied to the actual speed feedback used by the speed controller or the drive encoder reference system (Pr 3.43 to Pr 3.46). The user may apply a filter to the speed controller input and the drive encoder reference system input if required by setting Pr **3.42** to the required filter time. The encoder ripple seen by the speed controller is given by:

Encoder speed ripple = 60 / Filter time / (ELPR x 4)

If Pr **3.42** is set to zero (no filter) the ripple seen by the speed controller and drive encoder reference system is given by:

Encoder speed ripple = 60 / 250μs / (ELPR x 4)

Figure 6-1   Speed feedback filter arrangement

Figure 6-1 shows the filter arrangement. It should be noted that the same filtering is provided at the speed controller input and for **di05** (Pr **0.40**, **3.02**) when the feedback is obtained from an option module, but the variable length window filter is controlled by Pr **x.19**.

It is not advisable to set the speed feedback filter too high unless it is specifically required for high inertia applications with high controller gains because the filter has a non-linear transfer function. It is preferable to use the current demand filters (see Pr **4.12** or Pr **4.23**) as these are linear first order filters that provide filtering on noise generated from both the speed reference and the speed feedback. It should be noted that any filtering included within the speed controller feedback loop, either on the speed feedback or the current demand, introduces a delay and limits the maximum bandwidth of the controller for stable operation.

The speed ripple can be quite high, for example with a 4096 line encoder the speed ripple is 14.6rpm, but this does not define the resolution of the speed feedback which is normally much better and depends on the length of the measuring period used to obtain the feedback. This is shown in the improved resolution of the value accessible in **di05** (Pr **0.40**, **3.02**) which is measured over 16ms, i.e. a resolution of 0.23rpm with a 4096 line encoder. The speed controller itself accumulates all pulses from the encoder, and so the speed controller resolution is not limited by the feedback, but by the resolution of the speed reference. If a SINCOS encoder is used from an option the encoder speed ripple is reduced by a factor of $2^{(2\text{-Interpolation bits})}$. For example with the nominal 10 bits of interpolation information, the speed ripple is reduced by a factor of 256. This shows how a SINCOS encoder can reduce noise caused by encoder quantization without any filtering in the speed feedback or the current demand, so that high gains may be used to give high dynamic performance and a very stiff system.

di06 {0.41, 3.04}	**Speed controller output**						
RO	Bi	FI			NC	PT	
⇕	±TORQUE_PRODUCT_ CURRENT_MAX rpm		⇨				

The output of the speed regulator is a torque demand given as a percentage of rated motor torque. This is then modified to account for changes in motor flux if field weakening is active, and then used as the torque producing current reference.

di07 {0.42, 4.03}	**Torque demand**						
RO	Bi	FI			NC	PT	
⇕	±TORQUE_PROD_ CURRENT_MAX %		⇨				

The torque demand can be derived from the speed controller and/or the torque reference and offset. The units of the torque demand are a % of rated torque.

di08 {0.43, 4.01}	**Current magnitude**						
RO	Uni	FI			NC	PT	
⇕	0 to DRIVE_CURRENT_MAX A		⇨				

The current feedback signal is derived from internal current transformers. It is used for closed loop control and indication of the armature current, and to initiate motor protection.

di09 {0.44, 5.56}	**Field current feedback**						
RO	Bi	FI			NC	PT	
⇕	±50.00A		⇨				

Indicates the field current feedback in 0.01 amperes.

di10 {0.45, 5.02}	**Armature voltage**						
RO	Bi	FI			NC	PT	
⇕	±ARMATURE_VOLTAGE_ MAX V		⇨				

The average measured DC output voltage seen across the drive A1 and A2 terminals or the average measured DC output voltage seen across the motor. Selected by Pr **5.14**.

The armature voltage feedback has a resolution of 10-bit plus sign.

di11 {0.46, 1.11}	**Reference enabled indicator**						
di12 {0.47, 1.13}	**Reverse selected indicator**						
di13 {0.48, 1.14}	**Jog selected indicator**						
RO	Bit				NC	PT	
⇕	OFF (0) or On (1)		⇨				

These parameters are controlled by the drive sequencer as defined in Menu 6. They select the appropriate reference as commanded by the drive logic. **di11** (Pr **0.46**, **1.11**) will be active if a run command is given, the drive is enabled and the drive is ok. This parameter can be used as an interlock in a Onboard PLC or SM-Applications program to show that the drive is able to respond to a speed or torque demand.

di14 {0.49, 11.29}	**Software version**						
RO	Uni				NC	PT	
⇕	1.00 to 99.99		⇨				

The parameter displays the software version of the drive.

6.1.5 Trips

tr01 {0.51, 10.20}	**Trip 0**
tr02 {0.52, 10.21}	**Trip 1**
tr03 {0.53, 10.22}	**Trip 2**
tr04 {0.54, 10.23}	**Trip 3**
tr05 {0.55, 10.24}	**Trip 4**
tr06 {0.56, 10.25}	**Trip 5**
tr07 {0.57, 10.26}	**Trip 6**
tr08 {0.58, 10.27}	**Trip 7**
tr09 {0.59, 10.28}	**Trip 8**
tr10 {0.60, 10.29}	**Trip 9**

RO	Txt				NC	PT		PS
⇕	0 to 229		⇨					

Contains the last 10 drive trips. **tr01** (Pr **0.51**, **10.20**) is the most recent trip and **tr10** (Pr **0.60**, **10.29**) the oldest. When a new trip occurs all the parameters move down one, the current trip is put in **tr01** (Pr **0.51**, **10.20**) and the oldest trip is lost from the bottom of the log. Descriptions of the trips are given in Table 13-1 on page 167. All trips are stored, including HF trips numbered from 20 to 29. (HF trips with numbers from 1 to 16 are not stored in the trip log.) Any trip can be initiated by the actions described or by writing the relevant trip number to Pr **10.38**. If any trips shown as user trips are initiated the trip string is "txxx", where xxx is the trip number.

6.1.6 Speed loop

SP01 {0.61, 3.10}	**(Kp1) Speed controller proportional gains**						
RW	Uni						US
⇕	0.0000 to 6.5535 (1 / (rad/s))		⇨		0.0300		

SP01 (Pr **0.61/3.10**) operates in the feed-forward path of the speed-control loop in the drive. See Figure 11-3 on page 102 for a schematic of the speed controller. For information on setting up the speed controller gains, refer to Chapter 8 *Optimization* on page 78.

SP02 {0.62, 3.11}	**(Ki1) Speed controller integral gains**						
RW	Uni						US
⇕	0.00 to 655.35 (s / (rad/s))		⇨		0.1		

SP02 (Pr **0.62**, **3.11**) operates in the feed-forward path of the speed-control loop in the drive. See Figure 11-3 on page 102 for a schematic of

the speed controller. For information on setting up the speed controller gains, refer to Chapter 8 *Optimization* on page 78.

SP03 {0.63, 3.12}	(Kd1) Speed controller differential feedback gains						
RW	Uni					US	
↕	0.00000 to 0.65535 (1/s / (rad/s))		⇨	0.00000			

SP03 (Pr **0.63**, **3.12**) operates in the feed-forward path of the speed-control loop in the drive. See Figure 11-3 on page 102 for a schematic of the speed controller. For information on setting up the speed controller gains, refer to Chapter 8 *Optimization* on page 78.

6.1.7 Serial interface

Si01 {0.61, 11.25}	Serial comms baud rate						
RW	Txt					US	
↕	300 (0), 600 (1), 1200 (2), 2400 (3), 4800 (4), 9600 (5), 19200 (6), 38400 (7), 57600 (8)*, 115200 (9)*		⇨	19200 (6)			

* only applicable to Modbus RTU mode

This parameter can be changed via the drive keypad, via a Solutions Module or via the comms interface itself. If it is changed via the comms interface, the response to the command uses the original baud rate. The master should wait at least 20ms before send a new message using the new baud rate.

Si02 {0.67, 11.23}	Serial comms address						
RW	Uni					US	
↕	0 to 247		⇨	1			

Used to define the unique address for the drive for the serial interface. The drive is always a slave.

Modbus RTU

When the Modbus RTU protocol is used addresses between 0 and 247 are permitted. Address 0 is used to globally address all slaves, and so this address should not be set in this parameter

ANSI

When the ANSI protocol is used the first digit is the group and the second digit is the address within a group. The maximum permitted group number is 9 and the maximum permitted address within a group is 9. Therefore, **Si02** (Pr **0.67**, **11.23**) is limited to 99 in this mode. The value 00 is used to globally address all slaves on the system, and x0 is used to address all slaves of group x, therefore these addresses should not be set in this parameter.

6.1.8 Speed feedback

Fb01 {0.71, 3.26}	Speed feedback selector						
RW	Txt					US	
↕	drv (0), Slot1 (1), Slot2 (2), Slot3 (3), tACHO (4), Est SPEED (5)		⇨	Est SPEED (5)			

0, drv: Drive encoder

The position feedback from the encoder connected to the drive itself is used to derive the speed feedback for the speed controller and to calculate the motor rotor flux position.

1, Slot1: Solutions Module in slot 1

The position feedback from the Solutions Module in Solutions Module slot 1 is used to derive the speed feedback for the speed

controller and to calculate the motor rotor flux position. If a position feedback category Solutions Module is not installed in slot 1 the drive produces an EnC9 trip.

2, Slot2: Solutions Module in slot 2

3, Slot3: Solutions Module in slot 3

4, tACHO: Tachometer

5, ESt.SPEED: Estimated speed

Fb02 {0.72, 3.51}	Tachometer voltage rating						
RW	Uni					US	
↕	0 to 300.00 V/1000 rpm		⇨	Eur: 60.00, USA: 50.00			

Defines the rating of the tachometer installed to the motor. This parameter should be set slightly above or below the nominal value if the user wishes to trim out the tolerance build ups in the feedback electronics.

Fb03 {0.73, 3.53}	Tachometer input mode						
RW	Txt					US	
↕	DC (0), DC Filt (1), AC (2)		⇨	DC (0)			

The input electronics for the tachometer input can be configured in 3 ways.

Value	Text	Action
0	DC	DC tachometer
1	DC Filt	DC tachometer with input filter
2	AC	AC tachometer

Fb04 {0.74, 3.52}	Tachometer speed feedback						
RO	Bi	FI				NC	PT
↕	±SPEED_MAX rpm		⇨				

Provided the tachometer voltage rating parameter for the tachometer is correct this parameter shows the tachometer speed in rpm.

Fb05 {0.75, 3.34}	Drive encoder lines per revolution						
RW	Uni					US	
↕	1 to 50,000		⇨	1,024			

When Ab, Fd, Fr are used the equivalent number of encoder lines per revolution must be set-up correctly in **Fb05** (Pr **0.75, 3.34**) to give the correct speed and position feedback. This is particularly important if the encoder is selected for speed feedback with Fb01 (Pr **0.71, 3.26**). The equivalent number of encoder lines per revolution (ELPR) is defined as follows.:

Position feedback device	ELPR
Ab	number of lines per revolution
Fd, Fr	number of lines per revolution / 2

The incremental (A/B) signal frequency should not exceed 500kHz. If **Fb05** is changed the encoder is re-initialized.

Fb06 {0.76, 3.36}	**Drive encoder supply voltage**		
RW	Txt		US

| ↕ | 5V (0), 8V (1), 15V (2), 24V (3) | ⇨ | 5V (0) |

The encoder supply voltage present on the drive encoder connector is defined by this parameter as 0 (5V), 1 (8V), 2 (15V) or 3 (24V)

Fb07 {0.77, 3.38}	**Drive encoder type**		
RW	Txt		US

| ↕ | Ab (0), Fd (1), Fr (2) | ⇨ | Ab (0) |

The following encoders can be connected to the drive encoder port.

0, Ab: Quadrature incremental encoder, with or without marker pulse.

1, Fd: Incremental encoder with frequency and direction outputs, with or without marker pulse.

2, Fr: Incremental encoder with forward and reverse outputs, with or without marker pulse.

Fb08 {0.78, 3.39}	**Drive encoder termination select**		
RW	Uni		US

| ↕ | 0 to 2 | ⇨ | 1 |

The terminations may be enabled/disabled by this parameter as follows:

Encoder input	Fb08 {0.78, 3.39} = 0	Fb08 {0.78, 3.39} = 1	Fb08 {0.78, 3.39} = 2
A-A\	Disabled	Enabled	Enabled
B-B\	Disabled	Enabled	Enabled
Z-Z\	Disabled	Disabled	Enabled

Fb09 {0.79, 3.27}	**Drive encoder speed feedback**				
RW	Bi	FI	NC	PT	US

| ↕ | ±10,000.0 rpm | ⇨ | |

Provided the set-up parameters for the drive encoder are correct this parameter shows the encoder speed in rpm.

It should be noted that the value shown by this parameter is measured over a 16ms sliding window period (in the same way as **di05** (Pr **0.40, 3.02**)), and so the ripple in this parameter accessible via comms or by an option module is as defined for **di05** (Pr **0.40, 3.02**). The FI attribute for this parameter is set, and so further filtering is applied when this parameter is viewed with one of the drive keypads.

6.1.9 I/O

in01 {0.81, 7.15}	**Analog input 3 mode**		
RW	Txt		US

| ↕ | 0-20 (0), 20-0 (1), 4-20.tr (2), 20-4.tr (3), 4-20 (4), 20-4 (5), VOLt (6), th.SC (7), th (8), th. diSp (9) | ⇨ | Eur: th (8), USA: VOLt (6) |

The following modes are available for the analog input 3. A current loop loss trip is generated if the input current falls below 3mA. In modes 4 and 5 the analog input level goes to 0.0% if the input current falls below 3mA.

Parameter value	Parameter string	Mode	Comments
0	0-20	0 - 20mA	
1	20-0	20 - 0mA	
2	4-20.tr	4 -20mA with trip on loss	Trip if I < 3mA
3	20-4.tr	20 - 4mA with trip on loss	Trip if I < 3mA
4	4-20	4 - 20mA with no trip on loss	
5	20-4	20 - 4mA with no trip on loss	0.0% if I < 4mA
6	VOLt	Voltage mode	
7	th.SC	Thermistor with short circuit detection	TH trip if R > 3k3 TH reset if R < 1k8 THS trip if R < 50R
8	th	Thermistor without short circuit detection	TH trip if R > 3k3 TH reset if R < 1k8
9	th.diSp	Thermistor display only with no trip	

In modes 2 and 4 the destination parameter is at a value equivalent to 0.0% when the input current is less than 4mA. In modes 3 and 5 the destination parameter is at a value equivalent to 100.0% when the input current is less than 4mA.

in02 {0.82, 7.01}	**Analog input 1**					
RO	Bi		NC	PT		

| ↕ | ±100.00 % | ⇨ | |

in03 {0.83, 7.02}	**Analog input 2**					
RO	Bi		NC	PT		

| ↕ | ±100.0 % | ⇨ | |

in04 {0.84, 7.03}	**Analog input 3**					
RO	Bi		NC	PT		

| ↕ | ±100.0 % | ⇨ | |

When analog input 3 is in thermistor mode the display indicates the resistance of the thermistor as a percentage of 10kΩ.

in05 {0.85, 8.01}	**T24 digital I/O 1 state**
in06 {0.86, 8.02}	**T25 digital I/O 2 state**
in07 {0.87, 8.03}	**T26 digital I/O 3 state**
in08 {0.88, 8.04}	**T27 digital input 4 state**
in09 {0.89, 8.05}	**T28 digital input 5 state**
in10 {0.90, 8.06}	**T29 digital input 6 state**

RO	Bit		NC	PT	

| ↕ | OFF (0) or On (1) | ⇨ | |

OFF (0) = Terminal inactive

On (1) = Terminal active

7 Running the motor

This chapter takes the new user through all the essential steps to running a motor for the first time, in each of the possible operating modes.

⚠️ WARNING	Ensure that no damage or safety hazard could arise from the motor starting unexpectedly.

⚠️ CAUTION	The values of the motor parameters affect the protection of the motor. The default values in the drive should not be relied upon. It is essential that the correct value is entered in Pr **5.07** (**SE07**, **0.28**) *Motor rated current*. This affects the thermal protection of the motor.

⚠️ CAUTION	If the keypad mode has been used previously, ensure that the keypad reference has been set to 0 using the ◀▲▶▼ buttons as if the drive is started using the keypad it will run to the speed defined by the keypad reference (Pr **1.17**).

⚠️ WARNING	If the intended maximum speed affects the safety of the machinery, additional independent over-speed protection must be used.

Table 7-1 Minimum control connection requirements for each control mode

Drive control method	Requirements
Terminal mode	Drive enable Speed reference Run forward or run reverse command
Keypad mode	Drive enable
Serial communications	Drive enable Serial communications link

Refer to Figure 4-1 *Power connections for 480V drive* on page 33 for minimum connections to get a motor running.

7.1 Quick start commissioning / start-up (from European defaults)

Action	Detail	
Before power-up	Ensure: • Drive Enable signal is not given (terminal 31) • Run signal is not given • Motor connected • Tacho connected if one is being used • Encoder connected if one is being used	
Power-up the drive	Ensure: • Drive displays 'inh' **NOTE** The drive will trip 'th' (Motor thermistor trip) if no motor thermistor is connected to analog input 3 (terminal 8). If the motor protection is not connected to the drive, the 'th' trip can be disabled by setting Pr **7.15** (**in01**, **0.81**) (analog input 3 mode) to VOLt. For drive trips, see Chapter 13 *Diagnostics* on page 167.	
Enter motor nameplate details	Enter: • Armature rated voltage in Pr **5.09** (**SE06, 0.27**) (V) • Motor rated current in Pr **5.07** (**SE07, 0.28**) (A) • Motor rated speed (base speed) in Pr **5.08** (**SE08, 0.29**) (rpm) • Field rated current in Pr **5.70** (**SE10, 0.31**) (A) • Field rated voltage in Pr **5.73** (**SE11, 0.32**) (V)	

Set motor feedback parameters	**Incremental encoder basic set-up**
	Enter:
	• Drive encoder type in Pr **3.38** (**Fb07, 0.77**) = Ab (0): Quadrature encoder
	
	⚠ **CAUTION** Setting the encoder voltage supply too high for the encoder could result in damage to the feedback device.
	
	• Encoder power supply in Pr **3.36** (**Fb06, 0.76**) = 5V (0), 8V (1), 15V (2) or 24V (3)
	NOTE If output voltage from the encoder is >5V, then the termination resistors must be disabled Pr **3.39** (**Fb08, 0.78**) to 0.
	• Drive encoder lines per revolution (LPR) in Pr **3.34** (**Fb05, 0.75**) (set according to encoder)
	• Drive encoder termination resistor setting in Pr **3.39** (**Fb08, 0.78**)
	    0 = A-A\, B-B\, Z-Z\ termination resistors disabled
	    1 = A-A\, B-B\, termination resistors enabled, Z-Z\ termination resistors disabled
	    2 = A-A\, B-B\, Z-Z\ termination resistors enabled
	
	Tachometer set-up
	Enter:
	• Tachometer voltage rating Pr **3.51** (**Fb02, 0.72**) (V/1000 rpm)
	• Tachometer input mode Pr **3.53** (**Fb03, 0.73**)	

Set maximum speed	Enter: • Maximum speed in Pr **1.06** (**SE02, 0.23**) (rpm) • Set Pr **5.64** = On If field weakening is required **NOTE** For field weakening in Estimated Speed Mode please refer to Chapter8 *Optimization* on page 78	
Set acceleration / deceleration rates	Enter: • Acceleration rate in Pr **2.11** (**SE03, 0.24**) (time to accelerate to maximum speed) • Deceleration rate in Pr **2.21** (**SE04, 0.25**) (time to decelerate from maximum speed)	
Enable the field controller	**Field controller set-up** • Select field mode by setting Pr **5.78** = IntrnL (Internal field controller is used), Etrnl (External half control), E FULL (External in full control). • Set Pr **5.77** (**SE12**, **0.33**) = On to enable the field.	

Action	Detail	
Static autotune	Mentor MP is able to perform either a static, rotating or continuous autotune. The motor must be at a standstill before an autotune is enabled. **Static autotune for current loop gains** When this operation is performed the drive will perform an estimation of *Motor constant* (Pr **5.15**), *Continuous proportional gain* (Pr **4.13**), *Continuous integral gain* (Pr **4.14**), *Discontinuous integral gain* (Pr **4.34**), *Back EMF set point* (Pr **5.59**), *Armature resistance* (Pr **5.61**) and *Flux loop I gain* (Pr **5.72**) with respect to the selected motor map and store the values. To perform a static autotune: • Set Pr **5.12** (**SE13, 0.34**)= 1 • Close the Drive Enable signal (terminal 31). The drive will display 'rdY' • Close the run signal (terminal 26 or 27). The lower display will flash 'Auto' and 'tunE' alternatively, while the drive is performing the autotune • Remove the enable signal when the autotune has finished • Remove the run signal	

Checking speed feedback	• Close the enable signal. Close the run signal (terminal 26 or 27). Provide speed reference to run the drive up to a low speed, the drive will regulate its own estimated speed.
	• Check that the feedback device is functioning correctly:
	    For encoder speed feedback - Check encoder speed feedback Pr **3.27** (**Fb09, 0.79**).
	    For tachometer speed feedback - Check tachometer speed feedback Pr **3.52** (**Fb04, 0.74**).
	• When the feedback device being used is seen to be functioning correctly, stop the drive and select the correct feedback device using Pr **3.26** (**Fb01**, Pr **0.71**)
	NOTE
	For improved estimated speed accuracy and torque control in the field weakening range a rotating autotune is recommended to determine the motor flux characteristics Pr **5.12** (**SE13**, **0.34**) = 2	

Rotating autotune	Mentor MP is able to perform either a static, rotating or continuous autotune. The motor must be at a standstill before an autotune is enabled. **NOTE** A rotating autotune cannot be carried out in Estimated speed mode. ⚠ A rotating autotune will cause the motor to accelerate up to $^1/_4$ base speed in the direction selected regardless of the reference provided. Once complete the motor will coast to a stop. The enable signal must be removed before the drive can be made to run at the required reference. **WARNING** The drive can be stopped at any time by removing the run signal or removing the drive enable. **Rotating autotune for motor field flux set-up** When selected the drive will determine the rated field compensation factor (Pr **5.74**) for rated flux and the motor field winding saturation break-points (Pr **5.29** and Pr **5.30**), by spinning the motor at 25% of its base speed (Pr **5.08**) with respect to the selected motor map and store the values. To perform an autotune: • Set Pr **5.12** (**SE13, 0.34**) = 2 for a rotating autotune • Close the Drive Enable signal (terminal 31). The drive will display 'rdY' • Close the run signal (terminal 26 or 27). The lower display will flash 'Auto' and 'tunE' alternatively, while the drive is performing the autotune • Wait for the drive to display 'inh' and for the motor to come to a standstill If the drive trips, see Chapter 13 *Diagnostics* on page 167. • Remove the drive enable and run signal from the drive.	
Save parameters	Select SAVE in Pr **xx.00** (**SE00, 0.21**) Press the red ⊖ reset button or toggle the reset digital input (ensure Pr **xx.00** (**SE00, 0.21**) returns to 'no Act').	
Run	Drive is now ready to run • Close enable signal • Close run signal • Provide speed reference	⊙

7.2   Quick start commissioning / start-up (from USA defaults)

Action	Detail	
Before power-up	Ensure: • Drive Enable signal is not given (terminal 31) • Run signal is not given • Motor connected • Tacho connected if one is being used • Encoder connected if one is being used	
Power-up the drive	Ensure: • Drive displays 'inh' **NOTE** Motor thermistor input is disabled by default. If motor thermistor is available the thermistor should be used. The protection is enabled with Pr **7.15** (**in01**, **0.81**). For drive trips, see Chapter 13 *Diagnostics* on page 167.	
Enter motor nameplate details	Enter: • Armature rated voltage in Pr **5.09** (**SE06, 0.27**) (V) • Motor rated current in Pr **5.07** (**SE07, 0.28**) (A) • Motor rated speed (base speed) in Pr **5.08** (**SE08, 0.29**) (rpm) • Field rated voltage in Pr **5.73** (**SE11, 0.32**) (V)	

Set motor feedback parameters	**Incremental encoder basic set-up**
	Enter:
	• Drive encoder type in Pr **3.38** (**Fb07, 0.77**) = Ab (0): Quadrature encoder
	
	⚠ **CAUTION** Setting the encoder voltage supply too high for the encoder could result in damage to the feedback device.
	
	• Encoder power supply in Pr **3.36** (**Fb06, 0.76**) = 5V (0), 8V (1), 15V (2) or 24V (3)
	NOTE If output voltage from the encoder is >5V, then the termination resistors must be disabled Pr **3.39** (**Fb08, 0.78**) to 0.
	
	• Drive encoder lines per revolution (LPR) in Pr **3.34** (**Fb05, 0.75**) (set according to encoder)
	• Drive encoder termination resistor setting in Pr **3.39** (**Fb08, 0.78**)
	    0 = A-A\, B-B\, Z-Z\ termination resistors disabled
	    1 = A-A\, B-B\, termination resistors enabled, Z-Z\ termination resistors disabled
	    2 = A-A\, B-B\, Z-Z\ termination resistors enabled
	
	Tachometer set-up
	Enter:
	• Tachometer voltage rating Pr **3.51** (**Fb02, 0.72**) (V/1000 rpm)
	• Tachometer input mode Pr **3.53** (**Fb03, 0.73**)	

Set maximum speed	Enter: • Maximum speed in Pr **1.06** (**SE02, 0.23**) (rpm) **NOTE** For field weakening the field controller needs to be set-up in current control by setting Pr **5.75** = OFF, setting the rated field current into Pr **5.70** (**SE10, 0.31**)and setting Pr **5.64** to On. For field weakening in Estimated Speed Mode please refer to Chapter 8 *Optimization* on page 78.	
Set acceleration / deceleration rates	Enter: • Acceleration rate in Pr **2.11** (**SE03, 0.24**) (time to accelerate to maximum speed) • Deceleration rate in Pr **2.21** (**SE04, 0.25**) (time to decelerate from maximum speed)	
Enable the field controller	**Field controller set-up** • Select field mode by setting Pr **5.78** = IntrnL (Internal field controller is used), Etrnl (External half control), E FULL (External in full control). • Set Pr **5.77** (**SE12**, **0.33**) = On to enable the field.	

Action	Detail	
Static autotune	Mentor MP is able to perform either a static, rotating or continuous autotune. The motor must be at a standstill before an autotune is enabled. **Static autotune for current loop gains** When this operation is performed the drive will perform an estimation of *Motor constant* (Pr **5.15**), *Continuous proportional gain* (Pr **4.13**), *Continuous integral gain* (Pr **4.14**), *Discontinuous integral gain* (Pr **4.34**), Back EMF set point (Pr **5.59**), *Armature resistance* (Pr **5.61**) and *Flux loop I gain* (Pr **5.72**) with respect to the selected motor map and store the values. To perform a static autotune: • Set Pr **5.12** (**SE13, 0.34**)= 1 • Close the Drive Enable signal (terminal 31). The drive will display 'rdY' • Close the run signal (terminal 26 or 27). The lower display will flash 'Auto' and 'tunE' alternatively, while the drive is performing the autotune • Remove the enable signal when the autotune has finished • Remove the run signal **NOTE** A rotating autotune Pr **5.12** (**SE13**, **0.34**) = 2 should not be carried out when the field controller is in voltage mode, Pr **5.75** = On (USA default).	

Checking speed feedback	• Close the enable signal. Close the run signal (terminal 26 or 27). Provide speed reference to run the drive up to a low speed, the drive will regulate its own estimated speed.
	• Check that the feedback device is functioning correctly:
	    For encoder speed feedback - Check encoder speed feedback Pr **3.27** (**Fb09, 0.79**).
	    For tachometer speed feedback - Check tachometer speed feedback Pr **3.52** (**Fb04, 0.74**).
	• When the feedback device being used is seen to be functioning correctly, stop the drive and select the correct feedback device using Pr **3.26** (**Fb01, Pr 0.71**).	

Save parameters	Select SAVE in Pr **xx.00** (**SE00, 0.21**) Press the red ⊘ reset button or toggle the reset digital input (ensure Pr **xx.00** (**SE00, 0.21**) returns to 'no Act').	
Run	Drive is now ready to run • Close enable signal • Close run signal • Provide speed reference	

7.3 CTSoft software commissioning / start-up tool

CTSoft can be used for commissioning / start-up and monitoring, drive parameters can be uploaded, downloaded and compared, and simple or custom menu listings can be created. Drive menus can be displayed in standard list format or as live block diagrams. CTSoft includes a migration wizard that allows Mentor II parameters to be migrated to the Mentor MP. CTSoft is able to communicate with a single drive or a network.

CT Soft can be found on the CD which is supplied with the drive and is also available for download from the website www.controltechniques.com (file size approximately 100MB).

7.3.1 CTSoft system requirements:

1. Pentium IV 1000MHz or better recommended.
2. Windows Vista, Windows XP or Windows 2000 (Including the latest Service Packs) only.
3. Internet Explorer V5 or later should also be installed.
4. Microsoft .Net Framework 2.0 must also be installed.
5. Absolute minimum of 800 x 600 screen resolution. A resolution of 1024 x 768 or above is recommended.
6. Adobe Acrobat 5.05 or later (for parameter help).
7. 256MB RAM

NOTE

You must have administration rights under Windows NT/2000/XP/Vista to install.

7.3.2 To install CTSoft from the CD

1. Ensure that any previous copies of CTSoft have been uninstalled before proceeding with the installation (existing projects will not be lost).
2. Insert the CD. The auto-run software should start up the front-end screen from which CTSoft can be selected. User guides for the supported drive models are included with CTSoft application. When help is requested, CTSoft links to the parameter in the *Mentor MP Advanced User Guide.*

7.4   Setting up a feedback device

This section shows more detailed information on parameter settings that must be made to each of the compatible encoder types with Mentor MP. For more information on the parameters listed here please refer to the *Mentor MP Advanced User Guide*.

7.4.1   Detailed feedback device commissioning/start-up information

Standard quadrature encoder with or without marker pulse		
Encoder type	Pr **3.38** (**Fb07, 0.77**)	**Ab** (0) Standard quadrature incremental encoder with or without marker pulse
Encoder power supply voltage	Pr **3.36** (**Fb06, 0.76**)	**5V** (0), **8V** (1) or **15V** (2) or **24V** (3) NOTE If the voltage from the encoder is >5V, then the termination resistors must be disabled Pr **3.39** (**Fb08, 0.78**) to 0
Encoder number of lines per revolution	Pr **3.34** (**Fb05, 0.75**)	Set to the number of lines per revolution of the encoder
Encoder marker mode	Pr **3.35**	**0** = The marker system operates in a conventional manner, **1** = the marker causes a full position reset.
Encoder termination selection	Pr **3.39** (**Fb08, 0.78**)	**0** = A, B, Z termination resistors disabled, **1** = A, B termination resistors enabled and Z termination resistors disabled, **2** = A, B, Z termination resistors enabled
Encoder error detection level	Pr **3.40**	**0** = No wire break detect, **1** = Wire break detect on A and B (need termination enabled for 5V signals), **2** = Wire break detect on A, B and Z (need termination enabled for 5V signals)

Incremental encoder with frequency and direction, or forward reverse signals, with or without marker pulse		
Encoder type	Pr **3.38** (**Fb07, 0.77**)	**Fd** (2) Incremental encoder with frequency and direction outputs, with or without marker pulse, **Fr** (3) Incremental encoder with forward and reverse outputs, with or without marker pulse
Encoder power supply voltage	Pr **3.36** (**Fb06, 0.76**)	**5V** (0), **8V** (1) or **15V** (2) or **24V** (3) NOTE If the voltage from the encoder is >5V, then the termination resistors must be disabled Pr **3.39** (**Fb08, 0.78**) to 0
Encoder number of lines per revolution	Pr **3.34** (**Fb05, 0.75**)	Set to the number of lines per revolution of the encoder divide by 2
Encoder marker mode	Pr **3.35**	**0** = The marker system operates in a conventional manner, **1** = the marker causes a full position reset.
Encoder termination selection	Pr **3.39** (**Fb08, 0.78**)	**0** = A, B, Z termination resistors disabled, **1** = A, B termination resistors enabled and Z termination resistors disabled, **2** = A, B, Z termination resistors enabled
Encoder error detection level	Pr **3.40**	**0** = No wire break detect, **1** = Wire break detect on A and B (need termination enabled for 5V signals), **2** = Wire break detect on A, B and Z (need termination enabled for 5V signals)

8   Optimization

Before attempting to tune the drive the following data is required

- Armature full load current
- Armature voltage
- Field current
- Field voltage
- Base speed
- Maximum speed

In the following worked example the data below has been used

- Armature full load current = 67A with an overload of 90A for up to 30 seconds
- Armature voltage = 500V
- Field current = 1.85A
- Field voltage = 300V
- Base speed = 1750 rpm
- Maximum speed = 2500rpm

8.1   Armature current

- Set the motor rated current in Pr **5.07** (**SE07, 0.28**) to 67A.
- Set current limits in Pr **4.05** and Pr **4.06** to 90/67 x 100 = 134%
- Set the motor thermal time constant in Pr **4.15** = -30 / ln(1 - (1.05 / 1.34)^2) = 31.5

8.2   Speed feedback

8.2.1   Estimated speed feedback

For estimated speed feedback set Pr **3.26** (**Fb01, 0.71**) to ESt SPd. This uses an estimated speed feedback based on the motor back emf, motor rated speed, motor rated voltage, armature resistance, armature current and field flux feedback.

8.2.2   Tachometer speed feedback

For tachometer speed feedback set Pr **3.26** (**Fb01, 0.71**) to tACHO. Set the tachometer voltage rating in V/1000rpm in Pr **3.51** (**Fb02, 0.72**) and the tachometer input mode Pr **3.53** (**Fb03, 0.73**) to suit the type of tachometer used.

8.2.3   Encoder speed feedback

For encoder speed feedback set Pr **3.26** (**Fb01, 0.71**) to drv. Set the lines per revolution (Pr **3.34** (**Fb05, 0.75**)), encoder supply voltage (Pr **3.36** (**Fb06, 0.76**)) and encoder type (Pr **3.38** (**Fb07, 0.77**)).

8.2.4   Solutions Module speed feedback

If an Solutions Module is being used to provide speed feedback then Pr **3.26** (**Fb01, 0.71**) should be set to SLot1, SLot2, or SLot3.

8.3   Field current

The rated field current is set in Pr **5.70** (**SE10, 0.31**). When the field current equals the compensated rated field current (see Pr **5.74**), 100% field flux is produced.

8.3.1   Field weakening with a speed feedback device

If field weakening is required the field compensation factor (Pr **5.74**), the motor saturation breakpoints (Pr **5.29**, Pr **5.30**) and the voltage at which field weakening is required to begin (Pr **5.59**) must be set.

Setting up the drive in field weakening is straightforward when a speed feedback device is available. The rotating autotune (Pr **5.12** (**SE13, 0.34**) = 2) automatically sets up the parameters above. Follow the quick start commissioning / start-up (from European defaults) as shown in Table 6-1 on page 64 to set up the drive. Enable field weakening (Pr **5.64** = On). Save parameters.

For field weakening from USA defaults Pr **5.75** *Field voltage mode* should be set to OFF. Pr **5.28** *Field weakening compensation disable* should be set to OFF. Follow the quick start commissioning / start-up (from European defaults) as shown in Table 6-1 on page 64 to set up the drive. Enable field weakening (Pr **5.64** = On). Save parameters.

8.3.2   Field weakening in estimated speed mode (no speed feedback device)

The Rotating Autotune (Pr **5.12** (**SE13, 0.34**) = 2) sets up the field controller for more accurate flux control and open loop speed accuracy. The rotating autotune needs so to know the motor speed and so a speed feedback device has to be connected to the drive before a rotating autotune can be carried out. In some applications a speed feedback device may not be required and so the procedure below allows the user to manually adjust the field controller parameters to achieve better open loop speed control.

- Follow the quick start commissioning / start-up (from European defaults) as shown in Table 6-1 *Pre-defined sub block parameters* on page 64 until a static autotune (Pr **5.12** (**SE13, 0.34**) = 1) has been carried out.
- Set Pr **5.64** *Field weakening enable* to On.
- Ensure that Pr **5.29** , Pr **5.30**, Pr **5.68** and Pr **5.74** are set to their default values of 50%, 75%, 100% and 100% respectively.
- Set the speed demand to 1/4 of *Base speed* (Pr **5.08** (**SE08, 0.29**)) and run the machine up to speed and check the speed of the machine using a hand held device.
- If the machine speed is lower than 1/4 of base speed (which is normally the case) adjust the *Field compensation factor* (Pr **5.74**) down until the correct machine speed is reached. If the machine speed is higher than $1/4$ of base speed (only possible if the motor nameplate field current is low), adjust the rated field current (Pr **5.70** (**SE10, 0.31**)) up until the correct machine speed is reached.
- Set Pr **5.68** *Maximum flux* to 75% and measure the actual speed of the machine (speed 75)
- Set Pr **5.68** *Maximum flux* to 50% and measure the actual speed of the machine (speed 50).
- Stop the machine and set Pr **5.68** *Maximum flux* back to 100%.
- Set Pr **5.29** *Motor saturation breakpoint* 1 = 50 x set speed / actual speed (Speed 50)
- Set Pr **5.30** *Motor saturation breakpoint 2* = 75 x set speed / actual speed (speed 75).
- Save parameters.

For field weakening from USA defaults Pr **5.75** *Field voltage mode* should be set to OFF. Pr **5.28** *Field weakening compensation disable* should be set to OFF. The procedure above should then be followed to set up the drive for field weakening.

8.3.3   Field economy

Field economy can be used to keep the field energized, at a low level of current (to prevent overheating), when the motor is not running to prevent condensation forming in the motor. The field economy level and the timeout can be adjusted.

To use this function it is necessary to set:

- Set Pr **5.65** to enable the field economy timeout
- Set Pr **5.67** to the percentage of full field that you want to use in economy mode e.g 10%.
- Set Pr **5.66** to the time after the drive enable signal is removed to the field current reducing to the economy level.

8.4   Current loop gains self-tuning

For optimum performance the current loop must be set-up. The dynamics of the current loop are principally a function of the electrical characteristics of a particular motor.

The drive determines the electrical characteristics of the motor by injecting current into the armature winding.

8.4.1   Static autotune for current loop gains

If Pr **5.12** (**SE13, 0.34**) is set to a 1, the drive is enabled and a run command is applied in either direction the drive performs a static autotune test. The test will not start unless the drive is disabled and before the test is initiated by applying the enable or run, i.e. it will not start unless the drive is in a stop state.

When this operation is performed the drive will determine the *Motor constant* (Pr **5.15**), *Continuous proportional gain* (Pr **4.13**), *Continuous integral gain* (Pr **4.14**), *Discontinuous integral gain* (Pr **4.34**), *Back EMF set point* (Pr **5.59**), *Armature resistance* (Pr **5.60**) and *Flux loop I gain* (Pr **5.72**) with respect to the selected motor map and store the values.

8.4.2   Continuous autotune for current loop gains

In the static autotune the armature current loop gains are set up with no flux in the motor. In some motors the inductance of the armature changes significantly when flux is present in the machine. If this is the case, a continuous autotune can be enabled to correct the gains for the fluxed machine.

When Pr **5.26** is set to On, the continuous autotune is enabled which continuously monitors the motor ripple and adjusts *Motor constant* (Pr **5.15**), *Continuous proportional gain* (Pr **4.13**) and *Discontinuous integral gain* (Pr **4.34**) for optimum performance.

The static autotune should still be carried out because *Continuous integral gain* (Pr **4.14**) is not set by the continuous autotune.

Calculation of the gains is suspended when the voltage field weakening loop becomes active so that the gains are not increased when the field is weakened (less flux in the machine).

This function does not operate when the drives are set-up in serial 12 pulse.

8.4.3   Drive commissioning output

The Mentor MP has a test pin that gives instantaneous armature current feedback. The pin is identified by a half sign wave symbol and is located to the right of the tachometer terminals. An oscilloscope probe can be attached to this pin to monitor the armature current.

8.5   Speed loop gains tuning

The speed loop gains control the response of the speed controller to a change in speed demand. The speed controller includes proportional (Kp) and integral (Ki) feed forward terms, and a differential (Kd) feedback term. The drive holds two sets of these gains and either set may be selected for use by the speed controller with Pr **3.16**

Pr **3.16** may be changed when the drive is enabled or disabled.

- If Pr **3.16** = 0 - gains Kp1, Ki1 and Kd1 are used
- If Pr **3.16** = 1 - gains Kp2, Ki2 and Kd2 are used

8.5.1   Proportional gain (Kp) Pr 3.10 (SP01, 0.61) and Pr 3.13

If Kp has a value and the integral gain Ki is set to zero the controller will only have a proportional term, and there must be a speed error to produce a torque reference. Therefore as the motor load increases there will be a difference between the reference and actual speeds.

This effect, called regulation, depends on the level of the proportional gain, the higher the gain the smaller the speed error for a given load.

If the proportional gain is too high either the acoustic noise produced by speed feedback quantization becomes unacceptable, or the stability limit is reached.

8.5.2   Integral gain (Ki) Pr 3.11 (SP02, 0.62) and Pr 3.14

The integral gain is provided to prevent speed regulation. The error is accumulated over a period of time and used to produce the necessary torque demand without any speed error. Increasing the integral gain reduces the time taken for the speed to reach the correct level and increases the stiffness of the system, i.e. it reduces the positional displacement produced by applying a load torque to the motor. Unfortunately increasing the integral gain also reduces the system damping giving overshoot after a transient. For a given integral gain the damping can be improved by increasing the proportional gain. A compromise must be reached where the system response, stiffness and damping are all adequate for the application. The term is implemented in the form of Σ(Ki x error), and so the integral gain can be changed when the controller is active without causing large torque demand transients.

8.5.3   Differential gain (Kd) Pr 3.12 (SP03, 0.63) and Pr 3.15

The differential gain is provided in the feedback of the speed controller to give additional damping. The differential term is implemented in a way that does not introduce excessive noise normally associated with this type of function. Increasing the differential term reduces the overshoot produced by under-damping, however, for most applications the proportional and integral gains alone are sufficient.

8.5.4   Manually setting up the speed loop gains
Figure 8-1   Responses

There are two methods of tuning the speed loop gains dependant on the setting of Pr **3.17**:

1.   Pr **3.17** = 0, User set-up.
This involves the connecting of an oscilloscope to analog output 1 to monitor the speed feedback. Give the drive a step change in speed reference and monitor the response of the drive on the oscilloscope.

The proportional gain (Kp) should be set up initially. The value should be increased up to the point where the speed overshoots and then reduced slightly.

The integral gain (Ki) should then be increased up to the point where the speed becomes unstable and then reduced slightly.

It may now be possible to increase the proportional gain to a higher value and the process should be repeated until the system response matches the ideal response as shown.

Figure 8-1 shows the effect of incorrect P and I gain settings as well as the ideal response.

2.   Pr **3.17** = 1, Bandwidth set-up
If bandwidth based set-up is required, the drive can calculate Kp and Ki if the following parameters are set up correctly:

Pr **3.18** - Motor and load inertia - it is possible to measure the load inertia as part of the auto-tuning process (see Pr **5.12** (**SE13, 0.34**)).

Pr **3.20** - Required bandwidth,

Pr **3.21** - Required damping factor,

Pr **5.32** - Motor torque per amp (Kt).

8.5.5 Speed loop gains for very high inertia

Pr **3.17** = 2 - Kp gain times 16

If this parameter is set to 2 the Kp gain (from whichever source), is multiplied by 16. This is intended to boost the range of Kp for applications with very high inertia. It should be noted that if high values of Kp are used it is likely that the speed controller output will need to be filtered, see (Pr **3.42**). If the feedback is not filtered it is possible that the output of the speed controller will be a square wave that changes between the current limits causing the integral term saturation system to malfunction.

8.6 Current limit tapers

With some motors the commutation limit of the motor requires that the maximum armature current be reduced at higher speeds, the current limit tapers can be used to provide this speed dependent current limit.

For more information refer to section 11.22.4 *Current limit tapers* on page 142.

9 SMARTCARD operation

9.1 Introduction

This is a standard feature that enables simple configuration of parameters in a variety of ways. The SMARTCARD can be used for:

- Parameter copying between drives
- Saving whole drive parameter sets
- Saving 'differences from default' parameter sets
- Storing Onboard PLC programs
- Automatically saving all user parameter changes for maintenance purposes
- Loading complete motor map parameters.

Refer to Figure 9-1 for installing the SMARTCARD. Ensure the SMARTCARD is inserted with the MP arrow pointing upwards.

The drive only communicates with the SMARTCARD when commanded to read or write, this means that the card may be 'hot swapped'.

Figure 9-1 Installation of the SMARTCARD

9.2 Easy saving and reading

The SMARTCARD has 999 individual data block locations. Each individual location from 1 to 499 can be used to store data.

The drive can support SMARTCARDS that have a capacity of between 4kB and 512kB.

The usage of the data block locations in the SMARTCARD are shown in Table 9-1.

Table 9-1 SMARTCARD data blocks

Data block	Type	Example of usage
1 to 499	Read / Write	Application set-up
500 to 999	Read Only	Macros

Parameter sets labelled as 'Differences from default' will be much smaller than whole parameter sets. Therefore they use a lot less memory because most applications only require a few parameters to be changed from the default setting.

The whole card may be protected from writing or erasing by setting the read-only flag as shown in section 9.3.9 *9888 / 9777 - Set / clear the SMARTCARD read only flag* on page 83.

Either of these indications will tell the user that data is being transferred to or from the SMARTCARD:

- SM-Keypad: The decimal point after the fourth digit in the upper display will flash.
- MP-Keypad: The symbol 'CC' will appear in the lower left hand corner of the display.

The card should not be removed during data transfer because the drive will trip. If a trip occurs you must either try to transfer the data again or, in the case of a card-to-drive transfer, the default parameters should be loaded.

9.3 Transferring data

When a code is entered into Pr **xx.00** and the drive is subsequently reset, the drive will carry out the actions listed in Table 9-2.

Table 9-2 Transferring data

Codes	Actions
Pr **x.00** = rEAd 1	Transfer SMARTCARD data block 1 to the drive.
Pr **x.00** = rEAd 2	Transfer SMARTCARD data block 2 to the drive.
Pr **x.00** = rEAd 3	Transfer SMARTCARD data block 3 to the drive.
Pr **x.00** = PrOg 1	Transfer drive parameters as difference from default to SMARTCARD data block number 1.
Pr **x.00** = PrOg 2	Transfer drive parameters as difference from default to SMARTCARD data block number 2.
Pr **x.00** = PrOg 3	Transfer drive parameters as difference from default to SMARTCARD data block number 3.
Pr **x.00** = 2001	Transfer drive parameters as difference from defaults to a bootable SMARTCARD data block with block number 1. This will clear data block 1 on the card if it already exists.
Pr **x.00** = 3yyy	Transfer drive parameters to a SMARTCARD data block number yyy.
Pr **x.00** = 4yyy	Transfer drive data as difference from defaults to SMARTCARD data block number yyy.
Pr **x.00** = 5yyy	Transfer drive user program to SMARTCARD data block number yyy.
Pr **x.00** = 6yyy	Transfer SMARTCARD data block yyy to the drive.
Pr **x.00** = 7yyy	Erase SMARTCARD data block yyy.
Pr **x.00** = 8yyy	Compare drive parameters with data block yyy.
Pr **x.00** = 9555	Clear SMARTCARD warning suppression flag.
Pr **x.00** = 9666	Set SMARTCARD warning suppression flag.
Pr **x.00** = 9777	Clear SMARTCARD read-only flag.
Pr **x.00** = 9888	Set SMARTCARD read-only flag.
Pr **x.00** = 9999	Erase SMARTCARD.
Pr **11.42** (**SE09, 0.30**) = Read	Transfer SMARTCARD data block 1 to the drive provided it is a parameter file.
Pr **11.42** (**SE09, 0.30**) = Prog	Transfer drive parameters to a SMARTCARD data block number 1.
Pr **11.42** (**SE09, 0.30**) = Auto	Transfer drive parameters to a SMARTCARD data block with data block number 1 provided.
Pr **11.42** (**SE09, 0.30**) = boot	Pr **11.42** (**SE09, 0.30**) has been changed since power-up.

Where yyy indicates the data block number 001 to 999, refer to Table 9-1 for restrictions on data block numbers.

NOTE

If the read only flag is set then only codes 6yyy or 9777 are effective.

9.3.1 Writing to the SMARTCARD

3yyy - Transfer data to the SMARTCARD

The data block contains the complete parameter data from the drive, i.e. all user-save (US) parameters except parameters with the NC coding bit set. Power-down save (PS) parameters are not transferred to the SMARTCARD.

4yyy - Write default differences to a SMARTCARD

The data block only contains the parameter differences from the last time default settings were loaded.

Six bytes are required for each parameter difference. The data density is not as high as when using the 3yyy transfer method as described in the section *3yyy - Transfer data to the SMARTCARD* but in most cases the number of differences from default is small and the data blocks are therefore smaller. This method can be used for creating drive macros. PS parameters are not transferred to the SMARTCARD.

Writing a parameter set to the SMARTCARD

Setting Pr **11.42** (**SE09, 0.30**) to Prog (2) and resetting the drive will save the parameters to the SMARTCARD, i.e. this is equivalent to writing 3001 to Pr **xx.00**. All SMARTCARD trips apply except 'C.Chg'. If the data block already exists it is automatically overwritten.

When the action is complete this parameter is automatically reset to nonE (0).

9.3.2   Reading from the SMARTCARD

6yyy - Read default differences from a SMARTCARD

When the data is transferred back to a drive, using 6yyy in Pr **xx.00**, it is transferred to the drive RAM and the drive EEPROM. A parameter save is not required to retain the data after power-down. Set-up data for any Solutions Modules installed are stored on the card and are transferred to the destination drive. If the Solutions Modules are different between the source and destination drive, the menus for the slots where the Solutions Module categories are different are not updated from the card and will contain their default values after the copying action.

The drive will produce a 'C.Optn' trip if the Solutions Modules installed to the source and destination drive are different or are in different slots. If the data is being transferred to a drive of a different voltage or current rating a 'C.rtg' trip will occur.

Table 9-3 lists the rating dependent parameters (RA coding bit set) that will not be written to the destination drive and will contain their default values after the copying action.

Table 9-3   Rating dependent parameters

Parameter	Function
4.05	Current limit
4.06	Current limit
4.07	Current limit
4.24	User current maximum scaling
5.07 (**SE07, 0.28**)	Motor rated current
5.09 (**SE06, 0.27**)	Armature rated voltage

Reading a parameter set from the SMARTCARD

Setting Pr **11.42** (**SE09, 0.30**) to rEAd (1) and resetting the drive will transfer the parameters from the card into the drive parameter set and the drive EEPROM, i.e. this is equivalent to writing 6001 to Pr **xx.00**. All SMARTCARD trips apply. Once the parameters are successfully copied this parameter is automatically reset to nonE (0). Parameters are saved to the drive EEPROM after this action is complete.

> **NOTE**
> This operation is only performed if data block 1 on the card is a full parameter set (3yyy transfer) and not a default difference file (4yyy transfer). If data block 1 does not exist a 'C.dAt' trip occurs.

9.3.3   Auto saving parameter changes

This setting causes the drive to automatically save any changes made to Menu 0 parameters on the drive to the SMARTCARD. The latest Menu 0 parameter set in the drive is therefore always backed up on the SMARTCARD.

Changing Pr **11.42** (**SE09, 0.30**) to Auto (3) and resetting the drive will immediately save the complete parameter set from the drive to the card, i.e. all User Save (US) parameters except parameters with the NC coding bit set. Once the whole parameter set is stored only the individual modified menu 0 parameter setting is updated.

Advanced parameter changes are only saved to the card when Pr **xx.00** is set to a 1000 and the drive reset.

All SMARTCARD trips apply, except 'C.Chg'. If the data block already contains information it is automatically overwritten.

If the card is removed when Pr **11.42** (**SE09, 0.30**) is set to 3, Pr **11.42** (**SE09, 0.30**) is then automatically set to nonE (0).

When a new SMARTCARD is installed Pr **11.42** (**SE09, 0.30**) must be set back to Auto (3) by the user and the drive reset so the complete parameter set is rewritten to the new SMARTCARD if auto mode is still required.

When Pr **11.42** (**SE09, 0.30**) is set to Auto (3) and the parameters in the drive are saved, the SMARTCARD is also updated, therefore the SMARTCARD becomes a copy of the drives stored configuration.

At power up, if Pr **11.42** (**SE09, 0.30**) is set to Auto (3), the drive will save the complete parameter set to the SMARTCARD. The drive will display 'cArd' during this operation. This is done to ensure that if a user puts a new SMARTCARD in during power down the new SMARTCARD will have the correct data.

> **NOTE**
> When Pr **11.42** (**SE09, 0.30**) is set to Auto (3) the setting of Pr **11.42** (**SE09, 0.30**) itself is saved to the drive EEPROM but NOT to the SMARTCARD.

9.3.4   Booting up from the SMARTCARD on every power up (Pr 11.42 (SE09, 0.30) = boot (4))

When Pr **11.42** (**SE09, 0.30**) is set to boot (4) the drive operates the same as Auto mode, except when the drive is powered up. The parameters on the SMARTCARD will be automatically transferred to the drive at power-up if the following are true:

*   A card is inserted in the drive
*   Parameter data block 1 exists on the card
*   The data in block 1 is type 1 to 5 (as defined in Pr **11.38**)
*   Pr **11.42** (**SE09, 0.30**) on the card set to boot (4)

The drive will display 'boot' during this operation. If the drive mode is different from that on the card, the drive gives a 'C.Typ' trip and the data is not transferred.

If 'boot' mode is stored on the copying SMARTCARD this makes the copying SMARTCARD the master device. This provides a very fast and efficient way of re-programming a number of drives.

If data block 1 contains a bootable parameter set and data block 2 contains an Onboard PLC program (type 17 as defined in Pr **11.38**), then the onboard PLC program will be transferred to the drive at power up along with the parameter set in data block 1.

> **NOTE**
> "Boot" mode is saved to the card, but when the card is read, the value of Pr **11.42** (**SE09, 0.30**) is not transferred to the drive.

9.3.5   Booting up from the SMARTCARD on every power up (Pr xx.00 = 2001)

It is possible to create a difference from default bootable file by setting Pr **xx.00** to 2001 and resetting the drive. This type of file causes the drive to behave in the same way at power-up as a file created with boot mode set up with Pr **11.42** (**SE09, 0.30**). The difference from the default file is that it has the added advantage of including Menu 20 parameters.

Setting Pr **xx.00** to 2001 will overwrite data block 1 on the card, if it already exists.

If a data block 2 exists and contains an Onboard PLC program (type 17 as defined in Pr **11.38**), this will also be loaded after the parameters have been transferred.

A bootable difference from default file can only be created in one operation and parameters cannot be added as they are saved via Menu 0.

9.3.6   Comparing drive full parameter set with the SMARTCARD values

Setting 8yyy in Pr **xx.00**, will compare the SMARTCARD file with the data in the drive:

*   If the compare is successful Pr **xx.00** is simply set to 0
*   If the compare fails a 'C.cpr' trip is initiated

9.3.7 7yyy / 9999 - Erasing data from the SMARTCARD

Data can be erased from the SMARTCARD one data block at a time or with data blocks 1 to 499 in selected together.

- Setting 7yyy in Pr **xx.00** will erase SMARTCARD data block yyy
- Setting 9999 in Pr **xx.00** will erase SMARTCARD data blocks 1 to 499

9.3.8 9666 / 9555 - Set / clear SMARTCARD warning suppression flag

1. If the Solutions Module(s) installed to the source and destination drive are different, or are in different slots, the drive will produce a 'C.Optn' trip.
2. If the data is being transferred to a drive of a different voltage or current rating a 'C.rtg' trip will occur.

It is possible to suppress these trips by setting the warning suppression flag. If this flag is set the drive will not trip if the Solutions Module(s) or drive ratings are different between the source and the destination drives. The Solutions Module or rating dependent parameters will not be transferred.

- Setting 9666 in Pr **xx.00** will set the warning suppression flag
- Setting 9555 in Pr **xx.00** will clear the warning suppression flag

9.3.9 9888 / 9777 - Set / clear the SMARTCARD read only flag

The SMARTCARD may be protected from writing or erasing by setting the read only flag. If an attempt is made to write or erase a data block when the read only flag is set, a 'C.rdo' trip is initiated.

When the read only flag is set only codes 6yyy or 9777 are effective.

- Setting 9888 in Pr **xx.00** will set the read only flag
- Setting 9777 in Pr **xx.00** will clear the read only flag

9.4 Data block header information

Each data block stored on a SMARTCARD has header information detailing the following:

- A number which identifies the data block (Pr **11.37**)
- Type of data stored in the data block (Pr **11.38**)
- Drive mode if the data is parameter data (Pr **11.38**)
- Version number (Pr **11.39**)
- Checksum (Pr **11.40**)
- Read-only flag
- Warning suppression flag

The header information for each data block that has been used can be viewed in Pr **11.38** to Pr **11.40** by increasing or decreasing the data block number set in Pr **11.37**.

If Pr **11.37** is set to 1000: the checksum parameter (Pr **11.40**) shows the number of bytes left on the card in 16 byte pages.

If Pr **11.37** is set to 1001: the checksum parameter (Pr **11.40**) shows the total capacity of the card in 16 byte pages. Therefore, for a 4kB card this parameter would show 254.

If Pr **11.37** is set to 1002: the checksum parameter (Pr **11.40**) shows the state of the read-only (bit 0) and warning suppression flags (bit 1).

If there is no data on the card: Pr **11.37** can only have values of 0 or 1000 to 1002.

9.5 SMARTCARD parameters

11.36	SMARTCARD parameter data previously loaded						
RO	Uni	NC				PT	US
↕		0 to 999		⇨		0	

This parameter shows the number of the data block last parameter or difference from default data block transferred from a SMARTCARD to the drive.

11.37	SMARTCARD data number						
RW	Uni	NC					
↕		0 to 1002		⇨		0	

This parameter shows the data blocks that are stored on a SMARTCARD with header information, including a number to identify the data block.

11.38	SMARTCARD data type/mode						
RO	Txt	NC				PT	
↕		0 to 18		⇨			

This parameter gives the type/mode of the data block selected with Pr **11.37** as shown in the following table.

Table 9-4 Pr 11.38 types and modes

Pr 11.38	String	Type/Mode
0	FrEE	Value when Pr **11.37** = 0
1	3C.SE	Commander SE mode parameter file (not used)
2	3OpEn.LP	Open-loop mode parameter file
3	3CL.VECt	Closed-loop vector mode parameter file
4	3SErVO	Servo mode parameter file
5	3REGEn	Regen mode parameter file
6	3DC	DC mode parameter file
7	3Un	Unused
8	3Un	Unused
9	4C.SE	Commander SE mode difference from default file (not used)
10	4OpEn.LP	Open-loop mode difference from default file
11	4CL.VECt	Closed-loop vector mode difference from default file
12	4SErVO	Servo mode difference from default file
13	4REGEn	Regen mode difference from default file
14	4DC	DC Mode difference from default file
15 & 16	4Un	Unused
17	LAddEr	Onboard Application Lite user program file
18	Option	A file containing user defined data (the file is normally created by an SM-Applications Solutions Module)

11.39	SMARTCARD data version						
RW	Uni	NC					
↕		0 to 9999		⇨		0	

This parameter gives the version number of the data block.

11.40	SMARTCARD data checksum						
RO	Uni	NC				PT	
↕		0 to 65335		⇨		0	

This parameter gives the checksum of the data block, space left on the card, the total space on the card or the card flags. Refer to Pr **11.37** for information.

11.42 (SE09, 0.30)	Parameter copying						
RW	Txt	NC					US*
⇕	0 to 4			⇨		0	

NOTE

* Mode 1 and Mode 2 are not saved when the drive parameters are saved. This parameter can only be saved to EEPROM if it has a value of 0, 3 or 4.

Table 9-5   Pr 11.38 actions

Actions	Value	Result
None	0	Inactive
Reading	1	Read parameter set from SMARTCARD
Programming	2	Program parameter set to the SMARTCARD
Auto	3	Auto save
Boot	4	Boot mode

9.6   SMARTCARD trips

After an attempt to read, write or erase data to or from a SMARTCARD a trip may occur if there has been a problem with the command. Table 9-6 lists the trip indications and conditions that will cause the SMARTCARD to trip,

Table 9-6   Trip conditions

Trip	Condition
C.boot	**SMARTCARD trip: The menu 0 parameter modification cannot be saved to the SMARTCARD because the necessary file has not been created on the SMARTCARD**
177	A write to a Menu 0 parameter has been initiated with the keypad by exiting edit mode and Pr **11.42** (**SE09, 0.30**) is set for auto or boot mode. However the necessary boot file has not been created on the SMARTCARD to take the new parameter value. This occurs when Pr **11.42** (**SE09, 0.30**) is changed to auto or boot mode, but the drive is not subsequently reset.
C.BUSy	**SMARTCARD trip: SMARTCARD can not perform the required function as it is being accessed by a Solutions Module**
178	An attempt has been made to access a SMARTCARD. However an Solutions Module is already accessing the SMARTCARD.
C.Chg	**SMARTCARD trip: Data location already contains data**
179	An attempt has been made to store data in a SMARTCARD data block that already exists.
C.Optn	**SMARTCARD trip: Solutions Modules installed are different between source drive and destination drive**
180	Parameter data or default difference data is being transferred from a SMARTCARD to the drive, but the Solutions Module categories are different between source and destination drives. This trip does not stop the data transfer, but is a warning that the data for the Solutions Modules that are different will be set to the default values and not the values from the card. This trip also applies if a compare is attempted between the data block and the drive.
C.Rdo	**SMARTCARD trip: SMARTCARD has the Read Only bit set**
181	An attempt has been made to modify a read-only SMARTCARD (i.e. erase the card, erase a file or create a file). A SMARTCARD is read-only if the read-only flag has been set or the card contains data blocks with numbers from 500 to 999. Attempting to create data blocks with numbers from 500 to 999 will always cause a trip.
C.Err	**SMARTCARD trip: SMARTCARD data is corrupted**
182	An attempt has been made to transfer a data block from a SMARTCARD to the drive or to compare a SMARTCARD data block and the checksum is incorrect or the data structure on the card is incorrect.
C.dat	**SMARTCARD trip: Data location specified does not contain any data**
183	An attempt has been made to transfer a data block from a SMARTCARD to the drive or to compare a SMARTCARD data block and the block does not exist.
C.FULL	**SMARTCARD trip: SMARTCARD full**
184	An attempt has been made to create a data block on a SMARTCARD, but there is not enough space on the card.
C.Acc	**SMARTCARD trip: SMARTCARD Read / Write fail**
185	An attempt has been made to access a SMARTCARD, but a card is not present or communications failure has occurred between the drive and the card. This trip is also produced if an attempt is made to access a data block that has already been opened by an Solutions Module.
C.rtg	**SMARTCARD trip: The voltage and/or current rating of the source and destination drives are different**
186	Parameter data or default difference data is being transferred from a SMARTCARD to the drive, but the current and /or voltage ratings are different between source and destination drives. This trip does not stop the data transfer, but is a warning that the data for the Solutions Modules that are different will be set to the default values and not the values from the card. This trip also applies if a compare is attempted between the data block and the drive.
C.Typ	**SMARTCARD trip: SMARTCARD parameter set not compatible with drive**
187	This trip is produced during a compare if the drive mode in the data block is different from the current drive mode and the file is a parameter or defaults differences file. This trip is also produced if an attempt is made to transfer parameters from a parameter or default difference to the drive if the drive mode in the data block is outside the allowed range of drive modes for the drive.
C.cpr	**SMARTCARD trip: The values stored in the drive and the values in the data block on the SMARTCARD are different**
188	A compare has been carried out between a data block on a SMARTCARD and the drive and the compare has failed. This trip only occurs if the compare has not already failed with the following trips: C.Typ, C.rtg, C.Optn, C.BUSy, C.Acc or C.Err.

Table 9-7 SMARTCARD status indications

Lower display	Description
boot	
A parameter set is being transferred from the SMARTCARD to the drive during power-up. For further information please refer to *section 9.3.4 Booting up from the SMARTCARD on every power up (Pr 11.42 (SE09, 0.30) = boot (4))* on page 82.	
cArd	
The drive is writing a parameter set to the SMARTCARD during power-up. For further information please refer to *section 9.3.3 Auto saving parameter changes* on page 82.	

10 Onboard PLC

10.1 Onboard PLC and SYPT Lite

The Mentor MP has the ability to store and execute a 6kB Onboard PLC ladder logic program without the need for additional hardware in the form of a Solutions Module.

The ladder logic program is written using SYPT Lite, a Windows™ based ladder diagram editor allowing the development of programs for execution in SM-Applications Plus.

Advantages of SYPT Lite:

*   SYPT Lite is designed to be easy to use and to make program development as simple as possible. The features provided are a sub-set of those in the SYPT program editor.
*   SYPT Lite programs are developed using ladder logic, a graphical language widely used to program PLCs (IEC 61131-3).
*   SYPT Lite allows the user to draw a ladder diagram representing a program.
*   SYPT Lite provides a complete environment for the development of ladder diagrams. Ladder diagrams can be created, compiled into user programs and downloaded to SM-Applications Plus for execution, via the RJ45 serial communications port on the front of the drive.
*   The run-time operation of the compiled ladder diagram on the target can also be monitored using SYPT Lite and facilities are provided to interact with the program on the target by setting new values for target parameters.
*   SYPT Lite is available on the CD that is supplied with the drive.

10.2 Benefits

The combination of the Onboard PLC and SYPT Lite means that Mentor MP can replace nano and some micro PLCs in many applications. The Onboard PLC programs can consist of up to a maximum of 50 ladder logic rungs (up to 7 function blocks and 10 contacts per rung). The Onboard PLC program can also be transferred to and from a SMARTCARD for backup or quick commissioning / start-up.

In addition to the basic ladder symbols, SYPT Lite contains a sub-set of the function from the full version of SYPT. These include:

*   Arithmetic blocks
*   Comparison blocks
*   Timers
*   Counters
*   Multiplexers
*   Latches
*   Bit manipulation

Typical applications for the Onboard PLC include,

*   Ancillary pumps
*   Fans and control valves
*   Interlocking logic
*   Sequences routines
*   Custom control words.

10.3 Limitations

Compared with the SM-Applications Plus or SM-Applications Lite V2 modules when programmed with SYPT, the Onboard PLC program has the following limitations:

*   The maximum program size is 6080 bytes including header and optional source code.
*   The Mentor MP is rated for 100 program downloads. This limitation is imposed by the flash memory used to store the program within the drive.
*   The user cannot create user variables. The user is only able to manipulate the drive parameter set.
*   The program cannot be downloaded or monitored over CTNet. The program is only accessible via the drives RJ45 serial communications port.

*   There are no real-time tasks, i.e. the scheduling rate of the program cannot be guaranteed. SM-Applications Plus tasks such as Clock, Event, Pos0 or Speed are not available.
*   The Onboard PLC should not be used for time-critical applications. For time-critical applications either the SM-Applications Plus or SM-Applications Lite V2 Solutions Modules should be used.

The program runs at a low priority. The Mentor MP provides a single background task in which to run a ladder diagram. The drive is prioritized to perform its major functions first, e.g. motor control, and will use any remaining processing time to execute the ladder diagram as a background activity. As the drive's processor becomes more heavily loaded, less time is spent executing the program.

Figure 10-1 Mentor MP Onboard PLC program scheduling

The user program is scheduled for a short period approximately once every 64ms. The time for which the program is scheduled will vary between 0.2ms and 2ms depending on the loading of the drive's processor.

When scheduled, several scans of the user program may be performed. Some scans may execute in microseconds. However, when the main drive functions are scheduled there will be a pause in the execution of the program causing some scans to take many milliseconds. SYPT Lite displays the average execution time calculated over the last 10 scans of the user program.

The Onboard PLC and SYPT Lite form the first level of functionality in a range of programmable options for Mentor MP.

*   SYPT Lite can be used with either the Onboard PLC or with SM-Applications Lite V2 to create ladder logic programs.
*   SYPT can be used with either the SM-Applications Lite V2 or SM-Applications Plus to create fully flexible programs using ladder logic, function blocks or DPL script.

Figure 10-2   Programming options for Mentor MP

10.4   Getting started

SYPTLite can be found on the CD which is supplied with the drive.

SYPTLite system requirements

- Windows 2000/XP/Vista. **Windows 95/98/98SE/Me/NT4 are not supported**
- Pentium III 500MHz or better recommended
- 128MB RAM
- Minimum of 800 x 600 screen resolution. 1024 x 768 is recommended
- Adobe Acrobat 5.10 or later (for viewing User Guides)
- Microsoft Internet Explorer V5.0 or later
- RS232 to RS485, RJ45 communications lead to connect the PC to the drive
- Administrator rights are required to install the software

To install SYPTLite, insert the CD and the auto-run facility should start up the front-end screen, from which SYPTLite can be selected.

See the SYPTLite help file for more information regarding using SYPTLite, creating ladder diagrams and the available function blocks.

10.5   Onboard PLC parameters

The following parameters are associated with the Onboard PLC program.

11.47		**Drive Onboard PLC program enable**							
RW	Uni								US
⇕		0 to 2		⇨			2		

This parameter is used to start and stop the drive Onboard PLC program.

Value	Description
0	Halt the drive Onboard PLC program.
1	Run the drive Onboard PLC program (if installed). Any out-of-range parameter writes attempted will be clipped to the maximum / minimum values valid for that parameter before being written.
2	Run the drive Onboard PLC program (if installed). Any out-of-range parameter writes attempted will cause a 'UP ovr' trip.

11.48		**Drive Onboard PLC program status**							
RO	Bi					NC	PT		
⇕		-128 to +127		⇨					

The drive Onboard PLC program status parameter indicates to the user the actual state of the drive Onboard PLC program.

Value	Description
-n	Onboard PLC program caused a drive trip due to an error condition while running rung n. Note that the rung number is shown on the display as a negative number.
0	Onboard PLC program is not installed.
1	Onboard PLC program is installed but stopped.
2	Onboard PLC program is installed and running.

When an Onboard PLC program is installed and running, the lower display of the drive flashes 'PLC' once every 10s.

11.49	Drive Onboard PLC programming events						
RO	Uni				NC	PT		PS
↕	0 to 65,535		⇨				

The drive Onboard PLC programming events parameter holds the number of times an Onboard PLC program download has taken place and is 0 on dispatch from the factory. The drive is rated for one hundred ladder program downloads. This parameter is not altered when defaults are loaded.

11.50	Drive Onboard PLC program average scan time						
RO	Uni				NC	PT	
↕	0 to 65,535 ms		⇨				

This parameter is updated once per second or once per Onboard PLC program scan whichever is the longest. If more than one program scan occurs within the one second update period the parameter shows the average scan time. If the program scan time is longer than one second the parameter shows the time for the last program scan.

11.51	Drive Onboard PLC program first run						
RO	Bit				NC	PT	
↕	OFF (0) or On (1)		⇨				

The Drive Onboard PLC program first run parameter is set for the duration of program scan from the stopped state. This enables the user to perform any required initialisation every time the program is run. This parameter is set every time the program is stopped.

10.6 Onboard PLC trips

The following trips are associated with the Onboard PLC program.

Trip	Diagnosis
UP ACC	**Onboard PLC program: Cannot access Onboard PLC program file on drive**
98	Disable drive - write access is not allowed when the drive is enabled. Another source is already accessing Onboard PLC program - retry once the other action is complete.
UP div0	**Onboard PLC program attempted divide by zero**
90	Check program
UP OFL	**Onboard PLC program variables and function block calls using more than the allowed RAM space (stack overflow)**
95	Check program
UP ovr	**Onboard PLC program attempted out of range parameter write**
94	Check program
UP PAr	**Onboard PLC program attempted access to a non-existent parameter**
91	Check program
UP ro	**Onboard PLC program attempted write to a read-only parameter**
92	Check program
UP So	**Onboard PLC program attempted read of a write-only parameter**
93	Check program
UP udF	**Onboard PLC program undefined trip**
97	Check program
UP uSEr	**Onboard PLC program requested a trip**
96	Check program

10.7 Onboard PLC and the SMARTCARD

The Onboard PLC program in a drive may be transferred from the drive to a SMARTCARD and vice versa.

- To transfer an Onboard PLC program from the drive to a SMARTCARD, set Pr **xx.00** to 5yyy and reset the drive
- To transfer an Onboard PLC program from the SMARTCARD to a drive, set Pr **xx.00** to 6yyy and reset the drive.

(Where yyy is the data block location, see Table 9-1 *SMARTCARD data blocks* on page 81 for restrictions on block numbers).

If an attempt is made to transfer an Onboard PLC program from a drive to the SMARTCARD when the drive contains no program, the block is still created on the SMARTCARD but it will contain no data. If this data block is then transferred to a drive, the destination drive will then have no Onboard PLC program.

The smallest SMARTCARD compatible with Mentor MP has a capacity of 4064 bytes and each block can be up to 4064 bytes in size. The maximum size of a user program is 4032 bytes so it is guaranteed that any Onboard PLC program downloaded to a Mentor MP will fit on to an empty SMARTCARD. A SMARTCARD can contain a number of Onboard PLC programs until the capacity of the card is used.

11 Advanced parameters

This is a quick reference to all parameters in the drive showing units, ranges, limits etc, with block diagrams to illustrate their function. Full parameter descriptions can be found in the *Mentor MP* Advanced User Guide on the supplied CD ROM.

These advanced parameters are listed for reference purposes only. The lists in this chapter do not include sufficient information for adjusting these parameters. Incorrect adjustment can affect the safety of the system, and damage the drive and or external equipment. Before attempting to adjust any of these parameters, refer to the *Mentor MP Advanced User Guide*.

Table 11-1   Menu descriptions

Menu	Function
1	Speed reference selection, limits and filters
2	Ramps
3	Speed feedback and speed control
4	Torque and current control
5	Motor and field control
6	Sequencer and clock
7	Analog I/O
8	Digital I/O
9	Programmable logic and motorized pot
10	Drive status and trip information
11	General drive set-up
12	Threshold detectors, variable selectors and brake control function
13	Position control
14	User PID controller
15	Slot 1 Solutions Module menu
16	Slot 2 Solutions Module menu
17	Slot 3 Solutions Module menu
18	User application menu 1 (saved in drive EEPROM)
19	User application menu 2 (saved in drive EEPROM)
20	User application menu 3 (not saved in drive EEPROM)
21	Second motor parameters
22	Additional Menu 0 set up
23	Header selections

Default abbreviations:

Eur>   European default value
USA>   USA default value

NOTE

Parameter numbers shown in brackets {...} are the equivalent sub block/ Menu 0 parameters.

In some cases, the function or range of a parameter is affected by the setting of another parameter; the information in the lists relates to the default condition of such parameters.

Coding

The coding defines the attributes of the parameter as follows.

Table 11-2   Key to parameter table coding

Coding	Attribute
{X.XX}	Copied Mneu 0 or advanced parameter
Bit	1 bit parameter: 'On' or 'OFF' on the display
Bi	Bipolar parameter
Uni	Unipolar parameter
Txt	Text: the parameter uses text strings instead of numbers.
SP	Spare: not used
FI	Filtered: some parameters which can have rapidly changing values are filtered when displayed on the drive keypad for easy viewing.
DE	Destination pointer parameter: This parameter can be used to set up the location (i.e. menu/parameter number) where the destination data is to be routed.
VM	Variable maximum: the maximum of this parameter can vary.
DP	Decimal place: indicates the number of decimal places used by this parameter.
ND	No default: when defaults are loaded (except when the drive is manufactured or on EEPROM failure) this parameter is not modified.
RA	Rating dependant: this parameter is likely to have different values and ranges with drives of different voltage and current ratings. Parameters with this attribute will not be transferred to the destination drive by a SMARTCARD when the rating of the destination drive is different from the source drive if the drive voltage ratings are different or the file is a parameter file. However, the value will be transferred if only the current rating is different and the file is a differences from default type file.
NC	Not copied: not transferred to or from SMARTCARD during copying.
NV	Not visible: not visible on the keypad.
PT	Protected: cannot be used as a destination.
US	User save: saved in drive EEPROM when the user initiates a parameter save.
RW	Read/write: can be written by the user.
RO	Read only: can only be read by the user
BU	Bit default one/unsigned: Bit parameters with this flag set to one have a default of one (all other bit parameters have a default of zero. Non-bit parameters are unipolar if this flag is one.
PS	Power-down save: parameter automatically saved in drive EEPROM when the under volts (UV) trip occurs. Power-down save parameters are also saved in the drive when the user initiates a parameter save.

Table 11-3 Feature look-up table

Feature	Related parameters (Pr)													
Acceleration rates	2.10	2.11 to 2.19	2.32	2.33	2.34	2.02								
Analog speed reference 1	1.36	7.10	7.01	7.07	7.08	7.09	7.25	7.26	7.30					
Analog speed reference 2	1.37	7.14	1.41	7.02	7.11	7.12	7.13	7.28	7.31					
Analog I/O	Menu 7													
Analog input 1	7.01	7.07	7.08	7.09	7.10	7.25	7.26	7.30						
Analog input 2	7.02	7.11	7.12	7.13	7.14	7.28	7.31							
Analog input 3	7.03	7.15	7.16	7.17	7.18	7.29	7.32							
Analog output 1	7.19	7.20	7.21	7.33										
Analog output 2	7.22	7.23	7.24											
Application menu	Menu 18		Menu 19		Menu 20									
At speed indicator bit	3.06	3.07	3.09	10.06	10.05	10.07								
Auto reset	10.34	10.35	10.36	10.01										
Autotune	4.13	4.14	4.34	5.12	5.15	5.23	5.24	5.29	5.30	5.59	5.61	5.70	5.72	5.74
Binary sum	9.29	9.30	9.31	9.32	9.33	9.34								
Bipolar speed	1.10													
Brake control	12.40 to 12.49													
Catch a spinning motor	6.09													
Coast to stop	6.01													
Comms	11.23 to 11.26													
Copying	11.42	11.36 to 11.40												
Cost - per kWh electricity	6.16	6.17	6.24	6.25	6.26	6.40								
Current controller	4.13	4.14	4.34	5.15										
Current feedback	4.01	4.02	4.16	4.19	4.20	4.27	4.28	4.29	4.30	4.31	4.32	10.08	10.17	
Current limits	4.05	4.06	4.07	4.18	5.07	10.09								
Deceleration rates	2.20	2.21 to 2.29	2.04	2.35 to 2.37		2.02	2.08	6.01						
Defaults	11.46													
Digital I/O	Menu 8													
Digital I/O read word	8.20													
Digital I/O T24	8.01	8.11	8.21	8.31										
Digital I/O T25	8.02	8.12	8.22	8.32										
Digital I/O T26	8.03	8.13	8.23	8.33										
Digital input T27	8.04	8.14	8.24											
Digital input T28	8.05	8.15	8.25	8.39										
Digital input T29	8.06	8.16	8.26	8.39										
Digital lock	13.10	13.01 to 13.09	13.11	13.12	13.16	3.22	3.23	13.19 to 13.23						
Direction	10.13	6.30	6.31	3.01	3.02	10.14	8.03	8.04						
Display timeout	11.41													
Drive active	10.02													
Drive OK	10.01	8.27	8.07	8.17	10.36									
Electronic nameplate	3.49													
Enable	6.15	8.09	8.10											
Encoder reference	3.43	3.44	3.45	3.46										
Encoder set up	3.33	3.34 to 3.42	3.47	3.48										
External trip	10.32	8.10	8.07											
Fan speed	6.45													
Filter change	6.19	6.18												
Hard speed reference	3.22	3.23												
I/O sequencer	6.04	6.30	6.31	6.32	6.33	6.34	6.42	6.43	6.40					
Inertia compensation	2.38	5.12	4.22	3.18										
Jog reference	1.05	2.19	2.29											
Keypad reference	1.17	1.14	1.43	1.51	6.12	6.13								
Limit switches	6.35	6.36												
Line power supply loss	6.03	5.05												
Local position reference	13.20 to 13.23													
Logic function 1	9.01	9.04	9.05	9.06	9.07	9.08	9.09	9.10						
Logic function 2	9.02	9.14	9.15	9.16	9.17	9.18	9.19	9.20						
Marker pulse	3.32	3.31												
Maximum speed	1.06													
Menu 0 set up	22.01 to 22.21		Menu 22											
Minimum speed	1.07	10.04												
Modules - number of	11.35													

Feature	Related parameters (Pr)										
Motor map	5.07	5.08	5.09	5.70	5.73						
Motor map 2	Menu 21		11.45								
Motorized potentiometer	9.21	9.22	9.23	9.24	9.25	9.26	9.27	9.28			
Offset speed reference	1.04	1.38	1.09								
Onboard PLC	11.47 to 11.51										
Open collector digital outputs	8.30										
Orientation	13.10	13.13 to 13.15									
Output	5.01	5.02	5.03								
Overspeed threshold	3.08										
PID controller	Menu 14										
Position feedback - drive	3.28	3.29	3.30	3.50							
Positive logic	8.29										
Power up parameter	11.22	11.21									
Precision reference	1.18	1.19	1.20	1.44							
Preset speeds	1.15	1.21 to 1.28	1.16	1.14	1.42	1.45 to 1.48	1.50				
Programmable logic	Menu 9										
Regenerating	10.10										
Relative jog	13.17 to 13.19										
Relay output	8.07	8.17	8.27	8.40	8.50	8.60					
Reset	10.33	8.02	8.22	10.34	10.35	10.36	10.01				
S ramp	2.06	2.07									
Security code	11.30	11.44									
Serial comms	11.23 to 11.26										
Skip speeds	1.29	1.30	1.31	1.32	1.33	1.34	1.35				
SMARTCARD	11.36 to 11.40		11.42								
Software version	11.29	11.34									
Speed controller	3.10 to 3.17		3.20	3.21							
Speed feedback	3.02	3.03									
Speed feedback - drive	3.26	3.27	3.28	3.29	3.31	3.42	3.52	3.55	3.56	3.57	3.58
Speed reference selection	1.14	1.15	1.49	1.50	1.01						
Status word	10.40										
Supply	5.05										
Thermal protection - drive	7.04	7.34	10.18								
Thermal protection - motor	4.15	5.07	4.19	4.16	4.25	7.15					
Thermistor input	7.15	7.03									
Threshold detector 1	12.01	12.03 to 12.07									
Threshold detector 2	12.02	12.23 to 12.27									
Time - filter change	6.19	6.18									
Time - powered up log	6.20	6.21	6.28								
Time - run log	6.22	6.23	6.28								
Torque	4.03	4.26	5.32								
Torque mode	4.08	4.11	4.09	4.10							
Trip detection	10.20 to 10.29										
Trip log	10.20 to 10.29	10.41 to 10.51	6.28								
Under voltage	5.05										
Variable selector 1	12.08 to 12.15										
Variable selector 2	12.28 to 12.35										
Velocity feed forward	1.39	1.40									
Voltage rating	11.33	5.09	5.05								
Warning	10.19	10.17	10.18	10.40							
Zero speed indicator bit	3.05	10.03									

Parameter ranges and variable maximums:

The two values provided define the minimum and maximum values for the given parameter. In some cases the parameter range is variable and dependant on either:

- other parameters
- the drive rating
- or a combination of these

The values given in Table 11-4 are the variable maximums used in the drive.

Table 11-4   Definition of parameter ranges & variable maximums

Maximum	Definition
MAX_SPEED_REF [10000.0rpm]	**Maximum speed reference** If Pr **1.08** = 0: MAX_SPEED_REF = Pr **1.06** (**SE02, 0.23**) If Pr **1.08** = 1: MAX_SPEED_REF is Pr **1.06** (**SE02, 0.23**) or – Pr **1.07** (**SE01, 0.22**) whichever is the largest (If the second motor map is selected Pr **21.01** is used instead of Pr **1.06** (**SE02, 0.23**) and Pr **21.02** instead of Pr **1.07** (**SE01, 0.22**))
SPEED_LIMIT_MAX [10000.0rpm]	**Maximum applied to speed reference limits** A maximum limit may be applied to the speed reference to prevent the nominal encoder frequency from exceeding 500kHz. The maximum is defined by SPEED_LIMIT_MAX (in rpm) = 500kHz x 60 / ELPR = 3.0×10^7 / ELPR subject to an absolute maximum of 10,000 rpm. ELPR is equivalent encoder lines per revolution and is the number of lines that would be produced by a quadrature encoder. Quadrature encoder ELPR = number of lines per revolution F and D encoder ELPR = number of lines per revolution / 2 This maximum is defined by the device selected with the speed feedback selector (Pr **3.26** (**Fb01, 0.71**)) and the ELPR set for the position feedback device.
SPEED_MAX [10000.0rpm]	**Maximum speed** This maximum is used for some speed related parameters in menu 3. To allow headroom for overshoot etc. the maximum speed is twice the maximum speed reference. SPEED_MAX = 2 x MAX_SPEED_REF

MAX_RAMP_RATE
MAX_RAMP_RATE_M2
[3200.000]
	Maximum ramp rate
	If (Pr **1.06** (**SE02, 0.23**) [Pr **21.01**] >= 1000 and Pr **2.39** = 0) or Pr **2.39** >= 1000 then
	　MAX_RAMP_RATE = 3200.000
	Else if Pr **2.39** = 0
	　MAX_RAMP_RATE = 3200 * Pr **1.06** (**SE02, 0.23**) [Pr **21.01**] / 1000.0
	Else
	　MAX_RAMP_RATE = 3200 * Pr **2.39** / 1000.0
	End if

RATED_CURRENT_MAX [9999.99A]	**Maximum motor rated current**
DRIVE_CURRENT_MAX [9999.99A]	**Maximum drive current** The maximum drive current is the current at the over current trip level and is given by: DRIVE_CURRENT_MAX = RATED_CURRENT_MAX x 2
MOTOR1_CURRENT_LIMIT_MAX [1000.0%]	**Maximum current limit settings for motor map 1** This maximum current limit setting is the maximum applied to the current limit parameters in motor map 1. See introduction to Menu 4 for the definition.
MOTOR2_CURRENT_LIMIT_MAX [1000.0%]	**Maximum current limit settings for motor map 2** This maximum current limit setting is the maximum applied to the current limit parameters in motor map 2. See introduction to Menu 4 for the definition.
TORQUE_PROD_CURRENT_MAX [1000.0%]	**Maximum torque producing current** This is used as a maximum for torque and torque producing current parameters. It is MOTOR1_CURRENT_LIMIT_MAX or MOTOR2_CURRENT_LIMIT_MAX depending on which motor map is currently active.
USER_CURRENT_MAX [1000.0%]	**Current parameter limit selected by the user** The user can select a maximum for Pr **4.08** (torque reference) and Pr **4.20** (percentage load) to give suitable scaling for analog I/O with Pr **4.24**. This maximum is subject to a limit of CURRENT_LIMIT_MAX. USER_CURRENT_MAX = Pr **4.24**

Maximum	Definition
ARMATURE_VOLTAGE_MAX [1025]	**Maximum armature voltage** Vac x 1.35 ($\sqrt{2}$ x 3 / π) 480 +10% drive: 720 575 +10% drive: 860 690 +10% drive: 1025 **NOTE** For 4 quadrant drives maximum armature voltage = Vac x 1.15
QUADRANT_MAX	**Quadrant maximum** 0 for a 2 quadrant drive. 1 for a 4 quadrant drive.
POWER_MAX [9999.99kW]	**Maximum power in kW** The maximum power has been chosen to allow for the maximum power that can be output by the drive with maximum DC output voltage and maximum controlled current. Therefore: POWER_MAX = ARMATURE_VOLTAGE_MAX x DRIVE_CURRENT_MAX

The values given in square brackets indicate the absolute maximum value allowed for the variable maximum.

11.1 Menu 1: Speed reference

Menu 1 controls the main reference selection.

Figure 11-1 Menu 1 logic diagram

Pr 1.49	Pr 1.50	Reference being used
1	1	Analog reference 1
1	>1	Preset reference defined by Pr **1.50**
2	1	Analog reference 2
2	>1	Preset reference defined by Pr **1.50**
3	x	Preset reference defined by Pr **1.50**
4	x	Keypad reference
5	x	Precision reference
6	x	Keypad reference only

The parameters are all shown in their default settings

*Refer to Pr **1.14** (**SE05**, **0.26**)

	Parameter		Range(⇕)	Default(⇨)		Type		
1.01	Speed reference selected	{di01, 0.36}	±MAX_SPEED_REF rpm		RO	Bi	NC	PT
1.02	Pre-skip filter reference				RO	Bi	NC	PT
1.03	Pre-ramp reference	{di02, 0.37}			RO	Bi	NC	PT
1.04	Reference offset		±10,000.0 rpm	0.0	RW	Bi		US
1.05	Jog reference		0 to 1,000.0 rpm		RW	Uni		US
1.06	Maximum reference clamp	{SE02, 0.23}	SPEED_LIMIT_MAX rpm	1000.0	RW	Uni		US
1.07	Minimum reference clamp	{SE01, 0.22}	±SPEED_LIMIT_MAX rpm*	0.0	RW	Bi	PT	US
1.08	Negative minimum reference clamp enable			OFF (0)	RW	Bit		US
1.09	Reference offset select				RW	Bit		US
1.10	Bipolar reference enable		OFF (0) or On (1)		RW	Bit		US
1.11	Reference enabled indicator	{di11, 0.46}			RO	Bit	NC	PT
1.12	Reverse selected indicator	{di12, 0.47}			RO	Bit	NC	PT
1.13	Jog selected indicator	{di13, 0.48}			RO	Bit	NC	PT
1.14	Reference selector	{SE05, 0.26}	0 to 6	0 (A1.A2)	RW	Txt		US
1.15	Preset selector		0 to 9	0	RW	Uni		US
1.16	Preset reference selector timer		0 to 400.0s	10.0	RW	Uni		US
1.17	Keypad control reference		±MAX_SPEED_REF rpm	0.0	RO	Bi	NC PT	PS
1.18	Precision reference coarse		±MAX_SPEED_REF rpm		RW	Bi		US
1.19	Precision reference fine		0.0 to 0.099 rpm	0.000	RW	Uni		US
1.20	Precision reference update disable		OFF (0) or On (1)	OFF (0)	RW	Bit	NC	
1.21	Preset reference 1				RW	Bi		US
1.22	Preset reference 2				RW	Bi		US
1.23	Preset reference 3				RW	Bi		US
1.24	Preset reference 4		±MAX_SPEED_REF rpm	0.0	RW	Bi		US
1.25	Preset reference 5				RW	Bi		US
1.26	Preset reference 6				RW	Bi		US
1.27	Preset reference 7				RW	Bi		US
1.28	Preset reference 8				RW	Bi		US
1.29	Skip reference 1		0 to 10,000 rpm	0	RW	Uni		US
1.30	Skip reference band 1		0 to 250 rpm	5	RW	Uni		US
1.31	Skip reference 2		0 to 10,000 rpm	0	RW	Uni		US
1.32	Skip reference band 2		0 to 250 rpm	5	RW	Uni		US
1.33	Skip reference 3		0 to 10,000 rpm	0	RW	Uni		US
1.34	Skip reference band 3		0 to 250 rpm	5	RW	Uni		US
1.35	Reference in rejection zone		OFF (0) or On (1)		RO	Bit	NC	PT
1.36	Analog reference 1		±MAX_SPEED_REF rpm	0	RO	Bi	NC	
1.37	Analog reference 2				RO	Bi	NC	
1.38	Percentage trim		±100.00%	0.00	RW	Bi	NC	
1.39	Velocity feed forward		±10,000.0 rpm		RO	Bi	NC	PT
1.40	Velocity feed forward select				RO	Bit	NC	PT
1.41	Reference select flag 1				RW	Bit	NC	
1.42	Reference select flag 2				RW	Bit	NC	
1.43	Reference select flag 3				RW	Bit	NC	
1.44	Reference select flag 4		OFF (0) or On (1)	OFF (0)	RW	Bit	NC	
1.45	Reference select flag 5				RW	Bit	NC	
1.46	Reference select flag 6				RW	Bit	NC	
1.47	Reference select flag 7				RW	Bit	NC	
1.48	Reference timer reset flag				RW	Bit	NC	
1.49	Reference selected indicator		1 to 6		RO	Uni	NC	
1.50	Preset reference selected indicator		1 to 8		RO	Uni	NC	PT
1.51	Power-up keyboard control mode reference		0 to 2	0	RW	Txt		US
1.52	Reference select flags		OFF (0) or On (1)	OFF (0)	RW	Bit	NC	

*The range shown for Pr **1.07** shows the range used for scaling purposes (i.e. for routing to an analog output etc.). Further range restrictions are applied depending on the settings of Pr **1.08** and Pr **1.10**.

RW	Read / Write	RO	Read only	Uni	Unipolar	Bi	Bi-polar	Bit	Bit parameter	Txt	Text string		
FI	Filtered	DE	Destination	NC	Not copied	RA	Rating dependent	PT	Protected	US	User save	PS	Power down save

11.2 Menu 2: Ramps

The pre-ramp speed reference passes through the ramp block controlled by menu 2 before being used by the drive to produce input to the speed controller. The ramp block includes: linear ramps, and an S ramp function for ramped acceleration and deceleration.

Figure 11-2 Menu 2 logic diagram

Deceleration rate select bits

| 2.37 | 2.36 | 2.35 |

Deceleration ramp selected **2.31**

	2.37	2.36	2.35
1	0	0	0
2	0	0	1
3	0	1	0
4	0	1	1
5	1	0	0
6	1	0	1
7	1	1	0
8	1	1	1

Deceleration rate selector **2.20**

Deceleration rates 1 ~ 8

2.21	Deceleration rate 1
2.22	Deceleration rate 2
2.23	Deceleration rate 3
2.24	Deceleration rate 4
2.25	Deceleration rate 5
2.26	Deceleration rate 6
2.27	Deceleration rate 7
2.28	Deceleration rate 8

Preset reference selected *indicator* **1.50**

1	1
2	2
3	3
4	4
5	5
6	6
7	7
8	8

2.29 Jog deceleration rate

Jog selected *indicator* **1.13**

Forward Decel. rate   Reverse Decel. rate

Deceleration

Ramp control

| 2.06 | S-Ramp enable** |
| 2.07 | S-Ramp acceleration limit |

2.02 Ramp *enable*

Ramp output selector **2.05**

Post-ramp reference **2.01**

Menu 3

d/dt

Pr **3.18** = Motor and load inertia
Pr **5.32** = Motor torque per amp

2.38

Inertia compensation torque

** For more information refer to Chapter 11.22 *Advanced features* on page 140 section in the *Mentor MP User Guide.*

Parameter		Range(⇕)	Default(⇨)	Type				
2.01	Post ramp reference {di03, 0.38}	±SPEED_MAX rpm		RO	Bi		NC	PT	
2.02	Ramp enable		On (1)	RW	Bit				US
2.03	Ramp hold	OFF (0) or On (1)	0	RW	Bit				US
2.05	Ramp output selector		On (1)	RW	Bit				US
2.06	S ramp enable		0 Eur: 0, USA: 1	RW	Bit				US
2.07	S ramp acceleration limit	0 to 100.000 s²/1000rpm	3.600	RW	Uni				US
2.10	Acceleration rate selector	0 to 9	0	RW	Uni				US
2.11	Acceleration rate 1 {SE03, 0.24}			RW	Uni				US
2.12	Acceleration rate 2			RW	Uni				US
2.13	Acceleration rate 3			RW	Uni				US
2.14	Acceleration rate 4			RW	Uni				US
2.15	Acceleration rate 5	0 to MAX_RAMP_RATE s / (Pr **1.06** OR Pr **2.39**)	5.000	RW	Uni				US
2.16	Acceleration rate 6			RW	Uni				US
2.17	Acceleration rate 7			RW	Uni				US
2.18	Acceleration rate 8			RW	Uni				US
2.19	Jog acceleration rate			RW	Uni				US
2.20	Deceleration rate selector	0 to 9	0	RW	Uni				US
2.21	Deceleration rate 1 {SE04, 0.25}			RW	Uni				US
2.22	Deceleration rate 2			RW	Uni				US
2.23	Deceleration rate 3			RW	Uni				US
2.24	Deceleration rate 4	0 to MAX_RAMP_RATE s / (Pr **1.06** OR Pr **2.39**)	5.000	RW	Uni				US
2.25	Deceleration rate 5			RW	Uni				US
2.26	Deceleration rate 6			RW	Uni				US
2.27	Deceleration rate 7			RW	Uni				US
2.28	Deceleration rate 8			RW	Uni				US
2.29	Jog deceleration rate		10.000	RW	Uni				US
2.30	Acceleration ramp selected	1 to 8		RO	Uni		NC	PT	
2.31	Deceleration ramp selected			RO	Uni		NC	PT	
2.32	Acceleration select bit 0			RW	Bit		NC		
2.33	Acceleration select bit 1			RW	Bit		NC		
2.34	Acceleration select bit 2			RW	Bit		NC		
2.35	Deceleration select bit 0	OFF (0) or On (1)		RW	Bit		NC		
2.36	Deceleration select bit 1			RW	Bit		NC		
2.37	Deceleration select bit 2			RW	Bit		NC		
2.38	Inertia compensation torque	± 1,000.0 %		RO	Bi		NC	PT	
2.39	Ramp rate speed units	0 to 10000rpm	0	RW	Uni				US
2.40	Time of S ramp	0 to 100.000s	1.250	RW	Uni				US
2.41	S ramp mode	OFF (0) or On (1)	On (1)	RW	Bit				US

RW	Read / Write	RO	Read only	Uni	Unipolar	Bi	Bi-polar	Bit	Bit parameter	Txt	Text string		
FI	Filtered	DE	Destination	NC	Not copied	RA	Rating dependent	PT	Protected	US	User save	PS	Power down save

11.3   Menu 3: Speed feedback and speed control

Speed accuracy and resolution

Digital reference resolution

When a preset speed is used the reference resolution is 0.1rpm. Improved resolution can be obtained by using the precision reference (0.001rpm).

Analog reference resolution

The analog input has a maximum resolution of 14bits plus sign. The resolution of the reference from analog inputs 2 or 3 is 10bits plus sign.

Analog feedback resolution

The resolution for both Armature voltage and tachogenerator feedback is 10bit plus sign.

Accuracy

With encoder feedback the absolute speed accuracy depends on the accuracy of the crystal used with the drive microprocessor. The accuracy of the crystal is 100ppm, and so the absolute speed accuracy is 100ppm (0.01%) of the reference, when a preset speed is used. If an analog input is used the absolute accuracy is further limited by the absolute accuracy and non-linearity of the analog input. If analog feedback is used the accuracy is even further limited.

| Safety Information | Product information | Mechanical Installation | Electrical installation | Getting started | Basic parameters | Running the motor | Optimization | SMARTCARD operation | Onboard PLC | **Advanced parameters** | Technical data | Diagnostics | UL information |

Mentor MP User Guide **101**
Issue: 4   www.controltechniques.com

Figure 11-3   Menu 3 logic diagram

* If Pr **5.28** (Field weakening compensation disable) is set to 'OFF (0)' a multiplication factor is applied to the speed loop gains when the flux is below 100%.

Parameter		Range(⇕)	Default(⇨)	Type
3.01 Final speed reference	{di04, 0.39}	±SPEED_MAX rpm		RO Bi FI NC PT
3.02 Speed feedback	{di05, 0.40}			RO Bi FI NC PT
3.03 Speed error				RO Bi FI NC PT
3.04 Speed controller output	{di06, 0.41}	±Torque_prod_current_max %		RO Bi FI NC PT
3.05 Zero speed threshold		0 to 200 rpm	30	RW Uni US
3.06 At speed lower limit			5	RW Uni US
3.07 At speed upper limit		0 to 10,000 rpm		RW Uni US
3.08 Overspeed threshold			0	RW Uni US
3.09 Absolute 'at speed' detect		OFF (0) or On (1)	OFF (0)	RW Bit US
3.10 Speed controller proportional gain (Kp1)	{SP01, 0.61}	0.0 to 6.5535 (1 / rad/s))	0.0300	RW Uni US
3.11 Speed controller integral gain (Ki1)	{SP02, 0.62}	0 to 655.35 (s / rad/s))	0.10	RW Uni US
3.12 Speed controller differential feedback gain (Kd1)	{SP03, 0.63}	0 to 0.65535 (1/s / rad/s))	0.00000	RW Uni US
3.13 Speed controller proportional gain (Kp2)		0.0 to 6.5535 (1 / rad/s))	0.0300	RW Uni US
3.14 Speed controller integral gain (Ki2)		0 to 655.35 (s / rad/s))	0.10	RW Uni US
3.15 Speed controller differential feedback gain (Kd2)		0 to 0.65535 (1/s / rad/s))	0.00000	RW Uni US
3.16 Speed controller gain select		OFF (0) or On (1)	OFF (0)	RW Bit US
3.17 Speed controller set-up method		0 to 2	0	RW Uni US
3.18 Motor and load inertia		0.0 to 90.00000 kg m^2	0.00000	RW Uni US
3.20 Bandwidth		0 to 50 Hz	1	RW Uni US
3.21 Damping factor		0.0 to 10.0	1.0	RW Uni US
3.22 Hard speed reference		-MAX_SPEED_REF to MAX_SPEED_REF rpm	0.0	RW Bi US
3.23 Hard speed reference selector		OFF (0) or On (1)	OFF (0)	RW Bit US
3.26 Speed feedback selector	{Fb01, 0.71}	0 to 5	5	RW Txt US
3.27 Drive encoder speed feedback	{Fb09, 0.79}	±10,000.0 rpm		RO Bi FI NC PT
3.28 Drive encoder revolution counter		±32,768 revolutions		RO Bi FI NC PT
3.29 Drive encoder position		0 to 65,535 1/2^{16}ths of a revolution		RO Uni FI NC PT
3.31 Drive encoder marker position reset disable		OFF (0) or On (1)	OFF (0)	RW Bit US
3.32 Drive encoder marker flag				RW Bit NC
3.33 Drive encoder turn bits		0 to 16	16	RW Uni US
3.34 Drive encoder lines per revolution	{Fb05, 0.75}	1 to 50,000	1024	RW Uni US
3.35 Drive encoder marker mode		0 to 1		RW Uni US
3.36 Drive encoder supply voltage	{Fb06, 0.76}	0 to 3	0	RW Txt US
3.38 Drive encoder type	{Fb07, 0.77}			RW Txt US
3.39 Drive encoder termination select	{Fb08, 0.78}	0 to 2	1	RW Uni US
3.40 Drive encoder error detection level			0	RW Uni US
3.42 Drive encoder filter		0 to 5 (0 to 16ms)	2	RW Txt US
3.43 Maximum drive encoder reference		0 to 10,000 rpm	1000	RW Uni US
3.44 Drive encoder reference scaling		0 to 4.000	1.000	RW Uni US
3.45 Drive encoder reference		±100.0%		RO Bi FI NC PT
3.46 Drive encoder reference destination		0 to 22.99	0.00	RW Uni DE PT US
3.47 Re-initialise position feedback				RW Bit NC
3.48 Position feedback initialised		OFF (0) or On (1)		RO Bit NC PT
3.49 Full motor object electronic nameplate transfer			OFF (0)	RW Bit US
3.50 Position feedback lock				RW Bit NC
3.51 Tachometer voltage rating	{Fb02, 0.72}	0 to 300.00 v/1000rpm	Eur:60.00, USA 50.00	RW US
3.52 Tachometer speed feedback	{Fb04, 0.74}	±SPEED_MAX rpm		RO Bi FI NC PT
3.53 Tachometer input mode	{Fb03, 0.73}	0 to 2	0 (DC)	RW Txt US
3.54 Encoder direction		OFF (0) or On (1)	OFF (0)	RW Bit US
3.55 Select estimated speed on feedback loss				RW Bit US
3.56 Speed feedback loss window		0 to 100.0%	20.0%	RW US
3.57 Estimated speed has been automatically selected		OFF (0) or On (1)		RO Bit
3.58 Speed feedback percentage		±100.0%		RO NC PT

RW	Read / Write	RO	Read only	Uni	Unipolar	Bi	Bi-polar	Bit	Bit parameter	Txt	Text string		
FI	Filtered	DE	Destination	NC	Not copied	RA	Rating dependent	PT	Protected	US	User save	PS	Power down save

11.4 Menu 4: Torque and current control

MOTOR1_CURRENT_LIMIT_MAX is used as the maximum for some parameters such as the user current limits. The current maximum current limit is defined as follows (with a maximum of 1000%):

$$\text{CURRENT\_LIMIT\_MAX} = \left[\frac{\text{Maximum current}}{\text{Motor rated current}} \right] \times 100\%$$

Where:

Motor rated current is given by Pr **5.07 (SE07, 0.28)**

(MOTOR2_CURRENT_LIMIT_MAX is calculated from the motor map 2 parameters). The maximum current is 1.5 x drive rating.

Figure 11-4   Menu 4 logic diagram

Key

The parameters are all shown at their default settings

Parameter		Range($\updownarrow$)	Default($\Rightarrow$)	Type					
4.01	Current magnitude {di08, 0.43}	±DRIVE_CURRENT_MAX A		RO	Uni	FI	NC	PT	
4.02	Filtered current magnitude			RO	Uni	FI	NC	PT	
4.03	Torque demand {di07, 0.42}	±TORQUE_PROD_CURRENT_MAX %		RO	Bi	FI	NC	PT	
4.04	Current demand			RO	Bi	FI	NC	PT	
4.05	Motoring current limit	0 to MOTOR1_CURRENT_LIMIT_MAX %	150.0	RW	Uni		RA		US
4.06	Regen current limit			RW	Uni		RA		US
4.07	Symmetrical current limit			RW	Uni		RA		US
4.08	Torque reference	±USER_CURRENT_MAX %	0.00	RW	Bi				US
4.09	Torque offset		0.0	RW	Bi				US
4.10	Torque offset select	OFF (0) or On (1)	OFF (0)	RW	Bit				US
4.11	Torque mode selector	0 to 4	0	RW	Uni				US
4.12	Current demand filter 1	0.0 to 25.0 ms	6.0	RW	Uni				US
4.13	Continuous current controller Kp gain	0 to 4,000	100	RW	Uni		RA		US
4.14	Continuous current controller Ki gain		50	RW	Uni		RA		US
4.15	Thermal time constant	0 to 3000.0	89.0	RW	Uni				US
4.16	Thermal protection mode	0 to 1	0	RW	Bit				US
4.18	Overriding current limit	0 to TORQUE_PROD_CURRENT_MAX %		RO	Uni		NC	PT	
4.19	Overload accumulator	0 to 100.0 %		RO	Uni		NC	PT	
4.20	Percentage load	±USER_CURRENT_MAX %		RO	Bi	FI	NC	PT	
4.22	Inertia compensation enable	OFF (0) or On (1)	OFF (0)	RW	Bit				US
4.23	Current demand filter 2	0.0 to 25.0 ms	6.0	RW	Uni				US
4.24	User current maximum scaling	0.0 to TORQUE_PROD_CURRENT_MAX %	150.0	RW	Uni		RA		US
4.27	Current taper 1 threshold	0 to 10,000.0 rpm	10,000.0 rpm	RW	Uni				US
4.28	Current taper 2 threshold			RW	Uni				US
4.29	Current taper 1 end point	0 to 1000.0%	1000.0%	RW	Uni				US
4.30	Current taper 2 end point			RW	Uni				US
4.31	Taper threshold 1 exceeded	OFF (0) or On (1)		RO	Bit				
4.32	Taper threshold 2 exceeded			RO	Bit				
4.33	Slew rate limit	0.0 to 60,000 %s^{-1}	7000	RW	Uni				US
4.34	Discontinuous current controller Ki gain	0 to 4,000	200	RW	Uni		RA		US
4.35	Extra safe bridge change	OFF (0) or On (1)	OFF (0)	RW	Bit				US
4.36	Reduced hysteresis for bridge change over			RW	Bit				US

RW	Read / Write	RO	Read only	Uni	Unipolar	Bi	Bi-polar	Bit	Bit parameter	Txt	Text string		
FI	Filtered	DE	Destination	NC	Not copied	RA	Rating dependent	PT	Protected	US	User save	PS	Power down save

11.5 Menu 5: Motor and field control

Figure 11-5   Menu 5 field control logic diagram

Figure 11-6   Menu 5 armature control logic diagram

Parameter		Range(⇳)	Default(⇨)	Type					
5.01	Armature firing angle	0 to 175.0 °		RO	Uni	FI	NC	PT	
5.02	Armature voltage **{di10, 0.45}**	±ARMATURE_VOLTAGE_MAX V		RO	Bi	FI	NC	PT	
5.03	Output power	±POWER_MAX kW		RO	Bi	FI	NC	PT	
5.04	Estimated speed	±SPEED_MAX rpm		RO	Bi	FI	NC	PT	
5.05	Line voltage	0 to 1000V rms AC		RO	Uni	FI	NC	PT	
5.06	Machine armature voltage	±ARMATURE_VOLTAGE_MAX V		RO	Bi	FI	NC	PT	
5.07	Motor rated current **{SE07, 0.28}**	0 to RATED_CURRENT_MAX A	RATED_CURRENT_MAX	RW	Uni		RA		US
5.08	Base speed **{SE08, 0.29}**	0.0 to 10,000.0 rpm	1,000.0	RW	Uni				US
5.09	Armature rated voltage **{SE06, 0.27}**	0 to ARMATURE_VOLTAGE_MAX Vdc	For 480V drive: 440 Eur 500 USA For 575V drive: 630 Eur 630 USA For 690V drive: 760 Eur 760 USA	RW	Uni		RA		US
5.10	Direct firing angle	0 to 165.0 °	165.0	RW	Uni				
5.11	Direct firing angle enable	OFF (0) or On (1)	OFF (0)	RW	Bit				US
5.12	Autotune **{SE13, 0.34}**	0 to 3	0	RW	Uni		NC		
5.13	Continuous Back End Stop	0 to 165.0 °	165.0	RW	Uni				US
5.14	Armature voltage select	OFF (0) or On (1)	OFF (0)	RW	Bit				US
5.15	Motor constant	0 to 100.0%	50.0%	RW	Uni				US
5.16	DC contactor	OFF (0) or On (1)	OFF (0)	RW	Bit				US
5.21	Quadrant 1 Enable	0 to 1		RW	Uni				US
5.22	Quadrant 2 Enable		1	RW	Uni				US
5.23	Quadrant 3 Enable	0 to QUADRANT_MAX		RW	Uni				US
5.24	Quadrant 4 Enable	0 to QUADRANT_MAX		RW	Uni		RA		US
5.25	Disable adaptive control	OFF (0) or On (1)	OFF (0)	RW	Bit				US
5.26	Continuous auto tune			RW	Bit				US
5.28	Field weakening compensation disable		Eur: 0, USA: 1	RW	Bit				US
5.29	Motor saturation breakpoint 1	0 to 100% of rated flux	50	RW	Uni				US
5.30	Motor saturation breakpoint 2		75	RW	Uni				US
5.32	Motor torque per amp	0.000 to 50.000 NmA^{-1}		RO	Uni				
5.43	Armature mode	0 to 8	0	RW	Txt				US
5.44	Bridge request output			RW	Bit				
5.45		0 to 1		RW	Bit				
5.46	Slave bridge request status			RW	Bit				
5.47				RW	Bit				
5.52	IR drop	±ARMATURE_VOLTAGE_MAX Vdc		RO	Bi	FI	NC	PT	
5.53	Back emf			RO	Bi	FI	NC	PT	
5.54	Flux feedback	±150%		RO	Bi	FI	NC	PT	
5.55	Flux / Voltage demand	±120%		RW	Bi	FI	NC	PT	
5.56	Field current feedback **{di09, 0.44}**	±50.00 A		RO	Bi	FI	NC	PT	
5.57	Percentage voltage demand	±150.0%		RO	Bi	FI	NC	PT	
5.58	Field firing angle	0 to 180.0 °		RO	Uni	FI	NC	PT	
5.59	Back emf set point	0 to ARMATURE_VOLTAGE_MAX Vdc	For 480V Drive: 440 Eur 500 USA For 575V Drive: 630 Eur 630 USA For 690V Drive: 760 Eur 760 USA	RW	Uni				US
5.60	Field output voltage	0 to 500Vdc		RO	Uni	FI	NC	PT	
5.61	Armature Resistance	0 to 6.0000Ω	0.0000	RW	Uni				US
5.62	field weakening loop P gain	0 to 300.00	0.40	RW	Uni				US
5.63	field weakening loop I gain		5.00	RW	Uni				US
5.64	Field weakening enable	0 to 1	0	RW	Bit				US
5.65	Enable field economy timeout		Eur: 0, USA: 1	RW	Bit				US
5.66	Field economy timeout time	0 to 255s	30s	RW	Uni				US
5.67	Field economy level	0 to 120.0%	25.0%	RW	Uni				US
5.68	Maximum flux / Voltage limit	0 to MAX_FIELD_FLUX %	100.0%	RW	Uni				US
5.69	Minimum flux / Voltage limit	0 to 120.0%	50.0%	RW	Uni				US
5.70	Rated field current **{SE10, 0.31}**	0 to FIELD_CURRENT_SET_MAX	Size 1 - Eur: 2A , USA: 8A Size 2A & B - Eur: 3A, USA: 20A Size 2C & D - Eur: 5A, USA: 20A	RW	Uni		RA	PT	US
5.71	Flux loop P gain	0 to 30.00	3.00	RW	Uni			PT	US
5.72	Flux loop I gain	0 to 300.00	60.00	RW	Uni				US
5.73	Rated field voltage **{SE11, 0.32}**	0 to 500.0 Vdc	Eur: 360, USA: 300	RW	Uni				US
5.74	Rated field compensation factor	0 to 100%	100%	RW	Uni			PT	US
5.75	Field voltage mode select	0 to 1	Eur: 0, USA: 1	RW	Bit				US
5.76	Field controller supply	0 to 550 rms Vac		RO	Uni	FI	NC	PT	
5.77	Enable field control **{SE12, 0.33}**	0 to 1	0	RW	Bit				US
5.78	Field mode	0 to 2 (IntrnL (0), EtrnL (1) and E FULL (2))	IntrnL (0)	RW	Txt				US
5.79	Field economy active	0 to 1		RO	Bit				
5.80	Field economy level select	OFF (0) or On (1)	OFF (0)	RW	Bit				US
5.81	Field thermal time constant	0.0 to 3000.0	24.0	RW	Uni				US
5.82	Field overload accumulator	0 to 100.0%		RO	Uni		NC	PT	
5.83	Field reversal enable	0 to ONLY_2_QUADRANT	0	RW	Uni		RA		US
5.84	Field flux threshold	0 to 100%	75%	RW	Uni				US
5.85	Flux demand invert	0 to 1		RO	Bit		NC	PT	
5.86	Speed error invert	0 to 1		RO	Bit		NC	PT	

RW	Read / Write	RO	Read only	Uni	Unipolar	Bi	Bi-polar		Bit	Bit parameter	Txt	Text string			
FI	Filtered	DE	Destination	NC	Not copied	RA	Rating dependent	PT	Protected	US	User save	PS	Power down save

## 11.6 Menu 6: Sequencer and clock

Figure 11-7 Menu 6 logic diagram

Parameter		Range(⇕)	Default(⇨)	Type					
6.01	Stop mode	0 to 2	1	RW	Uni				US
6.03	Main loss ride through	OFF (0) or On (1)	OFF (0)	RW	Bit				US
6.04	Start/stop logic select	0 to 4	4	RW	Uni				US
6.08	Hold zero speed	OFF (0) or On (1)	OFF (0)	RW	Bit				US
6.09	Catch a spinning motor	0 to 1	1	RW	Uni				US
6.12	Enable stop key	OFF (0) or On (1)	OFF (0)	RW	Bit				US
6.13	Enable forward/reverse key	0 to 2	0	RW	Uni				US
6.15	Drive enable	OFF (0) or On (1)	On (1)	RW	Bit				US
6.16	Electricity cost per kWh	0.0 to 600.0 currency units per kWh	0.0	RW	Uni				US
6.17	Reset energy meter	OFF (0) or On (1)	OFF (0)	RW	Bit	NC			
6.18	Time between filter changes	0 to 30,000 hrs	0	RW	Uni				US
6.19	Filter change required / change done	OFF (0) or On (1)	OFF (0)	RW	Bit			PT	
6.20	Powered-up time: years.days	0 to 9.364 Years.Days		RW	Uni	NC		PT	
6.21	Powered-up time: hours.minutes	0 to 23.59 Hours.Minutes		RW	Uni	NC		PT	
6.22	Run time: years.days	0 to 9.364 Years.Days		RO	Uni	NC		PT	PS
6.23	Run time: hours.minutes	0 to 23.59 Hours.Minutes		RO	Uni	NC		PT	PS
6.24	Energy meter: MWh	±9999 MWh		RO	Bi	NC		PT	PS
6.25	Energy meter: kWh	±999 kWh		RO	Bi	NC		PT	PS
6.26	Running cost	±32000		RO	Bi	FI	NC	PT	
6.27	Time before filter change due	0 to 30,000 hrs		RO	Uni	NC		PT	PS
6.28	Select clock for trip log time stamping		OFF (0)	RW	Bit				US
6.29	Hardware enable			RO	Bit	NC		PT	
6.30	Sequencing bit: Run forward			RW	Bit	NC			
6.31	Sequencing bit: Jog			RW	Bit	NC			
6.32	Sequencing bit: Run/reverse			RW	Bit	NC			
6.33	Sequencing bit: Forward/reverse	OFF (0) or On (1)		RW	Bit	NC			
6.34	Sequencing bit: Run			RW	Bit	NC			
6.35	Forward limit switch		OFF (0)	RW	Bit	NC			
6.36	Reverse limit switch			RW	Bit	NC			
6.37	Sequencing bit: Jog reverse			RW	Bit	NC			
6.39	Sequencing bit: Not stop			RW	Bit	NC			
6.40	Enable sequencer latching			RW	Bit				US
6.41	Drive event flags	0 to 65535	0	RW	Uni	NC			
6.42	Control word	0 to 32767	0	RW	Uni	NC			
6.43	Control word enable	OFF (0) or On (1)	OFF (0)	RW	Bit				US
6.45	Force cooling fan to run at full speed			RW	Bit				US
6.49	Disable multi-module drive module number storing on trip	OFF (0) or On (1)	OFF (0)	RW	Bit				US
6.50	Drive comms state	0 to 3		RO	Txt	NC		PT	
6.52	Zero reference interlock	OFF (0) or On (1)	OFF (0)	RW	Bit				US
6.54	Run rising edge delay	0 to 25.0s	0.3	RW	Uni				US
6.55	Contactor active	OFF (0) or On (1)		RO	Bit	NC		PT	
6.56	Drive active falling edge delay	0 to 255s	0s	RW	Uni				US

RW	Read / Write	RO	Read only	Uni	Unipolar	Bi	Bi-polar	Bit	Bit parameter	Txt	Text string		
FI	Filtered	DE	Destination	NC	Not copied	RA	Rating dependent	PT	Protected	US	User save	PS	Power down save

11.7   Menu 7: Analog I/O

Figure 11-8   Menu 7 logic diagram

Parameter		Range(⇕)	Default(⇨)	Type				
7.01	T5/6 analog input 1 **{in02, 0.82}**	±100.00%		RO	Bi		NC	PT	
7.02	T7 analog input 2 **{in03, 0.83}**	±100.0%		RO	Bi		NC	PT	
7.03	T8 analog input 3 **{in04, 0.84}**			RO	Bi		NC	PT	
7.04	Power circuit temperature	-128°C to 127°C		RO	Bi		NC	PT	
7.08	T5/6 analog input 1 scaling	0 to 40.000	1.000	RW	Uni				US
7.09	T5/6 analog input 1 invert	OFF (0) to On (1)	OFF (0)	RW	Bit				US
7.10	T5/6 analog input 1 destination	Pr **0.00** to **22.99**	Pr **1.36**	RW	Uni			PT	US
7.11	T7 analog input 2 mode	0 to 6	6	RW	Uni				US
7.12	T7 analog input 2 scaling	0 to 40.000	1.000	RW	Uni				US
7.13	T7 analog input 2 invert	OFF (0) to On (1)	OFF (0)	RW	Bit				US
7.14	T7 analog input 2 destination	Pr **0.00** to **22.99**	Pr **1.37**	RW	Uni			PT	US
7.15	T8 analog input 3 mode **{in01, 0.81}**	0 to 9	Eur: 8, USA: 6	RW	Txt				US
7.16	T8 analog input 3 scaling	0 to 40.000	1.000	RW	Uni				US
7.17	T8 analog input 3 invert	OFF (0) to On (1)	OFF (0)	RW	Bit				US
7.18	T8 analog input 3 destination	Pr **0.00** to **22.99**	Pr **0.00**	RW	Uni			PT	US
7.19	T9 analog output 1 source		Pr **3.02**	RW	Uni			PT	US
7.20	T9 analog output 1 scaling	0.000 to 40.000	1.000	RW	Uni				US
7.21	T9 analog output 1 mode	0 to 3	0	RW	Txt				US
7.22	T10 analog output 2 source	Pr **0.00** to **22.99**	Pr **4.02**	RW	Uni			PT	US
7.23	T10 analog output 2 scaling	0.000 to 40.000	1.000	RW	Uni				US
7.24	T10 analog output 2 mode	0 to 3	0	RW	Txt				US
7.28	T7 analog input current loop loss 2	OFF (0) to On (1)		RO	Bit		NC	PT	
7.29	T8 analog input current loop loss 3			RO	Bit		NC	PT	
7.30	T5/6 analog input 1 offset	±100.00%	0.00	RW	Bi				US
7.31	T7 analog input 2 offset	±100.0%	0.0	RW	Bi				US
7.32	T8 analog input 3 offset			RW	Bi				US
7.34	SCR / Thyristor junction temperature	0 to 150°C		RO	Uni		NC	PT	

RW	Read / Write	RO	Read only	Uni	Unipolar	Bi	Bi-polar	Bit	Bit parameter	Txt	Text string		
FI	Filtered	DE	Destination	NC	Not copied	RA	Rating dependent	PT	Protected	US	User save	PS	Power down save

## 11.8 Menu 8: Digital I/O

Figure 11-9 Menu 8 logic diagram

Figure 11-10   Menu 8 logic diagram (cont)

Figure 11-11   Menu 8 logic diagram (cont)

Parameter		Range(⇕)	Default(⇨)	Type				
8.01	T24 digital I/O 1 state {in05, 0.85}			RO	Bit		NC	PT	
8.02	T25 digital I/O 2 state {in06, 0.86}			RO	Bit		NC	PT	
8.03	T26 digital I/O 3 state {in07, 0.87}			RO	Bit		NC	PT	
8.04	T27 digital input 4 state {in08, 0.88}	OFF (0) or On (1)		RO	Bit		NC	PT	
8.05	T28 digital input 5 state {in09, 0.89}			RO	Bit		NC	PT	
8.06	T29 digital input 6 state {in10, 0.90}			RO	Bit		NC	PT	
8.07	T51, 52, 53 relay state			RO	Bit		NC	PT	
8.09	T31 drive enable state			RO	Bit		NC	PT	
8.10	Enable mode select	0 to 2	0	RW	Uni				US
8.11	T24 digital I/O 1 invert			RW	Bit				US
8.12	T25 digital I/O 2 invert			RW	Bit				US
8.13	T26 digital I/O 3 invert			RW	Bit				US
8.14	T27 digital input 4 invert	OFF (0) or On (1)	OFF (0)	RW	Bit				US
8.15	T28 digital input 5 invert			RW	Bit				US
8.16	T29 digital input 6 invert			RW	Bit				US
8.17	T51, 52, 53 relay invert			RW	Bit				US
8.20	Digital I/O read word	0 to 4095		RO	Uni		NC	PT	
8.21	T24 digital I/O 1 source/ destination		Pr **10.06**	RW	Uni	DE		PT	US
8.22	T25 digital I/O 2 source/ destination		Pr **10.33**	RW	Uni	DE		PT	US
8.23	T26 digital I/O 3 source/ destination		Pr **6.30**	RW	Uni	DE		PT	US
8.24	T27 digital input 4 destination	Pr **0.00** to **22.99**	Pr **6.32**	RW	Uni	DE		PT	US
8.25	T28 digital input 5 destination		Pr **1.41**	RW	Uni	DE		PT	US
8.26	T29 digital input 6 destination		Pr **6.31**	RW	Uni	DE		PT	US
8.27	T51, 52, 53 relay source		Pr **10.01**	RW	Uni			PT	US
8.29	I/O polarity select	2	1	RW	Uni			PT	US
8.30	Open collector output		OFF (0)	RW	Bit				US
8.31	T24 digital I/O 1 output select		On (1)	RW	Bit				US
8.32	T25 digital I/O 2 output select			RW	Bit				US
8.33	T26 digital I/O 3 output select		OFF (0)	RW	Bit				US
8.40	T61, 62, 63 relay state	OFF (0) or On (1)		RO	Bit		NC	PT	
8.41	Start button state			RO	Bit		NC	PT	
8.42	Forward/reverse button state		OFF (0)	RO	Bit		NC	PT	
8.48	24V input state			RO	Bit		NC	PT	
8.50	T61, 62, 63 relay invert		OFF (0)	RW	Bit				US
8.52	Toggle enable			RW	Bit				US
8.60	T61, 62, 63 relay destination		Pr **6.55**	RW	Uni	DE		PT	US
8.61	Start button destination	Pr **0.00** to **22.99**	Pr **0.00**	RW	Uni	DE		PT	US
8.62	Forward/reverse button destination			RW	Uni	DE		PT	US

RW	Read / Write	RO	Read only	Uni	Unipolar	Bi	Bi-polar	Bit	Bit parameter	Txt	Text string		
FI	Filtered	DE	Destination	NC	Not copied	RA	Rating dependent	PT	Protected	US	User save	PS	Power down save

11.9   Menu 9: Programmable logic, motorized pot and binary sum

Figure 11-12   Menu 9 logic diagram: Programmable logic

Figure 11-13   Menu 9 logic diagram: Motorized potentiometer and binary sum

Parameter		Range(⇕)	Default(⇨)	Type					
9.01	Logic function 1 output	OFF (0) or On (1)		RO	Bit		NC	PT	
9.02	Logic function 2 output			RO	Bit		NC	PT	
9.03	Motorized pot output	±100.00%		RO	Bit		NC	PT	PS
9.04	Logic function 1 source 1	Pr **0.00** to **22.99**	Pr **0.00**	RW	Uni			PT	US
9.05	Logic function 1 source 1 invert	OFF (0) or On (1)	OFF (0)	RW	Bit				US
9.06	Logic function 1 source 2	Pr **0.00** to **22.99**	Pr **0.00**	RW	Uni			PT	US
9.07	Logic function 1 source 2 invert	OFF (0) or On (1)	OFF (0)	RW	Bit				US
9.08	Logic function 1 output invert			RW	Bit				US
9.09	Logic function 1 delay	±25.0s	0.0	RW	Bi				US
9.10	Logic function 1 destination	Pr **0.00** to **22.99**	Pr **0.00**	RW	Uni			PT	US
9.14	Logic function 2 source 1			RW	Uni			PT	US
9.15	Logic function 2 source 1 invert	OFF (0) or On (1)	OFF (0)	RW	Bit				US
9.16	Logic function 2 source 2	Pr **0.00** to **22.99**	Pr **0.00**	RW	Uni			PT	US
9.17	Logic function 2 source 2 invert	OFF (0) or On (1)	OFF (0)	RW	Bit				US
9.18	Logic function 2 output invert			RW	Bit				US
9.19	Logic function 2 delay	±25.0s	0.0	RW	Bi				US
9.20	Logic function 2 destination	Pr **0.00** to **22.99**	Pr **0.00**	RW	Uni			PT	US
9.21	Motorized pot mode	0 to 3	2	RW	Uni				US
9.22	Motorized pot bipolar select	OFF (0) or On (1)	OFF (0)	RW	Bit				US
9.23	Motorized pot rate	0 to 250s	20	RW	Uni				US
9.24	Motorized pot scale factor	0 to 4.000	1.000	RW	Uni				US
9.25	Motorized pot destination	Pr **0.00** to **22.99**	Pr **0.00**	RW	Uni			PT	US
9.26	Motorized pot up			RW	Bit		NC		
9.27	Motorized pot down			RW	Bit		NC		
9.28	Motorized pot reset	OFF (0) or On (1)	OFF (0)	RW	Bit		NC		
9.29	Binary sum ones input			RW	Bit		NC		
9.30	Binary sum twos input			RW	Bit		NC		
9.31	Binary sum fours input			RW	Bit		NC		
9.32	Binary sum output	0 to 255		RO	Uni		NC	PT	
9.33	Binary sum destination	Pr **0.00** to **22.99**	Pr **0.00**	RW	Uni			PT	US
9.34	Binary sum offset	0 to 248	0	RW	Uni				US
9.35	Up down disable source	Pr **0.00** to **22.99**	Pr **0.00**	RW	Uni			PT	US
9.36	Up down disable invert	OFF (0) or On (1)	OFF (0)	RW	Bit				US
9.37	Logic block 1 mode	0 to 4	0	RW	Uni				US
9.38	Logic block 2 mode			RW	Uni				US

RW	Read / Write	RO	Read only	Uni	Unipolar	Bi	Bi-polar	Bit	Bit parameter	Txt	Text string		
FI	Filtered	DE	Destination	NC	Not copied	RA	Rating dependent	PT	Protected	US	User save	PS	Power down save

11.10   Menu 10: Status and trips

Parameter		Range(⇕)	Default(⇨)	Type				
10.01	Drive ok			RO	Bit		NC	PT	
10.02	Drive active			RO	Bit		NC	PT	
10.03	Zero speed			RO	Bit		NC	PT	
10.04	Running at or below min speed			RO	Bit		NC	PT	
10.05	Below set speed			RO	Bit		NC	PT	
10.06	At speed			RO	Bit		NC	PT	
10.07	Above set speed			RO	Bit		NC	PT	
10.08	Load reached	OFF (0) or On (1)		RO	Bit		NC	PT	
10.09	Drive output is at current limit			RO	Bit		NC	PT	
10.10	Regenerating			RO	Bit		NC	PT	
10.13	Direction command			RO	Bit		NC	PT	
10.14	Direction running			RO	Bit		NC	PT	
10.17	Overload arm			RO	Bit		NC	PT	
10.18	Drive over temperature alarm			RO	Bit		NC	PT	
10.19	Drive warning			RO	Bit		NC	PT	
10.20	Trip 0 {tr01, 0.51}			RO	Txt		NC	PT	PS
10.21	Trip 1 {tr02, 0.52}			RO	Txt		NC	PT	PS
10.22	Trip 2 {tr03, 0.53}			RO	Txt		NC	PT	PS
10.23	Trip 3 {tr04, 0.54}			RO	Txt		NC	PT	PS
10.24	Trip 4 {tr05, 0.55}	0 to 229		RO	Txt		NC	PT	PS
10.25	Trip 5 {tr06, 0.56}			RO	Txt		NC	PT	PS
10.26	Trip 6 {tr07, 0.57}			RO	Txt		NC	PT	PS
10.27	Trip 7 {tr08, 0.58}			RO	Txt		NC	PT	PS
10.28	Trip 8 {tr09, 0.59}			RO	Txt		NC	PT	PS
10.29	Trip 9 {tr10, 0.60}			RO	Txt		NC	PT	PS
10.32	External trip	OFF (0) or On (1)	OFF (0)	RW	Bit		NC		
10.33	Drive reset			RW	Bit		NC		
10.34	Number of auto-reset attempts	0 to 5	0	RW	Uni				US
10.35	Auto-reset delay	0 to 25.0s	1.0	RW	Uni				US
10.36	Hold drive ok until last attempt	OFF (0) or On (1)	OFF (0)	RW	Bit				US
10.38	User trip	0 to 255	0	RW	Uni		NC		
10.40	Status word	0 to 32767		RO	Uni		NC	PT	
10.41	Trip 0 time: Years.Days	0 to 9.364 Years.Days		RO	Uni		NC	PT	PS
10.42	Trip 0 time: Hours.Minutes	0 to 23.59 Hours.Minutes		RO	Uni		NC	PT	PS
10.43	Trip 1 time: Hours.Minutes			RO	Uni		NC	PT	PS
10.44	Trip 2 time: Hours.Minutes			RO	Uni		NC	PT	PS
10.45	Trip 3 time: Hours.Minutes			RO	Uni		NC	PT	PS
10.46	Trip 4 time: Hours.Minutes			RO	Uni		NC	PT	PS
10.47	Trip 5 time: Hours.Minutes	0 to 600.00 Hours.Minutes		RO	Uni		NC	PT	PS
10.48	Trip 6 time: Hours.Minutes			RO	Uni		NC	PT	PS
10.49	Trip 7 time: Hours.Minutes			RO	Uni		NC	PT	PS
10.50	Trip 8 time: Hours.Minutes			RO	Uni		NC	PT	PS
10.51	Trip 9 time: Hours.Minutes			RO	Uni		NC	PT	PS
10.52	Trip mask 0			RW	Uni				US
10.53	Trip mask 1			RW	Uni				US
10.54	Trip mask 2			RW	Uni				US
10.55	Trip mask 3			RW	Uni				US
10.56	Trip mask 4	0 to 216	0	RW	Uni				US
10.57	Trip mask 5			RW	Uni				US
10.58	Trip mask 6			RW	Uni				US
10.59	Trip mask 7			RW	Uni				US
10.60	Trip mask 8			RW	Uni				US
10.61	Trip mask 9			RW	Uni				US
10.62	Stop on trip mask 0			RW	Bit				US
10.63	Stop on trip mask 1			RW	Bit				US
10.64	Stop on trip mask 2			RW	Bit				US
10.65	Stop on trip mask 3			RW	Bit				US
10.66	Stop on trip mask 4		On (1)	RW	Bit				US
10.67	Stop on trip mask 5	OFF (0) or On (1)		RW	Bit				US
10.68	Stop on trip mask 6			RW	Bit				US
10.69	Stop on trip mask 7			RW	Bit				US
10.70	Stop on trip mask 8			RW	Bit				US
10.71	Stop on trip mask 9			RW	Bit				US
10.72	Trip mask active			RO	Bit		NC		
10.73	Bridge active	0 to 2		RO	Txt		NC		
10.74	Electrical phase back			RO	Bit		NC		
10.75	Armature voltage clamp active	OFF (0) or On (1)		RO	Bit		NC		
10.76	Phase rotation	0 to 15		RO	Txt		NC		
10.77	Input frequency	0 to 100.00		RO	Uni		NC		

11.11 Menu 11: General drive set-up

Parameter	Range(⇕)	Default(⇨)	Type				
11.21 Parameter scaling	0 to 9.999	1.000	RW	Uni			US
11.22 Parameter displayed at power-up	0 to 00.90	00.40	RW	Uni		PT	US
11.23 Serial address {Si02, 0.67}	0 to 247	1	RW	Uni			US
11.24 Serial mode	0 to 2	1	RW	Txt			US
11.25 Baud rate {Si01, 0.66}	0 to 9	6	RW	Txt			US
11.26 Minimum comms transmit delay	0 to 250ms	2	RW	Uni			US
11.29 Software version {di14, 0.49}	1.0 to 99.99		RO	Uni	NC	PT	
11.30 User security code	0 to 999	0	RW	Uni	NC	PT	PS
11.32 Current rating	0 to 10000.0A		RO	Uni	NC	PT	
11.33 Drive voltage rating	0 (480), 1 (575), 2 (690)		RO	Txt	NC	PT	
11.34 Software sub-version	0 to 99		RO	Uni	NC	PT	
11.35 Number of modules	0 to 4		RW	Uni		PT	US
11.36 SMARTCARD parameter data previously loaded	0 to 999	0	RO	Uni	NC	PT	US
11.37 SMARTCARD data number	0 to 1003		RW	Uni	NC		
11.38 SMARTCARD data type/ mode	0 to 18		RO	Uni	NC	PT	
11.39 SMARTCARDdata version	0 to 9999	0	RW	Uni	NC		
11.40 SMARTCARD data checksum	0 to 65335		RO	Uni	NC	PT	
11.41 Status mode timeout	0 to 250s	240	RW	Uni			US
11.42 Parameter copying {SE09, 0.30}	0 to 4	0	RW	Txt	NC		*
11.44 Security status {SE14, 0.35}	0 to 2	0	RW	Txt		PT	
11.45 Select motor 2 parameters	OFF (0) or On (1)	OFF (0)	RW	Bit			US
11.46 Defaults previously loaded	0 to 2	Eur: or USA: 0	RO	Txt		PT	US
11.47 Drive Onboard Application Lite Ladder Program Enable	0 to 2	2	RW	Uni			US
11.48 Drive Onboard Application Lite Ladder Program Status	-128 to +127		RO	Bi	NC	PT	
11.49 Drive Onboard Application Lite Ladder Program Events	0 to 65535		RO	Uni	NC	PT	PS
11.50 Drive Onboard Application Lite Ladder Program Maximum Scan Time	0 to 65335ms		RO	Uni	NC	PT	
11.51 Drive Onboard Application Lite Ladder Program First Run	OFF (0) or On (1)		RO	Bit	NC	PT	
11.52 Drive serial number	0 to 999 999 999		RO	Uni	NC	PT	
11.53 Build location	0 to 255		RO	Uni	NC	PT	
11.55 Drive rating number	0 to 56		RO	Uni	NC	PT	
11.56 Power PCB software version	1.00 to 99.99		RO	Uni	NC	PT	
11.57 Serial programmable source	Pr **0.00** to **22.99**	Pr **0.00**	RW	Uni		PT	US
11.58 Serial scaling	0 to 1999	1000	RW	Uni			US
11.59 Mentor II Parameter Emulator Module Control	0 to 3	0	RW	Uni			US
11.60 Application parameters	16000 to -16000		RW	Uni	NC		
11.61 Application parameters			RW	Uni	NC		
11.62 Full power discharge time	0 to 25.0s	0.0	RW	Uni			US
11.63 Full power discharge period	0 to 1500.0s		RW	Uni			US
11.64 External discharge resistance	0 to 9999Ω	0	RW	Uni			US
11.65 External resistor temperature	0 to 100%		RO		NC	PT	
11.66 Suppressor voltage	0 to 2000V		RO		NC	PT	

RW	Read / Write	RO	Read only	Uni	Unipolar	Bi	Bi-polar	Bit	Bit parameter	Txt	Text string		
FI	Filtered	DE	Destination	NC	Not copied	RA	Rating dependent	PT	Protected	US	User save	PS	Power down save

* Modes 1 and 2 are not US (i.e. not saved when drive parameters are saved), mode 3 and 4 are US. Therefore this parameter can only be saved to EEPROM if it has a value of 0, 3 or 4.

11.12 Menu 12: Threshold detectors, variable selectors and brake control function

Figure 11-14 Menu 12 logic diagram

Figure 11-15   Menu 12 logic diagram (continued)

Variable Selector 1

Any variable parameter

Variable selector 1 input 1 scaling

Variable selector 1 output indicator

Variable selector 1 output destination

Any unprotected variable parameter

??.??

12.13

12.12

12.11

??.??

??.??

12.08   Variable selector 1 input 1 source

12.10   Variable selector 1 mode

12.15   Variable selector 1 control

??.??

Any variable parameter

Variable selector 1 input 2 scaling

??.??

12.14

??.??

12.09   Variable selector 1 input 2 source

Variable Selector 2

Any variable parameter

Variable selector 2 input 1 scaling

Variable selector 2 output indicator

Variable selector 2 output destination

Any unprotected variable parameter

??.??

12.33

12.32

12.31

??.??

??.??

12.28   Variable selector 2 input 1 source

12.30   Variable selector 2 mode

12.35   Variable selector 2 control

??.??

Any variable parameter

Variable selector 2 input 2 scaling

??.??

12.34

??.??

12.29   Variable selector 2 input 2 source

Key

| X ⊘   X ⊘ | Input terminals | 0.XX | Read-write (RW) parameter |
| X ⊘   X ⊘ | Output terminals | 0.XX | Read-only (RO) parameter |

Figure 11-16   Menu 12 Brake control function

Figure 11-17   Brake sequence

1. Wait for armature current and fully fluxed machine
2. Post-brake release delay
3. Wait for speed threshold
4. Wait for brake apply speed delay
5. Brake apply delay

Parameter		Range(⇕)	Default(⇨)	Type				
12.01	Threshold detector 1 output	OFF (0) or On (1)		RO	Bit		NC	PT	
12.02	Threshold detector 2 output			RO	Bit		NC	PT	
12.03	Threshold detector 1 source	Pr **0.00** to **22.99**	Pr **0.00**	RW	Uni			PT	US
12.04	Threshold detector 1 level	0 to 100.00%	0.00	RW	Uni				US
12.05	Threshold detector 1 hysteresis	0 to 25.00%		RW	Uni				US
12.06	Threshold detector 1 output invert	OFF (0) or On (1)	OFF (0)	RW	Bit				US
12.07	Threshold detector 1 destination			RW	Uni			PT	US
12.08	Variable selector 1 source 1	Pr **0.00** to **22.99**	Pr **0.00**	RW	Uni			PT	US
12.09	Variable selector 1 source 2			RW	Uni			PT	US
12.10	Variable selector 1 mode	0 to 10	0	RW	Uni				US
12.11	Variable selector 1 destination	Pr **0.00** to **22.99**	Pr **0.00**	RW	Uni			PT	US
12.12	Variable selector 1 output	±100.00%		RO	Uni		NC	PT	
12.13	Variable selector 1 source 1 scaling	±4.000	1.000	RW	Uni				US
12.14	Variable selector 1 source 2 scaling			RW	Uni				US
12.15	Variable selector 1 control	0 to 100.00	0.00	RW	Uni				US
12.23	Threshold detector 2 source	Pr **0.00** to **22.99**	Pr **0.00**	RW	Uni			PT	US
12.24	Threshold detector 2 level	0 to 100.00%	0.00	RW	Uni				US
12.25	Threshold detector 2 hysteresis	0 to 25.00%		RW	Uni				US
12.26	Threshold detector 2 output invert	OFF (0) or On (1)	OFF (0)	RW	Bit				US
12.27	Threshold detector 2 destination			RW	Uni			PT	US
12.28	Variable selector 2 source 1	Pr **0.00** to **22.99**	Pr **0.00**	RW	Uni			PT	US
12.29	Variable selector 2 source 2			RW	Uni			PT	US
12.30	Variable selector 2 mode	0 to 10	0	RW	Uni				US
12.31	Variable selector 2 destination	Pr **0.00** to **22.99**	Pr **0.00**	RW	Uni			PT	US
12.32	Variable selector 2 output	±100.00%		RO	Uni		NC	PT	
12.33	Variable selector 2 source 1 scaling	±4.000	1.000	RW	Uni				US
12.34	Variable selector 2 source 2 scaling			RW	Uni				US
12.35	Variable selector 2 control	0 to 100.00	0.00	RW	Uni				US
12.40	Brake release	OFF (0) or On (1)		RO	Uni		NC	PT	
12.41	Brake controller enable	0 to 3	0	RW	Txt				US
12.43	Lower current threshold	0 to 150%	10%	RW	Uni				US
12.45	Brake apply speed	0 to 200rpm	5rpm	RW	Uni				US
12.46	Brake apply speed delay			RW	Uni				US
12.47	Post-brake release delay	0 to 25.0s	1.0s	RW	Uni				US
12.48	Brake apply delay			RW	Uni				US
12.49	Enable position controller during brake release	OFF (0) or On (1)	OFF (0)	RW	Bit				US
12.50	Field active			RW	Bit				US
12.51	External field control			RW	Bit				US

RW	Read / Write	RO	Read only	Uni	Unipolar	Bi	Bi-polar	Bit	Bit parameter	Txt	Text string		
FI	Filtered	DE	Destination	NC	Not copied	RA	Rating dependent	PT	Protected	US	User save	PS	Power down save

11.13   Menu 13: Position control

Figure 11-18   Menu 13 logic diagram

Speed reference selected **1.01**

Velocity feed-forward **1.39**

Velocity feed-forward select **1.40**

Pre-ramp reference **1.03**

Menu 2 Ramp Control

Post-ramp reference **2.01**

Final speed reference **3.01**

Position controller mode **13.10**

13.10 = 5 or 6

13.10 = 1 or 3

13.10 = 1 to 6

Hard speed reference selector **3.23**

Position loop disabled

Hold zero speed **6.08**

Hard speed reference **3.22**

Position loop error
Revolution **13.01** Position **13.02** Fine Position **13.03**

Position controller P gain **13.09**

Position loop enabled

13.12 Position controller speed clamp

Orientation acceptance window **13.14**

Orientation

Orientation position complete **13.15**

Key

| X ⊘ / X ⊘ | Input terminals | **0.XX** | Read-write (RW) parameter |
| X ⊘ / X ⊘ | Output terminals | ◇ 0.XX | Read-only (RO) parameter |

This logic diagram applies only when all parameters are at their default settings

Parameter		Range(⇕)	Default(⇨)	Type				
13.01	Revolutions error	-32768 to +32767		RO	Uni		NC	PT	
13.02	Position error	-32768 to +32767		RO	Uni		NC	PT	
13.03	Fine position error	-32768 to +32767		RO	Uni		NC	PT	
13.04	Position controller reference source	0 to 4	0	RW	Txt				US
13.05	Position controller feedback source	0 to 3	0	RW	Txt				US
13.06	Position reference invert	OFF (0) or On(1)	OFF (0)	RW	Bit				US
13.07	Ratio numerator	0 to 4.000	1.000	RW	Uni				US
13.08	Ration denominator	0 to 1.000	1.000	RW	Uni				US
13.09	Position controller P gain	0 to 100.00 rads^{-1}/rad	25.00	RW	Uni				US
13.10	Position controller mode	0 to 6	0	RW	Uni				US
13.11	Absolute mode enable	OFF (0) or On(1)	OFF (0)	RW	Bit				US
13.12	Position controller speed clamp	0 to 250	150	RW	Uni				US
13.13	Orientation position reference	0 to 65535	0	RW	Uni				US
13.14	Orientation acceptance window	0 to 4096	256	RW	Uni				US
13.15	Orientation position complete	OFF (0) or On(1)		RO	Bit		NC	PT	
13.16	Position error reset	OFF (0) or On(1)	OFF (0)	RW	Bit		NC		
13.17	Relative jog reference	0 to 4000.0rpm	0.0	RW	Uni				US
13.18	Relative jog enable	OFF (0) or On(1)	OFF (0)	RW	Bit		NC		
13.19	Relative jog reverse	OFF (0) or On(1)	OFF (0)	RW	Bit		NC		
13.20	Local reference turns	0 to 65535	0	RW	Uni		NC		
13.21	Local reference position	0 to 65535	0	RW	Uni		NC		
13.22	Local reference fine position	0 to 65535	0	RW	Uni		NC		
13.23	Local reference disable	OFF (0) or On(1)	OFF (0)	RW	Bit		NC		
13.24	Ignore local reference turns	OFF (0) or On(1)	OFF (0)	RW	Bit				US

RW	Read / Write	RO	Read only	Uni	Unipolar	Bi	Bi-polar	Bit	Bit parameter	Txt	Text string		
FI	Filtered	DE	Destination	NC	Not copied	RA	Rating dependent	PT	Protected	US	User save	PS	Power down save

11.14   Menu 14: User PID controller

Figure 11-19   Menu 14 logic diagram

PID hold integrator *enable*

14.17

14.10 PID proportional gain

14.11 PID integral gain

14.12 PID derivative gain

14.13 PID output high limit

14.14 PID output low limit

14.18 PID symmetrical limits *enable*

PID controller output

14.01

PID output scale factor

14.15

PID output destination parameter*

14.16

Any unprotected variable parameter

??.??

??.??

Key

Input terminals	Read-write (RW) parameter **0.XX**
Output terminals	Read-only (RO) parameter **0.XX**

The parameters are all shown at their default settings

*The PID controller is only enabled if Pr **14.16** is set to a non Pr **xx.00** and unprotected destination parameter.

Parameter	Range(⇕)	Default(⇨)	Type			
14.01 PID output	±100.00%		RO	Uni	NC	PT
14.02 PID source1	Pr **0.00** to **22.99**	Pr **0.00**	RW	Uni	PT	US
14.03 PID source 2	Pr **0.00** to **22.99**	Pr **0.00**	RW	Uni	PT	US
14.04 PID source 3	Pr **0.00** to **22.99**	Pr **0.00**	RW	Uni	PT	US
14.05 PID source invert 1	OFF (0) or On (1)	OFF (0)	RW	Bit		US
14.06 PID source invert 2	OFF (0) or On (1)	OFF (0)	RW	Bit		US
14.07 PID reference slew rate limit	0 to 3200.0s	0.0	RW	Uni		US
14.08 PID enable	OFF (0) or On (1)	OFF (0)	RW	Bit		US
14.09 PID optional enable source	Pr **0.00** to **22.99**	Pr **0.00**	RW	Uni	PT	US
14.10 PID P gain	0 to 4.000	1.000	RW	Uni		US
14.11 PID I gain	0 to 4.000	0.500	RW	Uni		US
14.12 PID D gain	0 to 4.000	0.000	RW	Uni		US
14.13 PID upper limit	0 to 100.00%	100.00	RW	Uni		US
14.14 PID lower limit	±100.00%	-100.00	RW	Bi		US
14.15 PID scaling	0 to 4.000	1.000	RW	Uni		US
14.16 PID destination	Pr **0.00** to **22.99**	Pr **0.00**	RW	Uni	PT	US
14.17 PID hold integrator	OFF (0) or On (1)	OFF (0)	RW	Bit	NC	
14.18 PID symmetrical limit enable	OFF (0) or On (1)	OFF (0)	RW	Bit		US
14.19 PID main reference	±100.00%		RO	Bi	NC	PT
14.20 PID reference	±100.00%		RO	Bi	NC	PT
14.21 PID feedback	±100.00%		RO	Bi	NC	PT
14.22 PID error	±100.00%		RO	Bi	NC	PT

RW	Read / Write	RO	Read only	Uni	Unipolar	Bi	Bi-polar	Bit	Bit parameter	Txt	Text string		
FI	Filtered	DE	Destination	NC	Not copied	RA	Rating dependent	PT	Protected	US	User save	PS	Power down save

11.15 Menus 15, 16 and 17: Solutions Module slots

Pr **x.00** and Pr **x.01** are always present in menus 15, 16 and 17. Pr **x.01** indicates which type of module is present (0 = no module installed). When a module is installed the drive provides the relevant menu (menu 15 for slot 1, 16 for slot 2 and 17 for slot 3) depending on the Solutions Module installed. The possible categories are shown below.

Solutions Module ID	Module	Category
0	No module installed	
102	SM-Universal Encoder Plus	Feedback
104	SM-Encoder Plus and SM-Encoder Output Plus	
201	SM-I/O Plus	Automation (I/O Expansion)
203	SM-I/O Timer	
204	SM-I/O PELV	
205	SM-I/O24V Protected	
206	SM-I/O120V	
207	SM-I/O Lite	
208	SM-I/O 32	
304	SM-Applications Plus	Automation (Applications)
305	SM-Applications Lite V2	
306	SM-Register	
403	SM-PROFIBUS DP-V1	Fieldbus
404	SM-INTERBUS	
407	SM-DeviceNet	
408	SM-CANopen	
410	SM-Ethernet	
421	SM-EtherCAT	

Refer to the specific Solutions Module User Guide for more information.

Most modules include a processor and parameters are updated by the processor in the Solutions Module. However, dumb modules do not contain a processor and all parameters are updated by the drive processor.

Dumb Solutions Module parameters are read/written by the drive background task or at the combined update time for time critical parameters. The combined update time depends on the number and type of dumb Solutions Modules installed to the drive. For each Solutions Module the update rate of these parameters is specified as 4ms, 8ms, etc. The combined update time is the total of the update times for all dumb Solutions Modules installed.

For example, if a module with 4ms update time and a module with 8ms are installed to the drive, then the combined update time for the time critical parameters of each module is 12ms.

In the parameter tables the update time added by the type of module is given, for example 4ms for the SM-Encoder Plus or 8ms for the SM-I/O Plus.

When parameters are saved by the user in the drive EEPROM the option code of the currently installed module is saved in EEPROM. If the drive is subsequently powered-up with a different module installed, or no module installed where a module was previously installed, the drive gives a Slot.dF trip. The menu for the relevant slot appears for the new module category with the default parameter values for the new category. The new parameters values are not stored in EEPROM until the user performs a parameter save.

Parameters common to all categories

Parameter		Range	Default	Type					
x.01	Solutions Module ID	0 to 599		RO	Uni			PT	US
x.50	Solutions Module error status	0 to 255		RO	Uni		NC	PT	

11.16 Menu 18: Application menu 1

Parameter		Range(⇕)	Default(⇨)	Type				
18.01	Application menu 1 power-down saved integer	-32,768 to +32,767	0	RW	Bi		NC	PS
18.02 to 18.10	Application menu 1 read-only integer	-32,768 to +32,767	0	RO	Bi		NC	
18.11 to 18.30	Application menu 1 read-write integer	-32,768 to +32,767	0	RW	Bi			US
18.31 to 18.50	Application menu 1 read-write bit	OFF (0) or On (1)	0	RW	Bit			US

11.17 Menu 19: Application menu 2

Parameter		Range(⇕)	Default(⇨)	Type				
19.01	Application menu 2 power-down saved integer	-32,768 to +32,767	0	RW	Bi		NC	PS
19.02 to 19.10	Application menu 2 read-only integer	-32,768 to +32,767	0	RO	Bi		NC	
19.11 to 19.30	Application menu 2 read-write integer	-32,768 to +32,767	0	RW	Bi			US
19.31 to 19.50	Application menu 2 read-write bit	OFF (0) or On (1)	0	RW	Bit			US

11.18 Menu 20: Application menu 3

Parameter		Range(⇕)	Default(⇨)	Type			
20.01 to 20.20	Application menu 3 read-write integer	-32,768 to +32,767	0	RW	Bi		NC
20.21 to 20.40	Application menu 3 read-write long integer	-2^{31} to $2^{31}-1$	0	RW	Bi		NC

All menu 20 parameters are transferred to the SMARTCARD when a 4yyy transfer is performed. See section 9.3.1 *Writing to the SMARTCARD* on page 81 for more information.

RW	Read / Write	RO	Read only	Uni	Unipolar	Bi	Bi-polar	Bit	Bit parameter	Txt	Text string		
FI	Filtered	DE	Destination	NC	Not copied	RA	Rating dependent	PT	Protected	US	User save	PS	Power down save

11.19   Menu 21: Second motor parameters

Parameter		Range(⇕)	Default(⇨)	Type					
21.01	Maximum reference clamp	SPEED_LIMIT_MAX rpm	1000.0	RW	Uni				US
21.02	Minimum reference clamp	±SPEED_LIMIT_MAX rpm*	0.0	RW	Bi			PT	US
21.03	Reference selector	0 to 6	0 (A1.A2)	RW	Txt				US
21.04	Acceleration rate	0 to MAX_RAMP_RATE_M2	5.000	RW	Uni				US
21.05	Deceleration rate	0 to MAX_RAMP_RATE_M2	5.000	RW	Uni				US
21.06	Base speed	0 to 10000.0 rpm	1000	RW	Uni				US
21.07	Rated current	0 to RATED_CURRENT_MAX A	RATED_CURRENT_MAX	RW	Uni				US
21.08	Back emf set point	0 to ARMATURE_VOLTAGE_MAX V DC	For 480V drive: 440 Eur, 500 USA For 575V drive: 630 Eur, 630 USA For 690V drive: 760 Eur, 760 USA	RW	Uni				US
21.09	Rated voltage	0 to ARMATURE_VOLTAGE_MAX V DC	For 480V drive: 440 Eur, 500 USA For 575V drive: 630 Eur, 630 USA For 690V drive: 760 Eur, 760 USA	RW	Uni				US
21.10	Armature resistance	0 to 6.0000Ω	0.0000	RW	Uni				US
21.11	Motor constant	0 to 100.0%	50%	RW	Uni	RA			US
21.12	Discontinuous current controller Ki gain	0 to 4000	200	RW	Uni		RA		US
21.13	Continuous current controller Kp gain	0 to 4000	100	RW	Uni		RA		US
21.14	Continuous current controller Ki gain	0 to 4000	50	RW	Uni		RA		US
21.15	Motor 2 active	OFF (0) or On (1)		RO	Bit		NC	PT	
21.16	Thermal time constant	0 to 3000.0	89.0	RW	Uni				US
21.17	Speed controller Kp gain	0.00 to 6.5535(1 / (rad/s))	0.0300	RW	Uni				US
21.18	Speed controller Ki gain	0.00 to 655.35(s / (rad/s))	0.10	RW	Uni				US
21.19	Speed controller Kd gain	0.00000 to 0.65535(1/s / (rad/s))	0.00000	RW	Uni				US
21.21	Speed feedback selector	0 to 5	5	RW	Txt				US
21.23	Rated field voltage	0 to 500 Vdc	Eur: 360, USA: 300	RW	Uni				US
21.24	Rated field current	0 to FIELD_CURRENT_SET_MAX	Size 1: 2A Eur: 8A, USA: 8A Size: 2A&B Eur: 3A, USA: 20A Size 2C&D Eur: 5A, USA: 20A	RW	Uni		RA	PT	US
21.25	Motor saturation breakpoint 1	0 to 100% of rated flux	50	RW	Uni				US
21.26	Motor saturation breakpoint 2	0 to 100% of rated flux	75	RW	Uni				US
21.27	Motoring current limit	0 to MOTOR2_CURRENT_LIMIT_MAX %	150.0**	RW	Uni		RA		US
21.28	Regen current limit	0 to MOTOR2_CURRENT_LIMIT_MAX %	150.0**	RW	Uni		RA		US
21.29	Symmetrical current limit	0 to MOTOR2_CURRENT_LIMIT_MAX %	150.0**	RW	Uni		RA		US
21.30	Field thermal time constant	0.0 to 3000.0	24.0	RW	Uni				US
21.31	Flux loop P gain	0 to 30.0	3.0	RW	Uni				US
21.32	Flux loop I gain	0 to 300.0	60.0	RW	Uni				US
21.33	field weakening P gain	0 to 300.0	0.4	RW	Uni				US
21.34	field weakening I gain	0 to 300.0	5.0	RW	Uni				US
21.35	Rated field compensation factor	0 to 100%	100%	RW	Uni			PT	US

*The range shown for Pr **21.02** shows the range used for scaling purposes (i.e. for routing to an analog output etc.). Further range restrictions are applied depending on the settings of Pr **1.08** and Pr **1.10**.

These are the maximum default values. If the variable maximum of this parameter (MOTOR2_CURRENT_LIMIT_MAX) gives a lower value with the default value of Motor rated current (Pr **21.07) the default of this parameter is at the lower value.

11.20   Menu 22: Additional Menu 0 set-up

Parameter		Range(⇕)	Default(⇨)	Type					
22.01 to 22.20	Parameter 00.xy setup	Pr **0.00** to **22.99**	Pr **0.00**	RW	Uni			PT	US

11.21   Menu 23: Header selections

Parameter		Range(⇕)	Default(⇨)	Type					
23.01	Sub block headers	0 to 7 (USEr (0), SEt UP (1), diAGnoS (2), triPS (3), SP LOOP (4), SintEr (5), Fb SP (6), inPut (7))		RO	Uni		NC	PT	
23.02	Binary sum of per defined sub block enables	0 to 127		RO	Uni		NC	PT	
23.03 to 23.09	Pre-defined sub block enable	OFF (0) or On (1)	On (1)	RW	Bit				US

11.22 Advanced features

This section gives information on some of the advanced functions of the drive. For additional information see the *Mentor MP Advanced User Guide*.

Reference modes	Pr **1.14** (**SE05, 0.26**), Pr **1.15**
S ramps	Pr **2.06** and Pr **2.07**
Torque modes	Pr **4.08** and Pr **4.11**
Current limit tapers	Pr **4.27**, Pr **4.28**, Pr **4.29**, Pr **4.30**, Pr **4.31**, Pr **4.32**
Start/stop logic modes	Pr **6.04** and Pr **6.40**
Catch a spinning motor	Pr **6.09**
Position modes	Pr **13.10**

11.22.1 Reference modes

1.14 (SE05, 0.26)	Reference selector					
RW	Txt				NC	US
⇕	A1.A2 (0), A1.Pr (2), A2.Pr (2), Pr (3), PAd (4), Prc (5), Pad rEF (6)		⇨		A1.A2 (0)	

1.15	Preset reference selector					
RW	Uni				NC	US
⇕	0 to 9		⇨		0	

Table 11-5 Active reference

Pr 1.14 (SE05, 0.26)	Pr 1.15	Digital input T28		Digital input T29		Pr 1.49	Pr 1.50	Active reference
		State	Function	State	Function			
A1.A2 (0)	0 or 1	0	Local Remote		Jog forward**	1	1	Analog input 1
		1				2	1	Analog input 2
	2 to 8		No function			1 or 2	2 to 8	Preset reference 2 to 8
	9 *	0	Local Remote			1	1	Analog input 1
		1				2	1	Analog input 2
			No function			1 or 2	2 to 8	Preset reference 2 to 8
A1.Pr (1)	0	0	Preset select bit 0	0	Preset select bit 1	1	1	Analog input 1
		1					2	Preset reference 2
		0		1			3	Preset reference 3
		1					4	Preset reference 4
	1		No function		No function		1	Analog input 1
	2 to 8						2 to 8	Preset reference 2 to 8
	9 *						1	Analog input 1
							2 to 8	Preset reference 2 to 8
A2.Pr (2)	0	0	Preset select bit 0	0	Preset select bit 1	2	1	Analog input 2
		1					2	Preset reference 2
		0		1			3	Preset reference 3
		1					4	Preset reference 4
	1		No function		No function		1	Analog input 2
	2 to 8						2 to 8	Preset reference 2 to 8
	9 *						1	Analog input 2
							2 to 8	Preset reference 2 to 8
Pr (3)	0	0	Preset select bit 0	0	Preset select bit 1	3	1	Preset reference 1
		1					2	Preset reference 2
		0		1			3	Preset reference 3
		1					4	Preset reference 4
	1 to 8		No function		No function		1 to 8	Preset reference 1 to 8
	9 *						1 to 8	Preset reference 1 to 8
PAd (4)			No function		No function	4		Keypad reference
Prc (5)			No function		No function	5		Precision reference
Pad rEF (6)			No function		Jog forward**	6		Keypad reference

* Setting Pr **1.15** to 9 enables the Preset reference scan timer. With the scan timer enabled analog 1 and preset references 2 to 8 are selected automatically in turn. Pr **1.16** defines the time between each change.

** Jog forward can only be selected when the drive is in either the ready (rdy), inhibit (inh) or trip states.

Preset references
Preset references 1 to 8 are contained in Pr **1.21** to Pr **1.28**.

Keypad reference
If Keypad reference is selected the drive sequencer is controlled directly by the keypad keys and the keypad reference parameter (Pr **1.17**) is selected. The sequencing bits, Pr **6.30** to Pr **6.34**, and Pr **6.37** have no effect and jog is disabled.

Precision reference
If Precision reference is selected the speed reference is given Pr **1.18** and Pr **1.19**.

11.22.2 S ramps

2.06	**S ramp enable**					
RW	Bit					US
↕	OFF (0) or On (1)		⇨	EUR: OFF (0), USA: On (1)		

Setting this parameter enables the S ramp function.

2.07	**S ramp acceleration limit**					
RW	Bit					US
↕	0.000 to 100.000 s^2/1,000rpm	⇨		3.600		

This parameter defines the maximum rate of change of acceleration/deceleration. If the S ramp is disabled (Pr **2.06** = 0) a linear ramp is used and the time in seconds taken for the ramp output to change by speed (Δω*) is given by:

Speed

$$T_{Ramp} = \Delta\omega^* \times A \text{ / See Pr } \textbf{2.39}$$

Where A is the selected ramp rate in s / See Pr **2.39**

If the S ramp is enabled (Pr **2.06** = 1) then the ramp time is extended as shown in the diagram below.

The time taken in seconds for the ramp output to change by speed (Δω*) is given below. Two cases are given because the total ramp time must be calculated with a different equation depending on whether the acceleration is able to reach the selected ramp rate (A1) or not. If the required change is small the selected ramp rate is not reached and the ramp does not include the central linear ramp region. If the required change is larger the ramp does include the central linear region as shown in the diagram above.

Speed

$$\Delta\omega^*_{linear} = 1000 \times J / A1^2$$

where:

A = selected ramp rate

J = Pr **2.07**

If the required change is less than Δω*$_{linear}$ then T$_{Ramp1}$ should be used, but if the speed change is greater or equal to Δω*$_{linear}$ T$_{Ramp2}$ should be used.

$$T_{Ramp1} = 2 \sqrt{(\Delta\omega^* \times Pr \textbf{ 2.07} / 1000)}$$
$$T_{Ramp2} = (\Delta\omega^* \times A / 1000) + (Pr \textbf{ 2.07} / A)$$

The default values for the ramp rate and S ramp acceleration limit have been chosen such that for the default maximum speed, the curved parts of the S ramp are 25% of the original ramp if S ramp is enabled. Therefore the ramp time is increased by a factor of 1.5.

11.22.3 Torque modes

4.08	**Torque reference**					
RW	Bi					US
↕	±USER_CURRENT_MAX %	⇨		0.00		

4.11	**Torque mode selector**					
RW	Uni					US
↕	0 to 4	⇨		0		

The value of this parameter refers to switches TM0 to TM3 on Menu 4 diagram.

When this parameter is set to 1, 2 or 3 the ramps are not active while the drive is in the run state. When the drive is taken out of the run state, but not disabled, the appropriate stopping mode is used. It is recommended that coast stopping or stopping without ramps are used. However, if ramp stop mode is used the ramp output is pre-loaded with the actual speed at the changeover point to avoid unwanted jumps in the speed reference.

0: Speed control mode
The torque demand is equal to the speed loop output.

1: Torque control
The torque demand is given by the sum of the torque reference and the torque offset, if enabled. The speed is not limited in any way, however, the drive will trip at the overspeed threshold if runaway occurs.

2: Torque control with speed override
The output of the speed loop defines the torque demand, but is limited between 0 and the resultant torque reference (Pr **4.08** + Pr **4.09** (if enabled)). The effect is to produce an operating area as shown below if the final speed demand and the resultant torque reference are both positive. The speed controller will try and accelerate the machine to the final speed demand level with a torque demand defined by the resultant torque reference. However, the speed cannot exceed the reference because the required torque would be negative, and so it would be clamped to zero.

Depending on the sign of the final speed demand and the resultant torque the four areas of operation shown below are possible.

This mode of operation can be used where torque control is required, but

the maximum speed must be limited by the drive.

3: Coiler/uncoiler mode

Positive final speed demand: a positive resultant torque will give torque control with a positive speed limit defined by the final speed demand. A negative resultant torque will give torque control with a negative speed limit of -5rpm.

Negative final speed demand: a negative resultant torque will give torque control with a negative speed limit defined by the final speed demand. A positive resultant torque will give torque control with a positive speed limit of +5rpm.

Example of coiler operation:

This is an example of a coiler operating in the positive direction. The final speed demand is set to a positive value just above the coiler reference speed. If the resultant torque demand is positive the coiler operates with a limited speed, so that if the material breaks the speed does not exceed a level just above the reference. It is also possible to decelerate the coiler with a negative resultant torque demand. The coiler will decelerate down to -5rpm until a stop is applied. The operating area is shown in the following diagram:

Example of uncoiler operation:

This is an example for an uncoiler operating in the positive direction. The final speed demand should be set to a level just above the maximum normal speed. When the resultant torque demand is negative the uncoiler will apply tension and try and rotate at 5rpm in reverse, and so take up any slack. The uncoiler can operate at any positive speed applying tension. If it is necessary to accelerate the uncoiler a positive resultant torque demand is used. The speed will be limited to the final speed demand. The operating area is the same as that for the coiler and is shown below:

4: Speed control with torque feed-forward

The drive operates under speed control, but a torque value may be added to the output of the speed controller. This can be used to improve the regulation of systems where the speed loop gains need to be low for stability.

11.22.4 Current limit tapers

With some motors the commutation limit of the motor requires that the maximum armature current be reduced at higher speeds, the current limit tapers can be used to provide this speed dependent current limit.

4.27	Current taper 1 threshold							
RW	Uni						US	
⇕	0.0 to 10,000.0 rpm		⇨		10,000 rpm			

Sets a threshold value of speed feedback, beyond which Pr **4.31** changes to 1 to indicate that the threshold has been exceeded, and is the starting point for taper 2, if implemented. The current limit reduces, as a function of speed, to an end point defined by Pr **4.29**.

The output of the taper block controls Pr **4.18**.

If only 1 taper is used, it must be taper 1. If both are used, taper 1 must be first. Refer to Figure 11-20.

4.28	Current taper 2 threshold							
RW	Uni						US	
⇕	0.0 to 10,000.0 rpm		⇨		10,000 rpm			

Sets a threshold value of speed feedback, beyond which Pr **4.32** changes to 1 to indicate that the threshold has been exceeded, and is the starting point for taper 2, if implemented. The current limit reduces, as a function of speed, to an end point defined by Pr **4.30**.

The output of the taper block controls Pr **4.18**.

If only one taper is used, it must be taper 1. If both are used, taper 1 must be first. Refer to Figure 11-20.

4.29	Current taper 1 end point							
RW	Uni						US	
⇕	0 to 1000.0 %		⇨		1000.0 %			

Defines the current at the end of taper 1.

4.30	Current taper 2 end point							
RW	Uni						US	
⇕	0 to 1000.0 %		⇨		1000.0 %			

Defines the current at the end of taper 2.

4.31	Taper threshold 1 exceeded							
RO	Bit							
⇕	OFF (0) or On (1)		⇨					

Indicates when speed feedback has exceeded threshold 1.

4.32	Taper threshold 2 exceeded							
RO	Bit							
⇕	OFF (0) or On (1)		⇨					

Indicates when speed feedback has exceeded threshold 2.

Figure 11-20   Current limit versus speed

11.22.5   Start / stop logic modes

6.04	Start / stop logic select					
RW	Uni					US
⇕	0 to 4		⇨		0	

This parameter is provided to allow the user to select several predefined digital input routing macros to control the sequencer. When a value between 0 and 3 is selected the drive processor continuously updates the destination parameters for digital I/O T25, T26 and T27, and the enable sequencer latching bit (Pr **6.40**). When a value of 4 is selected the destination parameters for these digital I/O and Pr **6.40** can be modified by the user.

If Pr **6.04** is changed then a drive reset is required before the function of T25, T26 or T27 will become active.

If Pr **6.04** has been set to a value of 0 to 3, then setting Pr **6.04** to 4 does not automatically reconfigure terminals T25, T26 and T27 to their default functions. To return terminals T25, T26 and T27 to their default functions, one of the following operations should be performed.

- Drive defaults should be restored. See section 5.9 *Restoring parameter defaults* on page 61 for details.
- Manually set Pr **6.04** to 4, Pr **6.40** to 0, Pr **8.22** to 10.33, Pr **8.23** to 6.30, and Pr **8.24** to 6.32.

Figure 11-21   Digital input connections when Pr 6.04 is set to 0 to 3

6.40	**Enable sequencer latching**					
RW	Bit					US
↕	OFF (0) or On (1)		⇨	OFF (0)		

This parameter enables sequencer latching. When sequencer latching is used, a digital input must be used as a run permit or not stop input. The digital input should write to Pr **6.39**. The run permit or not stop input must be made active to allow the drive to run. Making the run permit or not stop input inactive resets the latch and stops the drive.

11.22.6   Catch a spinning motor

6.09	**Catch a spinning motor**					
RW	Uni					US
↕	0 to 1		⇨	1		

When the drive is enabled with this parameter at zero, the post ramp reference (Pr **2.01** (**di03, 0.38**)) starts at zero and ramps to the required reference. When the drive is enabled with this parameter at one, the post ramp reference is set to the motor speed.

11.22.7   Position modes

13.10	**Position controller mode**					
RW	Uni					US
↕	0 to 6		⇨	0		

This parameter is used to set the position controller mode as shown in the following table.

Parameter value	Mode	Feed forward active
0	Position controller disabled	
1	Rigid position control	✓
2	Rigid position control	
3	Non-rigid position control	✓
4	Non-rigid position control	
5	Orientation on stop	
6	Orientation on stop and when drive enabled	

Rigid position control

In rigid position control the position error is always accumulated. This means that, if for example, the slave shaft is slowed down due to excessive load, the target position will eventually be recovered by running at a higher speed when the load is removed.

Non-rigid position control

In non-rigid position control the position loop is only active when the 'At Speed' condition is met (see Pr **3.06** in the *Mentor MP Advanced User Guide*). This allows slippage to occur while the speed error is high.

Velocity feed forward

The position controller can generate a velocity feed forward value from the speed of the reference encoder. The feed-forward value is passed to menu 1, and so ramps may be included if required. Because the position controller only has a proportional gain, it is necessary to use velocity feed-forward to prevent a constant position error that would be proportional to the speed of the reference position.

If for any reason the user wishes to provide the velocity feed forward from a source other than the reference position, the feed forward system can be made inactive, i.e. Pr **13.10** = 2 or 4. The external feed forward can be provided via Menu 1 from any of the frequency/speed references. However, if the feed forward level is not correct a constant position error will exist.

Relative jogging

If relative jogging is enabled the feedback position can be made to move relative to the reference position at the speed defined by Pr **13.17**.

Orientation

If Pr **13.10** is 5 the drive orientates the motor following a stop command. If hold zero speed is enabled (Pr **6.08** = 1) the drive remains in position control when orientation is complete and holds the orientation position. If hold zero speed is not enabled the drive is disabled when orientation is complete.

If Pr **13.10** is 6 the drive orientates the motor following a stop command and whenever the drive is enabled provided that hold zero speed is enabled (Pr **6.08** = 1). This ensures that the spindle is always held in the same position following the drive being enabled.

When orientating from a stop command the drive goes through the following sequence:

1. The motor is decelerated or accelerated to the speed limit programmed in Pr **13.12**, using ramps if these are enabled, in the direction the motor was previously running.

2. When the ramp output reaches the speed set in Pr **13.12**, ramps are disabled and the motor continues to rotate until the position is found to be close to the target position (i.e. within 1/32 of a revolution). At this point the speed demand is set to 0 and the position loop is closed.

3. When the position is within the window defined by Pr **13.14**, the orientation complete indication is given in Pr **13.15**.

The stop mode selected by Pr **6.01** has no effect if orientation is enabled.

12 Technical data

12.1 Drive technical data

12.1.1 Power and current ratings

The power ratings for the 480V, 575V and 690V configurations are shown in Table 12-1, Table 12-2 and Table 12-3.

The continuous current ratings given are for a maximum ambient temperature of 40°C and an altitude of 1000m. For operation at higher temperatures and altitudes derating is required.

The maximum continuous output current rating of the drive should be 'derated' for operation at altitudes above 1000m. The derating is to be 1% derating of rated output current per 100m above 1000m to a maximum derating of 20% at 3000m.

Table 12-1   480V current ratings

Model	AC input current	DC output current		Typical motor power	
	Continuous	Continuous	150% overload	@ 400Vdc	@ 500Vdc
	A	A	A	kW	hp
MP25A4(R)	22	25	37.5	9	15
MP45A4(R)	40	45	67.5	15	27
MP75A4(R)	67	75	112.5	27	45
MP105A4(R)	94	105	157.5	37.5	60
MP155A4(R)	139	155	232.5	56	90
MP210A4(R)	188	210	315	75	125
MP350A4(R)	313	350	525	125	200
MP420A4(R)	376	420	630	150	250
MP550A4(R)	492	550	825	200	300
MP700A4(R)	626	700	1050	250	400
MP825A4(R)	738	825	1237.5	300	500
MP900A4(R)	805	900	1350	340	550
MP1200A4(R)	1073	1200	1800	450	750
MP1850A4(R)	1655	1850	2775	700	1150

Table 12-2   575V current ratings

Model	AC input current	DC output current		Typical motor power (With Vdc = 630V)	
	Continuous	Continuous	150% overload	kW	hp
	A	A	A		
MP25A5(R)	22	25	37.5	14	18
MP45A5(R)	40	45	67.5	25	33
MP75A5(R)	67	75	112.5	42	56
MP105A5(R)	94	105	157.5	58	78
MP155A5(R)	139	155	232.5	88	115
MP210A5(R)	188	210	315	120	160
MP350A5(R)	313	350	525	195	260
MP470A5(R)	420	470*	705	265	355
MP700A5(R)	626	700	1050	395	530
MP825A5(R)	738	825*	1237.5	465	620
MP1200A5(R)	1073	1200	1800	680	910
MP1850A5(R)	1655	1850	2775	1045	1400

* For this rating at 575V, 150% overload time is 20s at 40°C and 30s at 35°C

Table 12-3   690V current ratings

Model	AC input current	DC output Current		Typical motor power (With Vdc = 760V)	
	Continuous	Continuous	150% Overload	kW	hp
	A	A*	A		
MP350A6(R)	313	350	525	240	320
MP470A6(R)	420	470*	705	320	425
MP700A6(R)	626	700	1050	480	640
MP825A6(R)	738	825*	1237.5	650	850
MP1200A6(R)	1073	1200	1800	850	1150
MP1850A6(R)	1655	1850	2775	1300	1750

* For this rating at 690V, 150% overload time is 20s at 40°C and 30s at 35°C

Maximum continuous input current

The values of maximum continuous input current are given to aid the selection of cables and fuses. These values are stated for worst-case conditions.

> **NOTE**
>
> For current ratings above 1850A then parallel connection of the drives is required. However, this function is not implemented on firmware versions V01.05.01 and earlier.

12.1.2 Typical short-term overload limits

The maximum percentage overload limit changes depending on the selected motor

Variations in motor rated current will result in changes in the maximum possible overload as detailed in the *Mentor MP Advanced User Guide*.

Figure 12-1 can be used to determine the maximum overload duration available for overloads between 100% and 150%. For example the maximum overload available for a period of 60 seconds is 124%.

Figure 12-1   Maximum overload duration available

> **NOTE**
>
> Overload of 150% for 30s is available up to a maximum of 10 repetitions per hour..

12.1.3   Drive derating for extended ambient operation

Figure 12-2   Mentor MP size 1A derating for extended ambient operation

Figure 12-3   Mentor MP size 1B derating for extended ambient operation

Figure 12-4   Mentor MP size 2A derating for extended ambient operation

Figure 12-5   Mentor MP size 2B derating for extended ambient operation

Figure 12-6   Mentor MP Size 2C and 2D derating for extended ambient operation

The derating graphs show the derating required for worst-case conditions.

12.1.4 Power dissipation

The table below shows the maximum drive losses, assuming high output current ripple content.

Table 12-4 Drive losses

Model	Loss @ 40°C W	Loss @ 50°C W	Loss @ 55°C W
MP25A4(R) MP25A5(R)	125		91
MP45A4(R) MP45A5(R)	168	139	117
MP75A4(R) MP75A5(R)	219	194	183
MP105A4(R) MP105A5(R)	274		
MP155A4(R) MP155A5(R)	400		310
MP210A4(R) MP210A5(R)	561	456	310
MP350A4(R)	954		
MP350A5(R) MP350A6(R)	1045		
MP420A4(R)	1154		
MP470A5(R) MP470A6(R)	1546	1268	1162
MP550A4(R)	1568		1354
MP700A4(R)	1663		
MP825A4(R)			
MP700A5(R) MP700A6(R)	1955		1795
MP825A4(R)	2160	1909	1751
MP825A5(R) MP825A6(R)	2381	2004	1795
MP900A4(R)	2220	1908	1751
MP1200A4(R) MP1200A5(R) MP1200A6(R)	3635	3660	
MP1850A4(R) MP1850A5(R) MP1850A6(R)	5203	4418	4139

12.1.5 AC Supply requirements

The standard drive is rated for a nominal supply voltage up to 480Vrms.

An optional rating of 575Vrms is available for size 1 drives.

An optional rating of 575Vrms and 690Vrms is available for size 2 drives.

> ⚠️ **WARNING** Grounded delta supplies exceeding 575V are not permitted for drives up to and including 210A. Grounded delta supplies exceeding 600V are not permitted for drives rated 350A and above.

12.1.6 Supply types

Drives rated for supply voltages of up to 575V (rated up to 210A) and 600V (350A and above), are suitable for use with any supply type i.e. TN-S, TN-C-S, TT, IT with grounding at any potential i.e neutral, centre or corner ("Grounded delta").

Grounded delta supplies >575V are not permitted for drives rated up to and including 210A. Grounded delta supplies >600V are not permitted for drives rated 350A and above.

12.1.7 Main AC supply (L1, L2, L3)

Table 12-5 Three phase AC supply

Specification	Product voltage variant		
	480V	575V	690V
Maximum nominal supply	480V	575V	690V
Tolerance	+10%		
Minimum nominal supply	24V	500V	
Tolerance	-20%	-10%	

12.1.8 Auxiliary AC supply

Table 12-6 Line to line supply

Specification	Value
Maximum nominal supply	480V
Tolerance	+10%
Minimum nominal supply	208V
Tolerance	-10%

12.1.9 Line reactors

The Mentor MP, in common with all naturally commutated thyristor drives, causes voltage notches at the input supply terminals. In order to avoid disturbance to other equipment using the same supply, the addition of external line inductance is strongly recommended in order to restrict the depth of the notches imposed on the shared supply. This is generally not necessary where a dedicated transformer is used to supply the drive.

The following recommendations for added line inductance, have been calculated based on the power drive systems standard: EN 61800-3:2004 "Adjustable speed electrical power drive systems – Part 3: EMC requirements and specific test methods".

Table 12-7 Minimum required line inductance for a typical application (50% ripple content)

Drive rated current A	System voltage				Typical current rating A	Maximum current rating A
	400V μH	480V μH	575V μH	690V μH		
25	220	260	320		21	22
45	220	260	320		38	40
75	220	260	320		63	67
105	220	260	320		88	94
155	160	190	230		130	139
210	120	140	170		176	188
350	71	85	110	120	293	313
420	59	71			351	375
470			80	91	393	420
550	45	54			460	492
700	36	43	53	61	586	626
825			45	52	690	738
900	28	33			753	805
1200	21	25	31	36	1004	1073
1850	18	23	29	32	1548	1655

NOTE

1. The above assumes the supply has 1.5% impedance.
2. Assumes a minimum supply rating of 5kA and a maximum rating of 60kA.

12.1.10 Temperature, humidity and cooling method

Ambient temperature operating range:

0°C to 55°C (32°F to 131°F).
Output current derating must be applied at ambient temperatures >40°C (104°F).

Minimum temperature at power-up:

The drive will power up at -15°C (5°F)

Cooling method:

MP25Ax(R) and MP45Ax(R) = Natural convection.

MP75Ax(R) upwards = Forced cooling.

Maximum humidity:

The Mentor MP Product range can operate in environments up to 90% relative humidity at 50°C.

12.1.11 Storage

-40°C (-40°F) to +55°C (131°F) for long term storage, or to +70°C (158°F) for short term storage.

12.1.12 Altitude

Altitude range: 0 to 3,000m (9,900 ft), subject to the following conditions:

1,000m to 3,000m (3,300 ft to 9,900 ft) above sea level: derate the maximum output current from the specified figure by 1% per 100m (330 ft) above 1,000m (3,300 ft)

For example at 3,000m (9,900ft) the output current of the drive would have to be derated by 20%.

12.1.13 IP rating

The Mentor MP range of drives have the following Ingress Protection rating:

Table 12-8 IP rating

Frame size	IP Rating
1A	IP20 Protection against medium size foreign bodies ∅ > 12mm (finger) No protection against ingress of water
1B	
2A	IP10 Protection against large foreign bodies ∅ > 50mm (large area contact with hand) No protection against ingress of water
2B	
2C	IP00 No protection against contact, ingress of foreign bodies or ingress of water
2D	

⚠️ **WARNING**

IP rating

It is the installer's responsibility to ensure that any enclosure which allows access to drives from frame sizes 2A to 2D while the product is energized, provides protection against contact and ingress to the requirements of IP20.

The IP rating of a product is a measure of protection against contact and ingress of foreign bodies and water. It is stated as IP XX, where the two digits (XX) indicate the degree of protection.

12.1.14 Corrosive gasses

Concentrations of corrosive gases must not exceed the levels given in:
- Table A2 of EN 50178:1998
- Class 3C2 of IEC 60721-3-3

This corresponds to the levels typical of urban areas with industrial activities and/or heavy traffic, but not in the immediate neighborhood of industrial sources with chemical emissions.

12.1.15 RoHS compliance

Mentor MP meets EU directive 2002/95/EC for RoHS compliance.

12.1.16 Vibration

Maximum recommended continuous vibration level 0.14 g r.m.s. broad-band 5 to 200 Hz.

NOTE

This is the limit for broad-band (random) vibration. Narrow-band vibration at this level which coincides with a structural resonance could result in premature failure.

Bump test

Testing in each of three mutually perpendicular axes in turn.
Referenced standard:IEC 60068-2-29: Test Eb:
Severity: 18g, 6ms, half sine
No. of Bumps: 600 (100 in each direction of each axis)

Random vibration test

Testing in each of three mutually perpendicular axes in turn.
Referenced standard:IEC 60068-2-64: Test Fh:
Severity: 1.0 m²/s³ (0.01 g²/Hz) ASD from 5 to 20 Hz
            -3 dB/octave from 20 to 200 Hz
Duration: 30 minutes in each of 3 mutually perpendicular axes.

Sinusoidal vibration test

Testing in each of three mutually perpendicular axes in turn.
Referenced standard: IEC 60068-2-6: Test Fc:
Frequency range: 5 to 500 Hz
Severity: 3.5 mm peak displacement from 5 to 9 Hz
              10 m/s² peak acceleration from 9 to 200 Hz
              15 m/s² peak acceleration from 200 to 500 Hz
Sweep rate: 1 octave/minute
Duration: 15 minutes in each of 3 mutually perpendicular axes.

EN 61800-5-1:2007, Section 5.2.6.4. referring to IEC 60068-2-6
Frequency range: 10-150Hz
Amplitude: 10-57Hz @ 0.075mm pk
                     57-150Hz @ 1g pk
Sweep rate: 1 octave/minute
Duration: 10 sweep cycles per axes in each of 3 mutually perpendicular axes

Shock test

BS EN 60068-2-27, Test Ea
Pulse shape: half-sine
Severity: 15g pk acceleration, 11ms pulse duration
No of shocks: 3 in each direction of 3 mutually perpendicular axes (total of 18)

12.1.17 Start up time

This is the time taken from the moment of applying power to the drive, to the drive being ready to run a motor:

All sizes: 2s

12.1.18 Output speed range

Speed range: 0 to 10,000rpm

12.1.19 Accuracy

Accuracy in estimated speed mode: Typically 5 to 10%.

Other modes are dependent on feedback device used.

12.1.20 Acoustic noise

The heatsink fan generates the majority of the acoustic noise produced by the drive. The heatsink fan on the Mentor MP is a single speed fan.

Table 12-9 gives the acoustic noise produced by the drive.

Table 12-9 Acoustic noise data

Model			Frame Size	SPL at 1m (dBA)
MP25A4(R)	MP25A5(R)		1A	No fans installed
MP45A4(R)	MP45A5(R)			
MP75A4(R)	MP75A5(R)			43
MP105A4(R)	MP105A5(R)		1B	56
MP155A4(R)	MP155A5(R)			
MP210A4(R)	MP210A5(R)			
MP350A4(R)	MP350A5(R)	MP350A6(R)	2A	68
MP420A4(R)	MP470A5(R)	MP470A6(R)		
MP550A4(R)				
MP700A4(R)	MP700A5(R)	MP700A6(R)	2B	
MP825A4(R)	MP825A5(R)	MP825A6(R)		
MP900A4(R)				
MP1200A4	MP1200A5	MP1200A6	2C	67*
MP1850A4	MP1850A5	MP1850A6		
MP1200A4R	MP1200A5R	MP1200A6R	2D	
MP1850A4R	MP1850A5R	MP1850A6R		

NOTE

* The acoustic noise figure for frame sizes 2C and 2D has been taken with the bottom right angle ducting removed.

12.1.21 Overall dimensions

Refer to section 3.4 *Mounting method* on page 17.

12.1.22 Weights

Table 12-10 Overall drive weights

Model			Frame size	kg	lb
MP25A4	MP25A5		1A	10	22
MP45A4	MP45A5				
MP75A4	MP75A5			10.1	22.3
MP25A4R	MP25A5R			10.2	22.5
MP45A4R	MP45A5R				
MP75A4R	MP75A5R			10.5	23.1
MP105A4	MP105A5		1B	12.6	27.8
MP155A4	MP155A5				
MP210A4	MP210A5				
MP105A4R	MP105A5R			13.0	28.7
MP155A4R	MP155A5R				
MP210A4R	MP210A5R				
MP350A4	MP350A5	MP350A6	2A	35	77.2
MP420A4					
	MP470A5	MP470A6			
MP550A4					
MP350A4R	MP350A5R	MP350A6R		38	83.8
MP420A4R					
	MP470A5R	MP470A6R			
MP550A4R					
MP700A4	MP700A5	MP700A6	2B	41	90.4
MP825A4	MP825A5	MP825A6			
MP900A4					
MP700A4R	MP700A5R	MP700A6R		46	101.4
MP825A4R	MP825A5R	MP825A6R			
MP900A4R					
MP1200A4	MP1200A5	MP1200A6	2C	100	220.5
MP1850A4	MP1850A5	MP1850A6			
MP1200A4R	MP1200A5R	MP1200A6R	2D	138	304.2
MP1850A4R	MP1850A5R	MP1850A6R			

12.2 Cable and fuse size ratings

⚠ WARNING

The selection of the correct fuse is essential to ensure the safety of the installation

Maximum continuous input currents are given in section 2.1 *Ratings* on page 6 to aid the selection of fuses and cabling. The maximum input current is dependent on the ripple content of the output current. A value of 100% ripple has been assumed for the given ratings.

The cable sizing selected when installing a Mentor MP must comply with the local wiring regulations. The information provided in this section is provided for guidance purposes only.

The power terminals on Mentor MP frame size 1 drives have been designed to accommodate a maximum cable size of 150mm^2 (350kcmil) with a temperature of 90°C (194°F).

The power terminals on Mentor MP frame size 2A drives have been designed to accommodate a maximum cable size of 2 x 150mm^2 (2 x 350kcmil) with a temperature of 75°C (167°F).

The power terminals on Mentor MP frame size 2B drives have been designed to accommodate 2 x 240mm^2 with a temperature of 90°C (194°F). The use of cables sized using the US national electrical code as shown in Table 12-13 requires the use of a terminal adaptor.

The power terminals on Mentor MP frame size 2C and 2D drives have been designed for use with busbars. The drive can be used with cables as shown in Table 12-13 with the use of a terminal adaptor.

The actual cable size depends on a number of factors including:

- Actual maximum continuous current
- Ambient temperature
- Cable support, method and grouping
- Cable voltage drop

In applications where the motor used is of a reduced rating, the cable sizing selected can be appropriate for that motor. To protect the motor and the output cabling the drive must be programmed with the correct motor rated current.

NOTE

When using reduced cable sizes, the branch circuit protection fuse rating needs to be reduced in line with the cable size selected.

The following table shows typical cable sizes based on USA and International standards, assuming 3 conductors per raceway/conduit, an ambient temperature of 40°C (104°F) and applications with high output current ripple content.

Table 12-11 Typical cable sizes for size 1 drives

Model		IEC 60364-5-52[1]		UL508C/NEC[2]	
		Input	Output	Input	Output
MP25A4(R)	MP25A5(R)	2.5mm^2	4mm^2	8 AWG	8 AWG
MP45A4(R)	MP45A5(R)	10mm^2	10mm^2	4 AWG	4 AWG
MP75A4(R)	MP75A5(R)	16mm^2	25mm^2	1 AWG	1/0 AWG
MP105A4(R)	MP105A5(R)	25mm^2	35mm^2	1/0 AWG	1/0 AWG
MP155A4(R)	MP155A5(R)	50mm^2	70mm^2	3/0 AWG	4/0 AWG
MP210A4(R)	MP210A5(R)	95mm^2	95mm^2	300kcmil	350kcmil

NOTE

1. The maximum cable size is defined by the power terminal housing using 90°C (194°F) rated cables as per Table A.52-5 of the standard.
2. Assumes the use of 75°C rated cables, as per Table 310.16 of the National Electrical Code.

The use of higher temperature rated cable would allow a reduction on the minimum recommended cable size for Mentor MP shown above. For high temperature cable sizing, please contact the supplier of the drive.

Table 12-12   Auxiliary wiring for size 1 drives

Frame size	Maximum input current	Continuous output current	IEC 60364-5-52 Table A52-4 Column B2		UL 508C	
			Column B2 derated by 0,87 of PVC at 40			
			E1, E3 size	F+, F- , L11 & L12 size	E1, E3 size	F+, F- , L11 & L12 size
	A	**A**	**mm²**	**mm²**	**mm²**	**mm²**
1	13	8	2.5	1.5	14 AWG	14 AWG

Notes for IEC 60364:

IEC 60364-5-52 use installation method B2, Table A.52-4 for three loaded conductors, PVC insulation 30°C and apply derating factor for 40°C from Table A.52-14 (0.87 for PVC).

Notes for UL508C:

Either 60°C or 75°C cable can be used. Ampacities as per table 40.3 as described in the UL508C standard.

Table 12-13   Typical cable sizes for size 2 drives

Model			Maximum input current	Continuous output current	IEC 60364-5-52 Table A52-12 Column 5 derated by 0.91 for 40°C XLPE cables (IEC 60364-5-52 table A52-14) and 0.77 for cables bunching (IEC 60364-5-52 table A52-17 item 4)		US National Electrical Code	
					90°C cables at 40°C ambient		75°C cable at 40°C ambient	
			A	**A**	Input size mm²	Output size mm²	Input cables Kcmil	Output cables Kcmil
MP350A4(R)	MP350A5(R)	MP350A6(R)	313	350	120	150	350	400
MP420A4(R)			375	420	150	185	400	500
	MP470A5(R)	MP470A6(R)	420	470	185	240	500	600
MP550A4(R)			492	550	300	2 x 185	2 x 300	2 x 350
MP700A4(R)	MP700A5(R)	MP700A6(R)	626	700	2 x 150	2 x 150	2 x 500	2 x 600
MP825A4(R)	MP825A5(R)	MP825A6(R)	738	825	2 x 185	2 x 240	2 x 600	3 x 350
MP900A4(R)			805	900	2 x 185	2 x 240	3 x 350	3 x 400
MP1200A4(R)	MP1200A5(R)	MP1200A6(R)	1073	1200	2 x 300	3 x 240	3 x 600	4 x 400
MP1850A4(R)	MP1850A5(R)	MP1850A6(R)	1655	1850	4 x 240	4 x 300	*	*

* Values are beyond the mechanical design of the drive. At this power level it may be prudent to consider bus-bars.

Notes for IEC 60364:

> **NOTE**

1. IEC 60364-5-52 Table A 52-12 F method column 5 = Single core cable in free air.
2. IEC 60364-5-52 table A52-14 correction factor for ambient air temperature others than 30°C.
3. IEC 60364-5-52 table A52-17 item 4 correction factor for groups of more than one circuit or more than one multi-core cable placed on a single layer on a perforated tray.

> **NOTE**

Notes for US National Electrical Code:
1. Table 310.17 allowable ampacities of single-insulated conducted rated 0 through 2000V in free air, based on ambient air temperature of 30°C (87°F).
2. Derating factor of 0.88 is applied for 40°C to the 75°C cable column. Table 310.17 is based on 30°C (86°F) ambient air temperature.
3. NEC 2005 edition Table 310.15(B)(2)(a) shows the adjustment factors for more than three current-carrying conductors in a race way or cable, for 4-6 current-carrying conductors 0.80 derating factor is applied.

Table 12-14   Auxiliary wiring for size 2 drives

Frame size	Maximum input current	Continuous output current	IEC 60364-5-52 Table A52-4 Column B2		UL 508C	
			Column B2 derated by 0,87 of PVC at 40			
			E1, E3 size	F+, F- , L11 & L12 size	E1, E3 size	F+, F- , L11 & L12 size
	A	**A**	**mm²**	**mm²**	**mm²**	**mm²**
2	23	20	6	4	10 AWG	10 AWG

Notes for IEC 60364:

IEC 60364-5-52 use installation method B2, Table A.52-4 for three loaded conductors, PVC insulation 30°C and apply derating factor for 40°C from Table A.52-14 (0.87 for PVC).

Notes for UL508C: Either 60°C or 75°C cable can be used. Ampacities as per table 40.3 as described in the UL508C standard.

12.2.1 Ferraz Shawmut fuses

Ferraz Shawmut fuses are recommended for the Mentor MP.

Table 12-15 Ferraz Shawmut semiconductor fusing for size 1 drives

Model	International			USA		
	Description	Catalogue number	Ref number	Description	Catalogue number	Ref number
Field fuses	10 x 38mm Ferrule	FR10GB69V12.5	H330011	10 x 38mm Ferrule	FR10GB69V12.5	H330011
MP25A4	22 x 58mm Ferrule	FR22GC69V32	A220915	A50QS Series American Round Fuse	A50QS60-4	A218937
MP25A5						
MP45A4		FR22GC69V63	X220912	A50QS Series American Round Fuse	A50QS80-4	L201513
MP45A5						
MP75A4		FR22GC69V100	W220911	A50QS Series American Round Fuse	A50QS125-4	K218417
MP75A5						
MP25A4R		FR22GC69V32	A220915	A70QS Series American Round Fuse	A70QS60-4	H219473
MP25A5R						
MP45A4R		FR22GC69V63	X220912	A70QS Series American Round Fuse	A70QS80-4	X212816
MP45A5R						
MP75A4R		FR22GC69V100	W220911	A70QS Series American Round Fuse	A70QS125-4	Q216375
MP75A5R						
MP105A4	Size 30 Square Body Fuse	PC30UD69V160EF	M300092	A50QS Series American Round Fuse	A50QS175-4	A222663
MP105A5						
MP155A4		PC30UD69V200EF	N300093	A50QS Series American Round Fuse	A50QS250-4	W211251
MP155A5						
MP210A4		PC30UD69V315EF	Q300095	A50QS Series American Round Fuse	A50QS350-4	T215343
MP210A5						
MP105A4R	Size 70 Square Body Fuse	PC70UD13C160EF	T300604	A70QS Series American Round Fuse	A70QS175-4	A223192
MP105A5R						
MP155A4R		PC70UD13C200EF	V300605	A70QS Series American Round Fuse	A70QS250-4	L217406
MP155A5R						
MP210A4R		PC70UD12C280EF	L300712	A70QS Series American Round Fuse	A70QS350-4	M211266
MP210A5R						

NOTE

A50QS series are only rated up to 500Vac.

Table 12-16 Ferraz Shawmut branch circuit protection fusing for size 1 drives

Model		International			USA
		Description	Catalogue number	Ref number	Catalogue number
Auxiliary		21 x 57mm Cylindrical	HSJ15	D235868	AJT10
MP25A4	MP25A5	22 x 58mm Ferrule	FR22GG69V25	N212072	AJT30
MP45A4	MP45A5		FR22GG69V50	P214626	AJT45
MP75A4	MP75A5		FR22GG69V80	Q217180	AJT70
MP25A4R	MP25A5R		FR22GG69V25	N212072	AJT30
MP45A4R	MP45A5R		FR22GG69V50	P214626	AJT45
MP75A4R	MP75A5R		FR22GG69V80	Q217180	AJT70
MP105A4	MP105A5	NH 00 Knife Blade	NH00GG69V100	B228460	AJT125
MP155A4	MP155A5	NH 1 Knife Blade	NH1GG69V160	F228487	AJT175
MP210A4	MP210A5		NH1GG69V200	G228488	AJT225
MP105A4R	MP105A5R	NH 00 Knife Blade	NH00GG69V100	B228460	AJT125
MP155A4R	MP155A5R	NH 1 Knife Blade	NH1GG69V160	F228487	AJT175
MP210A4R	MP210A5R		NH1GG69V200	G228488	AJT225

Table 12-17   Ferraz Shawmut DC protection fusing for size 1 drives

Model	International			USA		
	Description	Catalogue number	Ref number	Description	Catalogue number	Ref number
MP25A4R	20 x 127mm Cylindrical	FD20GB100V32T	F089498	A70QS Series American Round Fuse	A70QS60-4	H219473
MP25A5R						
MP45A4R	36 x 127mm Cylindrical	FD36GC100V80T	A083651	A70QS Series American Round Fuse	A70QS80-4	X212816
MP45A5R						
MP75A4R	20 x 127mm Cylindrical	FD20GC100V63T x 2 connected in parallel.	F083656 x 2 connected in parallel.	A70QS Series American Round Fuse	A70QS125-4	Q216375
MP75A5R						
MP105A4R	Size 120 Square Body	D120GC75V160TF	R085253	A70QS Series American Round Fuse	A70QS175-4	A223192
MP105A5R						
MP155A4R	Size 121 Square Body	D121GC75V250TF	Q085252	A70QS Series American Round Fuse	A70QS250-4	L217406
MP155A5R						
MP210A4R	Size 122 Square Body	D122GC75V315TF	M085249	A70QS Series American Round Fuse	A70QS350-4	M211266
MP210A5R						

NOTE

DC fusing is required on four quadrant (R) drives only.

Table 12-18   Ferraz Shawmut Semiconductor fusing alternatives for size 1 drives

Model		Description	German DIN80 Blade		German DIN110 Blade Style		American Blade Style		French Flat End Style	
			Catalogue number	Ref number	Catalogue number	Ref number	Catalogue number	Ref number	Catalogue number	Ref number
MP105A4	MP105A5	Size 30 Square Body	PC30UD69V160A	J300112	PC30UD69V160D1A	V300122	A070UD30LI160	R300142	PC30UD69V125TF	V300053
MP155A4	MP155A5		PC30UD69V200A	K300113	PC30UD69V200D1A	W300123	A070UD30LI200	S300143	PC30UD69V200TF	X300055
MP210A4R	MP210A5R		PC30UD69V315A	M300115	PC30UD69V315D1A	Y300125	A070UD30LI315	V300145	PC30UD69V250TF	Y300056
MP105A4R	MP105A5R	Size 70 Square Body			PC70UD13C160D1A	Z300540	A130UD70LI160	A300656	PC70UD13C160TF	R300487
MP155A4R	MP155A5R				PC70UD13C200D1A	A300541	A130UD70LI200	B300657	PC70UD13C200TF	S300488
MP210A4R	MP210A5R				PC70UD12C280D1A	J300710	A130UD70LI315	Q300716	PC70UD12C280TF	N300714

Model		Description	NH Style	
			Catalogue number	Ref number
MP105A4	MP105A5	Size 00 Square body	NH00UD69V160PV	K320169
MP155A4	MP155A5		NH00UD69V200PV	M320171
MP210A4R	MP210A5R		NH00UD69V315PV	W320179

Table 12-19 Ferraz Shawmut semiconductor fusing for size 2 drives

Model	International			USA		
	Description	Catalogue number	Ref number	Description	Catalogue number	Ref number
Field fuses	10 x 38mm Ferrule	FR10GB69V25	L330014	10 x 38mm Ferrule	FR10GB69V25	L330014
MP350A4	Square Body Fuses	PC30UD69V500TF	W300399	American Round Fuses Form 101 Range A70QS	A50QS450-4 A7OQS450-4	EQ16871 F214848
MP350A4R		PC71UD11V500TF	F300523		A7OQS450-4	F214848
MP350A5 MP350A6		PC31UD69V500TF	T300006		A70QS450	F214848
MP350A5R MP350A6R		PC72UD13C500TF	D300498			
MP420A4		PC32UD69V630TF	M300069		A50QS600-4 A70QS600-4	Q219457 Y219993
MP420A4R		PC272UD13C630TF	W300721		A70QS600-4	Y219993
MP470A5 MP470A6 MP470A5R MP470A6R		PC272UD13C700TF	X300722		2 x A70QS400 in parallel	J214345 (x2)
MP550A4		PC33UD69V700TF	Y300079		A50QS700-4 A70QS700-4	N223181 E202772
MP550A4R		PC272UD13C700TF	X300722		A70QS700-4	E202772
MP700A4		PC32UD69V1000TF	S300074		A50QS900-4 2 x A70QS500-4 in parallel	R212282 A218431 (x2)
MP700A4R		PC72UD10C900TF	G300869		2 x A70QS500 in parallel.	A218431 (x2)
MP700A5 MP700A6		PC32UD69V1000TF	S300074			
MP700A5R MP700A6R		PC73UD12C900TF	T300512			
MP825A4		PC32UD69V1100TF	M300759		A50QS1200-4 2 x A70QS600-4 in parallel	C217904 Y219993 (x2)
MP825A5 MP825A6		PC33UD69V1100TF	C300083		2 x A7OQS600-4 in parallel	Y219993 (x2)
MP825A4R MP825A5R MP825A6R		PC73UD95V800TFB	W300514			
MP900A4		PC33UD69V1250TF	D300084		A50QS1200-4 2 x A70QS600-4 in parallel	C217904 Y219993 (x2)
MP900A4R		PC73UD95V800TFB	W300514		2 x A70QS600-4 in parallel	Y219993 (x2)
MP1200A4		PC33UD60V1600TF	Z300586		2 x A5OQS800-4 in parallel. 2 x A70QS800-4 in parallel	C202287 (x2) Z213830 (x2)
MP1200A4R		PC273UD11C16CTF	J302228		2 x A70QS800-4 in parallel	Z213830 (x2)
MP1200A5 MP1200A6		PC232UD69V16CTD	W300215			
MP1200A5R MP1200A6R		PC273UD11C16CTF	J302228			
MP1850A4		**7,5 URD 44 PPSAF 2200	**K235184		2 x A5OQS1000-4 in parallel. *3 x A7OQS700-4 in parallel	B217391 (x2) *E202772 (x3)
MP1850A4R					*3 x A7OQS700-4 in parallel	*E202772 (x3)
MP1850A5 MP1850A6						
MP1850A5R MP1850A6R						

NOTE

A50QS series are only rated up to 500Vac.

*Application overload limited to infrequent overloads to avoid fuse wear out

**Fuse limits applications to those operating at rated current. No cyclic overloads permitted.

Table 12-20 Ferraz Shawmut branch circuit protection fusing for size 2 drives

Model		International			USA		
		Description	**Catalogue number**	**Ref number**	**Description**	**Catalogue number**	**Ref number**
Auxiliary		25A 600Vac High Speed Class J	HSJ205	F235870	25A 600Vac High Speed Class J	AJT20R	X21160J
MP350A4(R)	MP350A5(R) MP350A6(R)	General purpose IEC (square body)	NH2GG69V355	Y228503	General purpose US (round body)	A6D400R	B216776
MP420A4(R)			NH3GG69V400	D228508		A6D500R	P217294
MP470A5(R) MP470A6(R)			NH4GG69V630-8 NH4AGG69V630-8	E215537 W222107		A6D600R	T217804
MP550A4 (R)			NH4GG69V630-8 NH4AGG69V630-8	E215537 W222107			
MP700A4(R)	MP700A5(R) MP700A6(R)		NH4GG69V800-8 NH4AGG69V800-8	K216554 M222858		A4BQ800	Z219373
MP825A4(R) MP825A5(R) MP825A6(R)			NH4GG69V800-8 NH4AGG69V800-8	K216554 M222858			
MP900A4R)		General purpose IEC (round body)	MF76GG69V1250	E302753		A4BQ1000	P216282
MP1200A4(R)	MP1200A5(R) MP1200A6(R)					A4BQ1200	R216790
MP1850A4(R)	MP1850A5(R) MP1850A6(R)		MF114GG69V2000	G302755		A4BQ2000	B223101

NOTE

USA fuses are only rated up to 600Vac.

Table 12-21 Ferraz Shawmut DC protection fusing for size 2 drives

Model	International			USA		
	Description	**Catalogue number**	**Ref number**	**Description**	**Catalogue number**	**Ref number**
MP350A4R	Square Body fuse	D123GB75V630TF	C098557	American round fuse	A70QS600-4	Y219993
MP350A5R MP350A6R					A100P600-4	A217373
MP420A4R		D123GB75V800TF	J220946		A70QS800-4	Z213830
MP470A5R MP470A6R		D2122GD75V900TF	T220955	American round fuses 2 in parallel	A100P1000-4 (x2)	Y217371 (x2)
MP550A4R					A70QS450-4 (x2)	F214848 (x2)
MP700A4R					A70QS600-4 (x2)	Y219993 (x2)
MP700A5R MP700A6R		D2123GB75V12CTF	D098558	American round fuse	A100P1200-4	N218397
MP825A4R				American round fuses 2 in parallel	A70QS800-4 (x2)	Z213830 (x2)
MP825A5R MP825A6R				American round fuse	A100P1200-4	N218397
MP900A4R		D2123GB75V14CTF	B090483	American round fuses 3 in parallel	A70QS600-4 (x3)	Y219993 (x3)
MP1200A4R	Square Body fuses 3 in parallel	PC73UD13C630TF (x3)	Q300509 (x3)	American round fuses 3 in parallel	A70QS700-4 (x3)	E202772 (x3)
MP1200A5R MP1200A6R					A100P700-4 (x3)	T223163 (x3)
MP1850A4R	Square Body fuses 4 in parallel	PC73UD13C700TF (x4)	R300510 (x4)	American round fuses 5 in parallel	A70QS600-4 (x5)	Y219993 (x5)
MP1850A5R MP1850A6R					A100P600-4 (x5)	A217373 (x5)

NOTE

The use of the A100P series fuses is limited to applications with L/R time constants of 30ms or less.

DC fusing is only required on four quadrant (R) drives.

12.2.2 Alternative fusing

Cooper Bussmann or Siba fuses are an acceptable alternative.

Table 12-22 Cooper Bussmann semiconductor fusing for size 1 two quadrant drives

Model		Fuse type	Rating V	Rating A	Catalogue number
Auxiliary		10.3 x 38mm ferrule	600Vac	12	FWC-12A10F
MP25A4	MP25A5	ET Type BS88 fuse	690Vac	40	40ET
MP45A4	MP45A5	FE Type BS88 fuse		80	80FE
MP75A4	MP75A5	EET Type BS88 fuse		140	140EET
MP105A4	MP105A5	FEE Type BS88 fuse		160	160FEE
MP155A4	MP155A5	FM Type BS88 fuse		250	250FM
MP210A4	MP210A5	FMM Type BS88 fuse		400	400FMM

Table 12-23 Cooper Bussmann North American alternative semiconductor fusing for size 1 two quadrant 480V drives only

Model	Fuse type	Rating V	Rating A	Catalogue number
MP25A4	FWH series American round fuse	500Vac	40	FWH-40
MP45A4			70	FWH-70
MP75A4			125	FWH-125
MP105A4			175	FWH-175
MP155A4			250	FWH-250
MP210A4			350	FWH-350

Table 12-24 Cooper Bussmann North American alternative semiconductor fusing for size 1 two quadrant 480V and 575V drives

Model		Fuse type	Rating V	Rating A	Catalogue number
MP25A4	MP25A5	FWP series American round fuse	700Vac	40	FWP-40
MP45A4	MP45A5			70	FWP-70
MP75A4	MP75A5			125	FWP-125
MP105A4	MP105A5			175	FWP-175
MP155A4	MP155A5			250	FWP-250
MP210A4	MP210A5			300	FWP-300

Table 12-25 Cooper Bussmann North American alternative semiconductor fusing for size 1 two and four quadrant drives

Model		Fuse type	Rating V	Rating A	Catalogue number
MP25A4(R)	MP25A5(R)	FWJ series American round fuse	1000Vac	40	FWJ-40
MP45A4(R)	MP45A5(R)			70	FWJ-70
MP75A4(R)	MP75A5(R)			125	FWJ-125
MP105A4(R)	MP105A5(R)			175	FWJ-175
MP155A4(R)	MP155A5(R)			250	FWJ-250
MP210A4(R)	MP210A5(R)			350	FWJ-350

Table 12-26 Cooper Bussmann branch circuit protection fusing for 480V and 575V size 1 drives

Model		Fuse type	Rating V	Rating A	Catalogue number
Auxiliary		10.3 x 38mm ferrule	600Vac	12	LP-CC-12
MP25A4(R)	MP25A5(R)	26.9 x 60.5mm ferrule		30	LPJ-30SP
MP45A4(R)	MP45A5(R)			60	LPJ-60SP
MP75A4(R)	MP75A5(R)	Cylindrical bolt-in type fuse		80	LPJ-80SP
MP105A4(R)	MP105A5(R)			110	LPJ-110SP
MP155A4(R)	MP155A5(R)			175	LPJ-175SP
MP210A4(R)	MP210A5(R)			225	LPJ-225SP

Table 12-27   Cooper Bussmann DC protection fusing for 480V and 575V size 1 drives

Model	Fuse type	Rating V	Rating A	Catalogue number
MP25A4R	FWJ series American round fuse	1000Vac	40	FWJ-40A
MP25A5R	AC fuse provides protection			
MP45A4R	FWJ series American round fuse	1000Vac	70	FWJ-70A
MP45A5R	AC fuse provides protection			
MP75A4R	FWJ series American round fuse	1000Vac	125	FWJ-125A
MP75A5R	AC fuse provides protection			
MP105A4R	FWJ series American round fuse	1000Vac	175	FWJ-175A
MP105A5R	AC fuse provides protection			
MP155A4R	FWJ series American round fuse	1000Vac	250	FWJ-250A
MP155A5R	AC fuse provides protection			
MP210A4R	FWJ series American round fuse	1000Vac	350	FWJ-350A
MP210A5R	AC fuse provides protection			

NOTE

DC protection fusing is only required for 4 quadrant drives.

Table 12-28   Cooper Bussman Semiconductor fusing for size 2 drives

Model	Description	Catalogue number	Alternative 1		Alternative 2		Alternative 3	
			Description	Catalogue number	Description	Catalogue number	Description	Catalogue number
Auxiliary	10 x 38mm Ferrule Fuse	FWC-25A10F						
MP350A4	690V, 500A BS88 Fuse	500FMM	700V, 500A FWP Series Fuse	FWP-500A	1000V, 500A FWJ Series Fuse	FWJ-500A	500V, 450A FWH Series Fuse	FWH-450A
MP350A4R	Size 3 US blade SQ Body	170M8536			1000V, 500A FWJ Series Fuse	FWJ-500A		
MP350A5 MP350A6	690V, 500A BS88 Fuse	500FMM	700V, 500A FWP Series Fuse	FWP-500A	1000V, 500A FWJ Series Fuse	FWJ-500A		
MP350A5R MP350A6R	Size 2 Square Body DIN 43 653 Fuse	170M5144						
MP420A4	690V, 630A BS88 Fuse	630FMM	700V, 700A FWP Series Fuse	FWP-700A	1000V, 600A FWJ Series Fuse	FWJ-600A	500V, 600A FWH Series Fuse	FWH-600A
MP420A4R	Size 2 Square Body DIN 43 653	170M5972			1000V, 600A FWJ Series Fuse	FWJ-600A		
MP470A5 MP470A6	Size 3 DIN 43 620 Square Body Blade	170M5139	700V, 800A FWP Series Fuse	FWP-800A	1000V, 800A FWJ Series Fuse	FWJ-800A		
MP470A5R MP470A6R	*2 x Size 2 Square Body DIN 43 653 in parallel.	170M5139						
MP550A4	690V, 700A BS88 Fuse	700FMM	700V, 800A FWP Series Fuse	FWP-800A	1000V, 800A FWJ Series Fuse	FWJ-800A	500V, 700A FWH Series Fuse	FWH-700A
MP550A4R	2 x Size 3 Square Body DIN 43 653 in parallel.	170M8616			1000V, 800A FWJ Series Fuse	FWJ-800A		
MP700A4	Size 1 Square Body Flush End	170M4419	700V, 900A FWP Series Fuse	FWP-900A	1000V, 1000A FWJ Series Fuse	FWJ-1000A	500V, 1000A FWH Series Fuse	FWH-1000A
MP700A4R	Size 3 Square DIN 43 653 Fuse	170M6147			1000V, 1000A FWJ Series Fuse	FWJ-1000A		
MP700A5 MP700A6	Size 2 Square Body Flush End	170M5415	700V, 900A FWP Series Fuse	FWP-900A	1000V, 1000A FWJ Series Fuse	FWJ-1000A		
MP700A5R MP700A6R	Square Body Flush End Contact	170M6726						
MP825A4	Size 2 Square Body Flush End	170M5417	700V, 1200A FWP Series Fuse	FWP-1200A	1000V, 1200A FWJ Series Fuse	FWJ-1200A	500V,1200A FWH Series Fuse	FWH-1200A
MP825A5 MP825A6								
MP825A4R	2 x Size 3 Square Body DIN 43 653 in parallel.	170M6143			*1000V, 1000A FWJ Series Fuse	*FWJ-1000A		
MP825A5R MP825A6R	Square Body Flush End Contact	170M6024						
MP900A4	Size 3 Square Body Flush End	170M6416	700V, 1200A FWP Series Fuse	FWP-1200A	1000V, 1200A FWJ Series Fuse	FWJ-1200A	500V, 1200A FWH Series Fuse	FWH-1200A
MP900A4R	*Size 3 Square DIN 43 653 Fuse	*170M6147			*1000V, 1000A FWJ Series Fuse	*FWJ-1000A		
MP1200A4	Size 4 Square Body Flush End	170M7061					2 x 500V, 1000A FWH Series Fuse in parallel.	FWH-1000A (x2)
MP1200A4R	2x Size 3 Square Body DIN 43 653 in parallel.	170M6146			FWJ-1600A	FWJ-1600A		
MP1200A5 MP1200A6	Size 4 Square Body Flush End	170M7061			1000V, 1600A FWJ Series Fuse	FWJ-1600A		
MP1200A5R MP1200A6R	*2 x Square Body Flush End Contact in parallel.	*170M6726						
MP1850A4	2 x Size 4 Square Body Flush End in parallel.	170M7059					2 x 500V, 1200A FWH Series Fuse in parallel.	FWH-1200A (x2)
MP1850A4R					*2 x 1000V, 1000A FWJ Series Fuses in parallel.	*FWJ-1000A		
MP1850A5 MP1850A6	*2 x Size 2 Square Body Flush End in parallel.	*170M5415						
MP1850A5R MP1850A6R	*3 x Size 3 Square body DIN 43 653 in parallel.	*170M6143						

NOTE

*Fusing limits applications to those operating at rated current. No cyclic overloads are permitted.

Table 12-29   Cooper Bussman branch circuit protection fusing for size 2 drives

Model			Description	Catalogue number
Auxiliary			Class CC, 600Vac, 20A Fuse	LP-CC-20
MP350A4	MP350A4R		Class L, 600Vac, 900A Fuse	KRP-C-900SP
MP350A6	MP350A5R	MP350A6R		
MP420A4	MP420A4R		Class L,600Vac, 1200A Fuse	KRP-C-1200SP
MP470A6	MP470A5R	MP470A6R		
MP550A4	MP550A4R		Class L, 600Vac, 1350A Fuse	KRP-C-1350SP
MP700A4	MP700A4R		Class L, 600Vac, 1600A Fuse	KRPC-1600SP
MP700A6	MP700A5R	MP700A6R		
MP825A4	MP825A4R		Class L, 600Vac, 2000A Fuse	KRP-C-2000SP
MP825A6	MP825A5R	MP825A6R		
MP900A4	MP900A4R		Class L, 600Vac, 2000A Fuse	KRP-C-2000SP
MP1200A4	MP1200A4R		Class L, 600Vac, 3000A Fuse	KRP-C-3000SP
MP1200A6	MP1200A5R	MP1200A6R		
MP1850A4	MP1850A4R		Class L, 600Vac, 4500A Fuse	KRP-C-4500SP
MP1850A6	MP1850A5R	MP1850A6R		

Table 12-30   Cooper Bussmann DC protection fusing for size 2 drives

Model	Description	Catalogue number	Alternative 1 Description	Alternative 1 Catalogue number	Alternative 2 Description	Alternative 2 Catalogue number
MP350A4R	1000V, 550A US Square Body Fuse	170M8536	1000V, 600A North American Fuse	FWJ - 600	700Vac 450A FWP Series Fuse	FWP 450A
MP420A4R	1000V, 800A North American Fuse	FWJ-800			700Vac 600A FWP Series Fuse	FWP 600A
MP550A4R	1000V, 900A Square Body End Contact Fuse	170M6603	1000V, 1000A North American Fuse	FWJ - 1000	700Vac 700A FWP Series Fuse	FWP 700A
MP350A5R MP350A6R	1500V, 630A Square Body End Contact Fuse	170M6726				
MP470A5R MP470A6R	1500V, 900A Square Body End Contact Fuse	170M6727				
MP700A4R	1000V, 1200A North American Fuse	FWJ-1200A	700Vac 900A FWP Series Fuse	FWP 900A		
MP900A4R	1000V, 1400A North American Fuse	FWJ-1400A	700Vac 1200A FWP Series Fuse	FWP 1200A		
MP700A5R MP700A6R	1500V, 1260A Double Body Fuse	170M6757				
MP825A4R	1000V, 1400A North American Fuse	FWJ-1400A	700Vac 1200A FWP Series Fuse	FWP 1200A		
MP825A5R MP825A6R	1500V, 1260A Double Body Fuse	170M6757				
MP1200A4R	1000V, 2000A North American Fuse	FWJ-2000	2 x 700Vac, 1000A FWP Fuses in parallel.	FWP 1000A		
MP1850A4R	1000V, 3000A End Contact Fuse	170M7680	2 x 700Vac, 1200A FWP Fuses in parallel.	FWP 1200A		
MP1200A5R MP1200A6R	1400V, 2000A Square Body End Contact Fuse	170M8112				
MP1850A5R MP1850A6R	1400V, 3000A Square Body End Contact Fuse	170M8163				

NOTE

DC fusing is only required on four quadrant (R) drives.

Table 12-31   Siba semiconductor fusing for 480V and 575V size 1 drives

Model		Fuse type	Rating V	Rating A	Description	Part number (with indicator)	Part number (without indicator)
Auxiliary		10 x 38mm ferrule	660Vac	12	10 x 38 cylindrical 660Vac URZ	50 179 06.12	
MP25A4	MP25A5	22 x 58mm ferrule	690Vac	32	22 x 58 cylindrical 690Vac URZ	50 140 06.32	
MP45A4	MP45A5			63		50 140 06.63	
MP75A4	MP75A5			100		50 140 06.100	
MP25A4(R)	MP25A5(R)			32		50 140 06.32	
MP45A4(R)	MP45A5(R)			63		50 140 06.63	
MP75A4(R)	MP75A5(R)			100		50 140 06.100	
MP105A4	MP105A5	Size 000 square body		160	URB 000 690Vac 160A bolt-type	20 282 20.160	20 282 21.160
MP155A4	MP155A5			200	URB 000 690Vac 200A bolt-type	20 282 20.200	20 282 21.200
MP210A4	MP210A5			315	URB 000 690Vac 315A bolt-type	20 282 20.315	20 282 21.315
MP105A4(R)	MP105A5(R)			160	URB 000 690Vac 160A bolt-type	20 282 20.160	20 282 21.160
MP155A4(R)	MP155A5(R)			200	URB 000 690Vac 200A bolt-type	20 282 20.200	20 282 21.200
MP210A4(R)	MP210A5(R)			315	URB 000 690Vac 315A bolt-type	20 282 20.315	20 282 21.315

Table 12-32   Siba branch circuit protection fusing for 480V and 575V size 1 drives

Model		Fuse type	Rating V	Rating A	Description	Part number
Auxiliary		NH 000 knife blade	690Vac	10	NH 000 gG 690Vac 10A	20 477 13.10
MP25A4	MP25A5			35	NH 000 gG 690Vac 35A	20 477 13.35
MP45A4	MP45A5	NH 00 knife blade		63	NH 00 gG 690Vac 63A	20 209 13.63
MP75A4	MP75A5			100	NH 00 gG 690Vac 100A	20 209 13.100
MP25A4(R)	MP25A5(R)	NH 000 knife blade		35	NH 000 gG 690Vac 35A	20 477 13.35
MP45A4(R)	MP45A5(R)	NH 00 knife blade		63	NH 00 gG 690Vac 63A	20 209 13.63
MP75A4(R)	MP75A5(R)			100	NH 00 gG 690Vac 100A	20 209 13.100
MP105A4	MP105A5	NH 1 knife blade		160	NH1 gG 690Vac 160A	20 211 13.160
MP155A4	MP155A5			200	NH1 gG 690Vac 200A	20 211 13.200
MP210A4	MP210A5	NH 2 knife blade		315	NH2 gG 690Vac 315A	20 212 13.315
MP105A4(R)	MP105A5(R)	NH 1 knife blade		160	NH1 gG 690Vac 160A	20 211 13.160
MP155A4(R)	MP155A5(R)			200	NH1 gG 690Vac 200A	20 211 13.200
MP210A4(R)	MP210A5(R)	NH 2 knife blade		315	NH2 gG 690Vac 315A	20 212 13.315

Table 12-33   Siba DC protection fusing for 480V and 575V size 1 drives

Model		Fuse type	Rating V	Rating A	Description	Ref number	Configuration
MP25A4R	MP25A5R	20 x 127mm cylindrical	1000Vdc	32	20 x 127 1000Vdc 32A gR	90 080 10.32	single fuse
MP45A4R	MP45A5R			50	20 x 127 1000Vdc 50A gR	90 080 10.50	single fuse
MP75A4R	MP75A5R	36 x 190mm cylindrical	1500Vdc	80	36 x 190 1500Vdc 80A gR	90 094 10.80	single fuse
MP105A4R	MP105A5R	SQB-DC2 square body	900Vdc	125	SQB-DC2 1200V 125A	90 203 25.125	single fuse
MP155A4R	MP155A5R			160	SQB-DC2 1200V 160A	90 203 25.160	single fuse
MP210A4R	MP210A5R			250	SQB-DC2 1200V 250A	90 203 25.250	single fuse

NOTE

DC protection fusing is only required for 4 quadrant drives.

Table 12-34   Siba Semiconductor fusing for size 2 drives

Model	International			USA
	Description	Part number		
		Metric thread contact	Blade contact	Blade contact
Auxiliary	10 x 38mm Ferrule Fuse		50 179 06.20	
MP350A4	690V SQB1 500A	20 660 31.500	20 610 31.500	20 617 31.500
MP420A4	690V SQB1 550A	20 660 31.550	20 610 31.550	20 617 31.550
MP550A4	2 x 690V SQB1 400A in parallel.	20 660 31.400	20 610 31.400	20 617 31.400
MP350A4R	690V SQB1 500A	20 660 31.500	20 610 31.500	20 617 31.500
MP420A4R	690V SQB1 550A	20 660 31.550	20 610 31.550	20 617 31.550
MP550A4R	2 x 690V SQB1 400A in parallel.	20 660 31.400	20 610 31.400	20 617 31.400
MP350A5 MP350A6	1250V SQB1 450A	20 760 31.450	20 713 31.450	20 719 31.450
MP470A5 MP470A6	2 x 1250V SQB3 350A in parallel.	20 780 31.350	20 733 31.350	20 739 31.350
MP350A5R MP350A6R	1250V SQB1 450A	20 760 31.450	20 713 31.450	20 719 31.450
MP470A5R MP470A6R	2 x 1250V SQB3 350A in parallel.	20 780 31.350	20 733 31.350	20 739 31.350
MP700A4	690V SQB1 900A	20 660 31.900	20 610 31.900	20 617 31.900
MP825A4	2 x 690V SQB2 630A in parallel.	20 670 31.630	20 620 31.630	20 627 31.630
MP900A4	690V SQB2-2 1250A	20 678 32.1250		
MP700A4R	690V SQB1 900A	20 660 31.900	20 610 31.900	20 617 31.900
MP825A4R	2 x 690V SQB2 630A in parallel.	20 670 31.630	20 620 31.630	20 627 31.630
MP900A4R	690V SQB2-2 1250A	20 678 32.1250		
MP700A5 MP700A6	*1250V SQB3 900A	20 780 31.900	20 733 31.900	20 739 31.900
MP825A5 MP825A6	1250V SQB2 800A	*20 770 31.800	*20 723 31.800	*20 729 31.800
MP700A5R MP700A6R	1250V SQB3 900A	20 780 31.900	20 733 31.900	20 739 31.900
MP825A5R MP825A6R	*1250V SQB2 800A	*20 770 31.800	*20 723 31.800	*20 729 31.800
MP1200A4	690V SQB2-2 1600A	20 678 32.1600		
MP1850A4	*690V SQB3-2 1800A	*20 688 32.1800		
MP1200A5 MP1200A6	2 x 1250V SQB3-2 900A in parallel.	20 788 32.900		
MP1850A5 MP1850A6	**2 x 1250V SQB3-2 900A in parallel.	**20 788 32.900		
MP1200A4R	690V SQB2-2 1600A	20 678 32.1600		
MP1850A4R	*690V SQB3-2 1800A	*20 688 32.1800		
MP1200A5R MP1200A6R	2 x 1250V SQB3-2 900A in parallel.	20 788 32.900		
MP1850A5R MP1850A6R	**2 x 1250V SQB3-2 900A in parallel.	**20 788 32.900		

NOTE

*Applications limited to 100% current ripple content and no cyclic overloads to avoid fuse wear-out.

**Applications limited to 30% current ripple content and no cyclic overloads to avoid fuse wear-out.

Table 12-35   Siba branch circuit fusing for size 2 drives

Model	International	
	Description	**Part number**
Aux	*500Vac, 20A gG NH-Knife Blade 690Vac, 20A gG NH-Knife Blade	20 000 13.20 20 477 13.20
MP350A4(R)	*500Vac, 355A gG NH-knife blade 690Vac, 355A gG NH-knife blade	20 004 13.355 20 212 13.355
MP350A5(R) MP350A6(R)	690Vac, 355A gG NH-knife blade	20 212 13.355
MP420A4(R)	*500Vac, 400A gG NH-knife blade 690Vac, 400A gG NH-knife blade	20 004 13.400 20 212 13.400
MP470A5(R) MP470A6(R)	690Vac, 630A gG NH-knife blade	20 225 13.630
MP550A4(R)	690Vac, 630A gG NH-knife blade	20 225 13.630
MP700A4(R)	*500Vac, 800A gG NH-knife blade 690Vac, 800A gG NH-knife blade	20 006 13.800 20 225 13.800
MP700A5(R) MP700A6(R)	690Vac, 800A gG NH-knife blade	20 225 13.800
MP825A4(R) MP825A5(R) MP825A6(R)	690Vac, 800A gG NH-knife blade	20 225 13.800
MP900A4(R)	*500Vac, 1250A gG NH-knife blade	20 006 13.1250
MP1200A4(R)	*500Vac, 1250A gG NH-knife blade	20 006 13.1250

NOTE

Fuses are only rated up to 500Vac.

Table 12-36   Siba DC protection fusing for size 2 drives

Model	Description	International		USA	
		Part number			
		Metric thread	**Blade contact**	**UNC thread**	**Blade contact**
MP350A4R	2 x SQB3 1250V 315A in parallel.	2078132.315A.	2073532.315A	2078432.315A	2073932.315A
MP350A5R MP350A6R	SQB3 1250V 400A	*2078132.400A.	*2073532.400A	*2078432.400A	*2073932.400A
MP420A4R	SQB3 1250V 500A	*2078132.500A	*2073532.500A	*2078432.500A	*2073932.500A
MP470A5R MP470A6R	2 x SQB3 1250V 315A in parallel.	*2078132.315A.	*2073532.315A	*2078432.315A	*2073932.315A
MP550A4R	2 x SQB3 1250V 315A in parallel.	*2078132.315A.	*2073532.315A	*2078432.315A	*2073932.315A
MP700A4R	2 x SQB3 1250V 500A in parallel.	2078132.500A	2073532.500A	2078432.500A	2073932.500A
MP700A5R MP700A6R	2 x SQB3 1250V 450A in parallel.	*2078132.450A	*2073532.450A	*2078432.450A	*2073932.450A
MP825A4R MP825A5R MP825A6R	2 x SQB3 1250V 500A in parallel.	*2078132.500A	*2073532.500A	*2078432.500A	*2073932.500A
MP900A4R	2 x SQB3 1250V 500A in parallel.	*2078132.500A	*2073532.500A	*2078432.500A	*2073932.500A

NOTE

DC fusing is only required on four quadrant (R) drives.

* Applications limited to 100% current ripple content and no cyclic overloads to avoid fuse wear-out

Table 12-37 Mentor MP size 1 drive thyristor I²t ratings for semiconductor fusing

Model		Thyristor I²t (A²s)
Auxiliary		400
MP25A4	MP25A5	1030
MP45A4	MP45A5	3600
MP75A4	MP75A5	15000
MP25A4(R)	MP25A5(R)	1030
MP45A4(R)	MP45A5(R)	3600
MP75A4(R)	MP75A5(R)	15000
MP105A4	MP105A5	80000
MP155A4	MP155A5	
MP210A4	MP210A5	
MP105A4(R)	MP105A5(R)	
MP155A4(R)	MP155A5(R)	
MP210A4(R)	MP210A5(R)	

Table 12-38 Mentor MP size 2 drive thyristor I²t ratings for semiconductor fusing

Model			Thyristor I²t (A²s)
Auxiliary			400
MP350A4(R)	MP420A4(R)	MP550A4(R)	320000
MP350A6(R)	MP470A5(R)	MP470A6(R)	281000
MP700A4(R)	MP825A4(R)	MP900A4(R)	1050000
MP700A6(R)	MP825A5(R)	MP825A6(R)	1200000
MP1200A4(R)	MP1200A5(R)	MP1200A6(R)	2720000
MP1850A4(R)	MP1850A5(R)	MP1850A6(R)	

12.2.3 Torque settings

Table 12-39 Drive control, status relay and encoder terminal data

Model	Connection type	Torque setting
All	Plug-in terminal block	0.5 Nm 0.4 lb ft

Table 12-40 Drive auxiliary and machine armature terminal data

Model	Connection type	Torque setting
All	Terminal block	0.5 Nm 0.4 lb ft

Table 12-41 Drive power stage terminals

Model	Connection type	Torque setting
All	M8 stud	10 Nm 7.4 lb ft

Table 12-42 Drive power stage terminals on size 2 drives

Model	Connection type	Torque setting
Size 2A	M10 stud	15 Nm (11.06 lb ft)
Size 2B	M12 stud	30 Nm (22.12 lb ft)
Size 2C		
Size 2D		

12.2.4 Electromagnetic compatibility (EMC)

This is a summary of the EMC performance of the drive. For full details, refer to the Mentor MP EMC data sheet which can be obtained from the supplier of the drive.

Table 12-43 Immunity compliance

Standard	Type of immunity	Test specification	Application	Level
IEC 61000-4-2 EN 61000-4-2	Electrostatic discharge	6kV contact discharge 8kV air discharge	Module enclosure	Level 3 (industrial)
IEC 61000-4-3 EN 61000-4-3	Radio frequency radiated field	10V/m prior to modulation 80 - 1000MHz 80% AM (1kHz) modulation	Module enclosure	Level 3 (industrial)
IEC 61000-4-4 EN 61000-4-4	Fast transient burst	5/50ns 2kV transient at 5kHz repetition frequency via coupling clamp	Control lines	Level 4 (industrial harsh)
		5/50ns 2kV transient at 5kHz repetition frequency by direct injection	Power lines	Level 3 (industrial)
IEC 61000-4-5 EN 61000-4-5	Surges	Common mode 4kV 1.2/50μs waveshape	AC supply lines: line to ground	Level 4
		Differential mode 2kV 1.2/50μs waveshape	AC supply lines: line to line	Level 3
		Lines to ground	Signal ports to ground [1]	Level 2
IEC 61000-4-6 EN 61000-4-6	Conducted radio frequency	10V prior to modulation 0.15 - 80MHz 80% AM (1kHz) modulation	Control and power lines	Level 3 (industrial)
IEC 61000-4-11 EN 61000-4-11	Voltage dips and interruptions	-30% 10ms +60% 100ms -60% 1s <-95% 5s	AC power ports	
EN 61000-6-1:2007 IEC 61000-6-1	Generic immunity standard for the residential, commercial and light-industrial environment			Complies
IEC 61000-6-2 EN 61000-6-2:2005	Generic immunity standard for the industrial environment			Complies
IEC 61800-3 EN 61800-3:2004	Product standard for adjustable speed power drive systems (immunity requirements)		Meets immunity requirements for first and second environments	

[1] See section 4.9.4 *Surge immunity of control circuits - long cables and connections outside a building* on page 47 for control ports for possible requirements regarding grounding and external surge protection.

Emission

The requirements of the following standards are met for motor cable lengths up to 100m.

Table 12-44   Emission compliance

Model	Filter		
	None	Field: Standard Armature: Standard	Field: Standard Armature:High performance
MP25A4(R)	C4	C3	C2
MP45A4(R)			
MP75A4(R)			
MP105A4(R)			
MP155A4(R)			
MP210A4(R)			
MP350A4(R)			
MP420A4(R)			
MP550A4(R)			
MP700A4(R)			
MP825A4(R)			
MP900A4(R)			
MP1200A4(R)			
MP1850A4(R)			

Key (shown in decreasing order of permitted emission level):

C4   EN 61800-3:2004 second environment, restricted distribution (Additional measures may be required to prevent interference)

C3   EN 61800-3:2004 second environment, unrestricted distribution

C2   Industrial generic standard EN 61000-6-4:2007
EN 61800-3:2004 first environment restricted distribution (The following caution is required by EN 61800-3:2004)

> **CAUTION**
> This is a product of the restricted distribution class according to IEC 61800-3. In a residential environment this product may cause radio interference in which case the user may be required to take adequate measures.

C1   Residential generic standard EN 61000-6-3:2007
EN 61800-3:2004 first environment unrestricted distribution

EN 61800-3:2004 defines the following:

- The first environment is one that includes residential premises. It also includes establishments directly connected without intermediate transformers to a low-voltage power supply network which supplies buildings used for residential purposes.
- The second environment is one that includes all establishments other than those directly connected to a low-voltage power supply network which supplies buildings used for residential purposes.
- Restricted distribution is defined as a mode of sales distribution in which the manufacturer restricts the supply of equipment to suppliers, customers or users who separately or jointly have technical competence in the EMC requirements of the application of drives.

12.3 Optional external EMC filters

EMC filters can be sourced directly from Schaffner and Epcos. See Table 12-45 for details.

> ⚠ **CAUTION** It is essential that line reactors be connected between the filter terminals and the power input terminals, as shown in Figure 4-1. Failure to observe this requirement could result in destruction of the thyristors.

Table 12-45 Mentor MP and EMC filter cross reference

Model	Manufacturers part number				
	Schaffner armature standard	Schaffner armature high performance	Epcos armature high performance	Schaffner standard field filter	Epcos standard field filter
MP25A4(R)	FN3270H-80-35	FN3258-75-52	B84143-A66-R105	FN3280H-8-29	W62400-T1262D004
MP45A4(R)	FN3270H-80-35	FN3258-75-52	B84143-A66-R105	FN3280H-8-29	W62400-T1262D004
MP75A4(R)	FN3270H-80-35	FN3258-75-52	*B84143-A90-R105	FN3280H-8-29	W62400-T1262D004
MP105A4(R)	FN3270H-200-99	FN3258H-180-40	B84143BO250S080	FN3280H-8-29	W62400-T1262D004
MP155A4(R)	FN3270H-200-99	FN3258H-180-40	B84143BO250S080	FN3280H-8-29	W62400-T1262D004
MP210A4(R)	FN3270H-200-99	FN3258H-180-40	B84143BO250S080	FN3280H-8-29	W62400-T1262D004
MP350A4 (R)		FN3359-800-99		FN3280H-25-33	
MP420A4 (R)		FN3359-800-99		FN3280H-25-33	
MP550A4 (R)		FN3359-800-99		FN3280H-25-33	
MP700A4 (R)		FN3359-800-99		FN3280H-25-33	
MP825A4(R)		FN3359-800-99		FN3280H-25-33	
MP900A4 (R)		FN3359-800-99		FN3280H-25-33	
MP1200A4 (R)		FN3359-1600-99		FN3280H-25-33	
MP1850A4 (R)		FN3359-1600-99		FN3280H-25-33	

* This filter is required if the input current to the Mentor MP will be greater than 66Amps.

13   Diagnostics

The display on the drive gives various information about the status of the drive. These fall into three categories:

- Trip indications
- Alarm indications
- Status indications

Users must not attempt to repair a drive if it is faulty, nor carry out fault diagnosis other than through the use of the diagnostic features described in this chapter.
If a drive is faulty, it must be returned to an authorized Control Techniques distributor for repair.

13.1   Trip indications

If the drive trips, the output of the drive is disabled so that the drive stops controlling the motor. The upper display indicates that a trip has occurred and the lower display shows the trip.

Trips are listed alphabetically in Table 13-1 based on the trip indication shown on the drive display. Refer to Figure 13-1.

If a display is not used, the drive LED Status indicator will flash if the drive has tripped. Refer to Figure 13-2.

The trip indication can be read in Pr **10.20** providing a trip number. Trip numbers are listed in numerical order in Table 13-2 so the trip indication can be cross referenced and then diagnosed using Table 13-1.

Example
1. Trip code 3 is read from Pr **10.20** via serial communications.
2. Checking Table 13-2 shows Trip 3 is an AOC trip.

3. Look up AOC in Table 13-1.
4. Perform checks detailed under *Diagnosis*.

Figure 13-1   Keypad status modes

Figure 13-2   Location of the status LED

Table 13-1   Trip indications

Trip	Diagnosis
AOC	**Instantaneous output over current detected: Peak current greater than 225%**
3	Check for short circuit on armature cabling Check integrity of motor insulation Check current loop stability
AOP	**Voltage has been applied to the armature but no current feedback has been detected**
158	Check the armature circuit
C.Acc	**SMARTCARD trip: SMARTCARD Read / Write fail**
185	Check SMARTCARD is installed / located correctly Ensure SMARTCARD is not writing data to data location 500 to 999 Replace SMARTCARD
C.boot	**SMARTCARD trip: The menu 0 parameter modification cannot be saved to the SMARTCARD because the necessary file has not been created on the SMARTCARD**
177	A write to a menu 0 parameter has been initiated via the keypad with Pr **11.42** (**SE09, 0.30**) set to auto(3) or boot(4), but the necessary file on the SMARTCARD has not bee created Ensure that Pr **11.42** (**SE09, 0.30**) is correctly set and reset the drive to create the necessary file on the SMARTCARD Re-attempt the parameter write to the menu 0 parameter
C.bUSY	**SMARTCARD trip: SMARTCARD can not perform the required function as it is being accessed by a Solutions Module**
178	Wait for the Solutions Module to finish accessing the SMARTCARD and then re-attempt the required function
C.Chg	**SMARTCARD trip: Data location already contains data**
179	Erase data in data location Write data to an alternative data location
C.cPr	**SMARTCARD trip: The values stored in the drive and the values in the data block on the SMARTCARD are different**
188	Press the red ⊘ reset button

Trip	Diagnosis
C.dAt	**SMARTCARD trip: Data location specified does not contain any data**
183	Ensure data block number is correct
C.Err	**SMARTCARD trip: SMARTCARD data is corrupted**
182	Ensure the card is located correctly Erase data and retry Replace SMARTCARD
C.Full	**SMARTCARD trip: SMARTCARD full**
184	Delete a data block or use different SMARTCARD
cL2	**Analog input 2 current loss (current mode)**
28	Check analog input 2 (terminal 7) current signal is present (4-20mA, 20-4mA)
cL3	**Analog input 3 current loss (current mode)**
29	Check analog input 3 (terminal 8) current signal is present (4-20mA, 20-4mA)
CL.bit	**Trip initiated from the control word (Pr 6.42)**
35	Disable the control word by setting Pr **6.43** to 0 or check setting of Pr **6.42**
C.OPtn	**SMARTCARD trip: Solutions Modules installed are different between source drive and destination drive**
180	Ensure correct Solutions Modules are installed Ensure Solutions Modules are in the same Solutions Module slot Press the red ⊘ reset button
C.Prod	**SMARTCARD trip: The data blocks on the SMARTCARD are not compatible with this product**
175	Erase all data on the SMARTCARD by setting Pr **xx.00** to 9999 and pressing the red ⊘ reset button Replace SMARTCARD
C.rdo	**SMARTCARD trip: SMARTCARD has the Read Only bit set**
181	Enter 9777 in Pr **xx.00** to allow SMARTCARD Read / Write access Ensure the drive is not writing to data locations 500 to 999 on the card
C.rtg	**SMARTCARD trip: The voltage and/or current rating of the source and destination drives are different**
186	Parameter data or default difference data is being transferred from a SMART card to the drive, but the current and /or voltage ratings are different between source and destination drives. This trip does not stop the data transfer, but is a warning that the data for the Solution Modules that are different will be set to the default values and not the values from the card. This trip also applies if a compare is attempted between the data block and the drive.
C.TyP	**SMARTCARD trip: SMARTCARD parameter set not compatible with drive**
187	Press the reset button Ensure destination drive type is the same as the source parameter file drive type
dESt	**Two or more parameters are writing to the same destination parameter**
199	Set Pr **xx.00** = 2001 check all visible parameters in the menus for duplication
EEF	**EEPROM data corrupted - Drive mode becomes open loop and serial comms will timeout with remote keypad on the drive RS485 comms port.**
31	This trip can only be cleared by loading default parameters and saving parameters
EnC1	**Drive encoder trip: Encoder power supply overload**
189	Check encoder power supply wiring and encoder current requirement Maximum current = 200mA @ 15V, or 300mA @ 8V and 5V
EnC2	**Drive encoder trip: Wire break**
190	Check cable continuity Check wiring of feedback signals is correct Check encoder power supply is set correctly in Pr **3.36** (**Fb06, 0.76**) Replace feedback device If wire break detection on the main drive encoder input is not required, set Pr **3.40** = 0 to disable the Enc2 trip
EnC3	**Drive encoder trip: Overload**
191	Overload
EnC9	**Drive encoder trip: Position feedback is selected from a Solutions Module slot which does not have a speed / position feedback Solutions Module installed**
197	Check setting of Pr **3.26** (**Fb01, 0.71**) (or Pr **21.21** if the second motor parameters have been enabled)
EnC10	**Drive encoder trip: Termination overload**

Trip	Diagnosis
198	If the voltage from the encoder is >5V, then the termination resistors must be disabled (Pr **3.39** to 0)
Et	**External trip**
6	Check terminal 31 signal Check value of Pr **10.32** Enter 12001 in Pr **xx.00** and check for parameter controlling Pr **10.32** Ensure Pr **10.32** or Pr **10.38** (=6) are not being controlled by serial comms
FbL	**No feedback from the tachogenerator or encoder**
159	If the difference between the estimated speed (Pr **5.04**) and the actual speed feedback (Pr **3.02** (**di05**, **0.40**)) exceeds the value set in the speed feedback loss window (Pr **3.56**) the drive will trip Feedback loss. With fast acceleration rates in applications with low load intertia estimated speed (Pr **5.04**) may not track the actual speed feedback (Pr **3.02** (**di05**, **0.40**)) fast enough and the speed feedback loss window (Pr **3.56**) may need to be increased. Check the feedback device is connected correctly Check motor name plate values have been entered into the drive correctly Check the speed feedback in estimated speed mode - refer to running a motor section checking speed feedback Carry out a rotating autotune
Fbr	**The polarity of the feedback tachogenerator or encoder is incorrect**
160	Check that the feedback devices are connected correctly
FdL	**No current in the field supply circuit**
168	Check that the field controller (Pr **5.77** (**SE12**, **0.33**)) is enabled. For the internal field controller check terminals L11, L12 are closed Check internal auxiliary fuses, refer to section 4.6.3 *Internal field fuses* on page 44.
FOC	**Excess current detected in field current feedback**
169	Maximum current feedback is present Check Field rated current (Pr **5.70** (**SE10**, **0.31**)) and Field rated voltage (Pr **5.73** (**SE11**, **0.32**)) are set correct to motor nameplate Check for short circuit on field circuit cabling Check integrity of motor insulation
F.OVL	**Field I^{2}t overload**
157	See Pr **5.81** and Pr **5.82**
HF01	**Data processing error: CPU address error**
	Hardware fault - return drive to supplier
HF02	**Data processing error: DMAC address error**
	Hardware fault - return drive to supplier
HF03	**Data processing error: Illegal instruction**
	Hardware fault - return drive to supplier
HF04	**Data processing error: Illegal slot instruction**
	Hardware fault - return drive to supplier
HF05	**Data processing error: Undefined exception**
	Hardware fault - return drive to supplier
HF06	**Data processing error: Reserved exception**
	Hardware fault - return drive to supplier
HF07	**Data processing error: Watchdog failure**
	Hardware fault - return drive to supplier
HF08	**Data processing error: Level 4 crash**
	Hardware fault - return drive to supplier
HF09	**Data processing error: Heap overflow**
	Hardware fault - return drive to supplier
HF10	**Data processing error: Router error**
	Hardware fault - return drive to supplier
HF11	**Data processing error: Access to EEPROM failed**
	Hardware fault - return drive to supplier
HF12	**Data processing error: Main program stack overflow**
	Hardware fault - return drive to supplier

Trip	Diagnosis
HF17	**Data processing error: No Comms from power processor**
217	Hardware fault - return drive to supplier
HF18	**Bucket suppressor capacitor failure**
218	Hardware fault - return drive to supplier
HF19	**Overheat on bucket suppressor or snubber circuits**
219	Check internal fan operation
HF20	**Power stage recognition: identification code error**
220	Hardware fault - return drive to supplier
HF21	**Power processor: Watchdog failure**
221	Hardware fault - return drive to supplier
HF22	**Power processor: Undefined exception**
222	Hardware fault - return drive to supplier
HF23	**Power processor: Level overrun**
223	Hardware fault - return drive to supplier
HF27	**Power circuit: Thermistor 1 fault**
227	Hardware fault - return drive to supplier
HF28	**Power software not compatible with user software**
228	Hardware fault - return drive to supplier
HF29	**User processor: Armature timing error**
229	Hardware fault - return drive to supplier
It.AC	**I^{2}t on drive output current (Refer to Pr 4.16)**
20	Ensure the load is not jammed / sticking Check the load on the motor has not changed
O.ht1	**Drive overheat (thyristor junction) based on thermal model**
21	Reduce ambient temperature Reduce overload cycle
O.ht2	**Heatsink over temperature**
22	Check enclosure / drive fans are still functioning correctly Check enclosure ventilation paths Check enclosure door filters Increase ventilation Decrease acceleration / deceleration rates Reduce duty cycle Reduce motor load
O.ht3	**External discharge resistor over temperature**
27	The temperature of the external discharge resistor is monitored by the temperature accumulators. When the resistor temperature (Pr **11.65**) reaches 100% the drive will trip See Pr **11.62**, Pr **11.63** and Pr **11.64**
O.Ld1	**Digital output overload: total current drawn from 24V supply and digital outputs exceeds 200mA**
26	Check total load on digital outputs (terminals 24,25,26)and +24V rail (terminal 22)
O.SPd	**Motor speed has exceeded the over speed threshold**
7	The drive will trip O.SPd if the armature is open circuit when the drive is in estimated speed mode. Check armature circuit If the speed feedback (Pr **3.02** (**di05, 0.40**)) exceeds the over speed threshold (Pr **3.08**) in either direction an over speed trip is produced. If this parameter is set to zero, the over speed threshold is automatically set to 1.2 x Pr **1.06** (**SE02, 0.23**) or Pr **1.07** (**SE01, 0.22**). Reduce the speed loop gain (Pr **3.10** (**SP01, 0.61**)) and speed integral (Pr **3.11** (**SP02, 0.62**)) to prevent speed overshoot.
PAd	**Keypad has been removed when the drive is receiving the speed reference from the keypad**
34	Install keypad and reset Change speed reference selector to select speed reference from another source
PLL Err	**Phase Lock Loop cannot lock to the auxiliary supply**
174	Check auxiliary supply is stable

Trip	Diagnosis
PS	**Internal power supply fault**
5	Remove any Solutions Modules and reset Hardware fault - return drive to supplier
PS.10V	**10V user power supply current greater than 10mA**
8	Check wiring to terminal 4 Reduce load on terminal 4
PS.24V	**24V internal power supply overload**
9	The total user load of the drive and Solutions Modules has exceeded the internal 24V power supply limit. The user load consists of the drive's digital outputs, the SM-I/O Plus digital outputs, the drive's main encoder supply and the SM-Universal Encoder Plus encoder supply. • Reduce load and reset • Provide an external 24V >50W power supply • Remove any Solutions Modules and reset
PSAVE.Er	**Power down save parameters in the EEPROM are corrupt**
37	Indicates that the power was removed when power down save parameters were being saved. The drive will revert back to the power down parameter set that was last saved successfully. Perform a user save (Pr **xx.00** to SAVE and reset the drive) or power down the drive normally to ensure this trip does or occur the next time the drive is powered up.
SAVE.Er	**User save parameters in the EEPROM are corrupt**
36	Indicates that the power was removed when user parameters were being saved. The drive will revert back to the user parameter set that was last saved successfully. Perform a user save (Pr **xx.00** to SAVE and reset the drive) to ensure this trip does or occur the next time the drive is powered up.
SCL	**Drive RS485 serial comms loss to remote keypad**
30	Reinstall the cable between the drive and keypad Check cable for damage Replace cable Replace keypad
SL	**AC input phase loss**
170	Ensure all three thyristor bridge supply phases are present Check input voltage levels are correct (at full load)
SLX.dF	**Solutions Module slot X trip: Solutions Module type installed in slot X changed**
204,209,214	Save parameters and reset
SLX.Er	**Solutions Module slot X trip: Solutions Module in slot X has detected a fault**
202,207,212	**Feedback module category** See the *Diagnostics* section in the relevant Solutions Module User Guide for more information.
SLX.HF	**Solutions Module slot X trip: Solutions Module X hardware fault**
200,205,210	Ensure Solutions Module is installed correctly Return Solutions Module to supplier
SLX.nF	**Solutions Module slot X trip: Solutions Module has been removed**
203,208,213	Ensure Solutions Module is installed correctly Reinstall Solutions Module Save parameters and reset drive
SL.rtd	**Solutions Module trip: Drive mode has changed and Solutions Module parameter routing is now incorrect**
215	Press reset. If the trip persists, contact the supplier of the drive.
SLX.tO	**Solutions Module slot X trip: Solutions Module watchdog timeout**
201,206,211	Press reset. If the trip persists, contact the supplier of the drive.
S.Old	**The maximum power the over voltage suppressor can handle has been exceeded**
171	Check the recommended line reactors are installed Check the recommended external suppressor resistor is installed
S.OV	**Excessive suppressor voltage**
172	Operation of the drive requires the installation of the external suppressor resistance, see section 4.7 *External suppressor resistor* on page 44.

Trip	Diagnosis
t002	**Reserved**
2	A value of 2 is being written to user trip (Pr **10.38**). The drives internal logic, on board or Solutions Module program must be interrogated. The program should be modified so that only trips defined as User trip are used.
t004	**Reserved**
4	See diagnosis for t002
t010	**Reserved**
10	See diagnosis for t002
t019	**Reserved**
19	See diagnosis for t002
t023	**User trip**
23	This trip is user defined. The drives internal logic, on board or Solutions module program must be interrogated to find the cause of this trip. A value of 23 is being written to user trip (Pr **10.38**)
t032	**Reserved**
32	See diagnosis for t002
t032 to t033	**Reserved**
32 to 33	See diagnosis for t002
t038 to t039	**Reserved**
38 to 39	See diagnosis for t002
t040 to t089	**User trip**
40 to 89	See diagnosis for t023
t099	**User trip defined in 2nd processor Solutions Module code**
99	This solutions module program must be interrogated to find the cause of this trip. A value of 99 is being written to user trip (Pr **10.38**)
t101	**User trip**
101	See diagnosis for t023
t102 to t111	**Reserved**
102 to 111	See diagnosis for t002
t112 to t156	**User trip**
112 to 156	See diagnosis for t023
t161 to t167	**Reserved**
161 to 167	See diagnosis for t002
t176	**Reserved**
176	See diagnosis for t002
t192 to t196	**Reserved**
192 to 196	See diagnosis for t002
t216	**User trip**
216	See diagnosis for t023
th	**Motor thermistor trip**
24	Check motor temperature Check thermistor continuity Set Pr **7.15** (**in01, 0.81**) = VOLt and reset the drive to disable this function
th.Err	**Missing thyristor**
173	Hardware fault - return drive to supplier
thS	**Motor thermistor short circuit**
25	Check motor thermistor wiring Replace motor / motor thermistor Set Pr **7.15** (**in01, 0.81**) = VOLt and reset the drive to disable this function
tunE	**Autotune stopped before completion**
18	The drive has tripped out during the autotune The red stop key has been pressed during the autotune
tunE1*	**The position feedback did not change or required speed could not be reached during the inertia test (see Pr 5.12 (SE13, 0.34))**

Trip	Diagnosis
11	Ensure the motor is free to turn i.e. brake was released Ensure Pr **3.26** and Pr **3.38** are set correctly Check feedback device wiring is correct Check feedback device coupling to motor
tunE2*	**Position feedback direction incorrect or motor could not be stopped during the inertia test (See Pr 5.12 (SE13, 0.34))**
12	Check motor cable wiring is correct Check feedback device wiring is correct
tunE3*	**Field flux has not decayed to zero during autotune**
13	Contact the supplier of the drive
tunE4*	**Back emf detected during autotune**
14	Check that the motor is not spinning when a static autotune is carried out
tunE5*	**No field current detected during autotune**
15	Reset Pr **5.70** (**SE10, 0.31**) to nameplate value and re-autotune motor
tunE6*	**Cannot achieve ¼ rated back emf during autotune**
16	Reset Pr **5.70** (**SE10, 0.31**) to nameplate value and re-autotune motor
tunE7*	**Rotating autotune initiated with Estimated speed selected**
17	Connect a feedback device to carry out a rotating autotune
UP ACC	**Onboard PLC program: cannot access Onboard PLC program file on drive**
98	Disable drive - write access is not allowed when the drive is enabled Another source is already accessing Onboard PLC program - retry once other action is complete
UP div0	**Onboard PLC program attempted divide by zero**
90	Check program
UP OFL	**Onboard PLC program variables and function block calls using more than the allowed RAM space (stack overflow)**
95	Check program
UP ovr	**Onboard PLC program attempted out of range parameter write**
94	Check program
UP PAr	**Onboard PLC program attempted access to a non-existent parameter**
91	Check program
UP ro	**Onboard PLC program attempted write to a read-only parameter**
92	Check program
UP So	**Onboard PLC program attempted read of a write-only parameter**
93	Check program
UP udF	**Onboard PLC program un-defined trip**
97	Check program
UP uSEr	**Onboard PLC program requested a trip**
96	Check program
UV	**The drive is running from the external 24V supply**
1	The drive is running from the external 24V supply

*If a tunE through tunE 7 trip occurs, then after the drive is reset the drive cannot be made to run unless it is disabled via the drive enable parameter (Pr **6.15**) or the control word (Pr **6.42**).

Table 13-2 Serial communications look-up table

No.	String	No.	String	No.	String
1	UV	91	UP Par	189	EnC1
2	t002	92	UP ro	190	EnC2
3	AOC	93	UP So	191	EnC3
4	t004	94	UP ovr	192-196	t192 - t196
5	PS	95	UP OFL	197	EnC9
6	Et	96	UP uSEr	198	EnC10
7	O.SPd	97	UP udf	199	dESt
8	PS.10V	98	UP ACC	200	SL1.HF
9	PS.24V	99	t099	201	SL1.tO
10	t010	100		202	SL1.Er
11	tunE1	101	t101	203	SL1.nF
12	tunE2	102-111	t102 - t111	204	SL1.dF
13	tunE3	112-156	t112 - t156	205	SL2.HF
14	tunE4	157	F.OVL	206	SL2.tO
15	tunE5	158	AOP	207	SL2.Er
16	tunE6	159	FbL	208	SL2.nF
17	tunE7	160	Fbr	209	SL2.dF
18	tunE	161-167	t161 - t167	210	SL3.HF
19	t019	168	FdL	211	SL3.tO
20	lt.AC	169	FOC	212	SL3.Er
21	O.ht1	170	SL	213	SL3.nF
22	O.ht2	171	S.OLd	214	SL3.dF
23	t023	172	S.OV	215	SL.rtd
24	th	173	th.Err	216	t216
25	thS	174	PLL Err	217-229	HF17 – HF29
26	O.Ld1	175	C.Prod		
27	O.ht3	176	t176		
28	cL2	177	C.Boot		
29	cL3	178	C.BUSy		
30	SCL	179	C.Chg		
31	EEF	180	C.Optn		
32-33	t032 - t033	181	C.RdO		
34	Pad	182	C.Err		
35	CL.bit	183	C.dat		
36	SAVE.Er	184	C.FULL		
37	PSAVE.Er	185	C.Acc		
38-39	t038 - t039	186	C.rtg		
40-89	t040 - t089	187	C.Typ		
90	UP div0	188	C.cpr		

13.2 Trip categories

Trips can be grouped into the following categories. It should be noted that a trip can only occur when the drive is not tripped or is already tripped but with a trip with a lower priority number.

Table 13-3 Trip categories

Priority	Category	Trips	Comments
1	Hardware faults	HF01 to HF16	These indicate fatal problems and cannot be reset. The drive is inactive after one of these trips and the display shows HFxx.
2	Non-resetable trips	HF17 to HF29, SL1.HF, SL2.HF, SL3.HF	Cannot be reset
3	EEF trip	EEF	Cannot be reset unless a code to load defaults is first entered in parameter x.00
4	SMARTCARD trips	C.Boot, C.Busy, C.Chg, C.Optn, C.RdO, C.Err, C.dat, C.FULL, C.Acc, C.rtg, C.Typ, C.cpr,	SMARTCARD trips have priority 5 during power up.
4	Encoder power supply trips	Enc1, Enc2	These trips can only override the following priority 5 trips: Enc2, Enc9 or Enc10
5	Normal trips	All other trips not included in this table	Can be reset after 1.0s
6	Self reseting trips	UV	Under voltage trip cannot be reset by the user, but is automatically reset by the drive when the supply voltage is with specification.

Unless otherwise stated, trips cannot be reset until 1.0s after the trip has been accepted by the drive.

13.3   Alarm indications

In any mode an alarm flashes alternately with the data displayed on the 2nd row when one of the following conditions occur. If action is not taken to eliminate any alarm except "Autotune", and "PLC" the drive may eventually trip. Alarms flash once every 640ms except "PLC" which flashes once every 10s. Alarms are not displayed when a parameter is being edited.

Table 13-4   Alarm indications

Lower display	Description
Hot	Heatsink alarm is active
The temperature displayed in Pr **7.04** has exceeded the alarm level (see Pr **7.04**).	
OVLd	Motor overload
The motor I^{2}t accumulator (Pr **4.19**) in the drive has reached 75% of the value at which the drive will be tripped and the load on the drive is > motor rated current (Pr **5.07** (**SE07, 0.28**)).	
Autotune	Autotune in progress
The autotune procedure has been initialised. 'Auto' and 'tunE' will flash alternatively on the display.	
CLt	Current limit is active
Indicates that current limits are active.	
PLC	Onboard PLC program is running
An Onboard PLC program is installed and running. The lower display will flash 'PLC' once every 10s.	
S.OV	Indicated suppressor over voltage
Indicates that the over voltage suppressor voltage is within 30V of the trip level	
S.rS	Suppressor resistor overload
Indicates that the external voltage suppressor resistor is in an overload condition	
ESt SPd	Estimated speed selected
The drive has lost speed feedback and automatically selected Estimated speed mode. See Pr **3.55** (Select estimated speed on feedback loss).	

13.4   Status indications

Table 13-5   Status indications

Upper display	Description	Drive output stage
dEC	Decelerating	Enabled
Speed is ramping to zero after a stop		
inh	Inhibited	Disabled
Enable input is inactive		
POS	Position	Enabled
Position control active during orientation stop		
rdY	Ready	Disabled
Enable closed, but drive not active		
run	Running	Enabled
Drive active and motor running		
StoP	Stopped	Enabled
Drive active, but holding zero speed.		
triP	Tripped	Disabled
Drive is tripped.		

13.5   Displaying the trip history

The drive retains the last 10 trips that have occurred.

Table 13-6 shows parameters used to store the last 10 trip.

Table 13-6   Trips

Menu 0	Parameter	Description	Display
0.51	**10.20**	Trip 0 (most recent trip)	**tr01**
0.52	**10.21**	Trip 1	**tr02**
0.53	**10.22**	Trip 2	**tr03**
0.54	**10.23**	Trip 3	**tr04**
0.55	**10.24**	Trip 4	**tr05**
0.56	**10.25**	Trip 5	**tr06**
0.57	**10.26**	Trip 6	**tr07**
0.58	**10.27**	Trip 7	**tr08**
0.59	**10.28**	Trip 8	**tr09**
0.60	**10.29**	Trip 9	**tr10**

13.6   Behavior of the drive when tripped

If the drive trips the output of the drive is disabled so that the drive stops controlling the motor. If any trip occurs (except UV) the following read only parameters are frozen to help in diagnosing the cause of the trip

Table 13-7   Parameters frozen on trip

Menu 0	Parameter	Description	Display
0.36	**1.01**	Speed reference selected	**di01**
	1.02	Pre-skip filter reference	
0.37	**1.03**	Pre-ramp reference	**di02**
0.38	**2.01**	Post ramp reference	**di03**
0.39	**3.01**	Final speed reference	**di04**
0.40	**3.02**	Speed feedback	**di05**
	3.03	Speed error	
0.41	**3.04**	Speed controller output	**di06**
0.43	**4.01**	Current magnitude	**di08**
	5.01	Armature firing angle	
0.45	**5.02**	Armature voltage	**di10**
	5.03	Output power	
	5.04	Estimated speed	
	5.05	Line voltage	
	5.58	Field firing angle	
0.82	**7.01**	Analog input 1	**in02**
0.83	**7.02**	Analog input 2	**in03**
0.84	**7.03**	Analog input 3	**in04**
	10.77	Input frequency	

Analog and digital I/O

The analog and digital I/O on the drive continue to work correctly if a trip occurs, except the digital outputs will go low if one of the following trips occur: O.Ld1, PS.24V.

Drive logic functions

The drive logic functions (i.e. PID, variable selectors, threshold detectors, etc.) continue to operate when the drive is tripped.

Onboard PLC program

The Onboard PLC program continues to run if the drive is tripped, except if one of Onboard PLC program trips occur.

13.7   Trip masking

Drive trips can be masked by setting the appropriate trip code in Pr **10.52** to Pr **10.61**. Refer to Pr **10.52** to Pr **10.72** (Advanced parameter descriptions chapter - Menu 10) in the *Mentor MP Advanced User Guide* for further information.

14   UL information

Mentor MP frame size 1 drives have been assessed to comply with both ULus and cUL requirements.

Control Techniques UL file number is E171230. Confirmation of UL listing can be found at website: www.ul.com

14.1   Common UL Information

Conformity: The drive conforms to UL listing requirements only when the following are observed:

1. The drive is installed in a type 1 enclosure, or better as defined in UL 50.
2. The ambient temperature does not exceed 40°C when the drive is operating.
3. The terminal torques specified in section 3.9.3 *Torque settings* on page 30 are to be used.
4. The power terminal lug used to crimp the, I/P & O/P cables are to be UL listed.
5. The drive is to be installed in to a pollution degree 2 environment.
6. If the drive control stage is supplied by an external power supply, (+24V), the external power supply must be a UL class 2 power supply.
7. Fuses sized as specified in the various tables in Chapter 4 *Electrical installation* on page 32 are to be used. Fusing is to incorporate a Class J fuse in line with a semiconductor fuse as specified.
8. Field wiring is to be class 1 75°C (167°F) copper wire only.

Motor overload protection

All models incorporate an internal overload protection model for the motor load that does not require the use of an external or remote overload protection device.

The protection level is adjustable, and the method of adjustment is provided with the instructions for the product.

Maximum current overload is dependant on the values entered into the current limit parameters (motoring current limit, regen current limit and symmetrical current limit entered as percentage) and the motor rated current parameter (entered in amperes).

The duration of the overload is dependant on motor thermal time constant (variable up to a maximum of 3000 seconds). The default overload protection is set such that the product is capable of 150% of the current value entered into the motor rated current parameter (Pr **5.07** (**SE07**, **0.28**)) for 30 seconds (20 seconds for MP470A4(R), MP470A5(R), MP825A5(R) and MP825A6(R). The product also provides user terminal default functionality such that the product can be connected to a motor thermistor to protect the motor in terms of temperature, in the event of a motor cooling fan failure.

Over speed protection

The drive provides overspeed protection. However it does not provide the level of protection afforded by an independent high integrity overspeed protection device.

14.2   AC supply specification

The maximum UL supply voltage is 600Vac.

The drive is suitable for use in a circuit capable of delivering not more than 100,000rms symmetrical Amperes at 575V (size 1A and 1B).

14.3   Maximum continuous output current

The drive models are listed as having the maximum continuous output currents (FLC) shown in section 2.1 *Ratings* on page 6.

14.4   Safety label

The safety label supplied with connectors and mounting brackets must be placed on a fixed part of the drive enclosure where it can be seen clearly by maintenance personnel for UL compliance.

The label clearly states "CAUTION risk of electric shock power down at least 10 minutes before removing cover".

14.5   UL Listed accessories

- SM-Keypad
- SM-DeviceNet
- SM-INTERBUS
- SM-Ethernet
- SM-Register
- SM-Applications Plus
- SM-Encoder Plus
- SM-I/O Plus
- SM-I/O Lite
- SM-I/O PELV
- SM-I/O 24V Protected
- Single ended encoder interface

- MP-Keypad
- SM-PROFIBUS-DP-V1
- SM-CANopen
- SM-EtherCAT
- SM-Applications Lite-V2
- SM-Universal Encoder Plus
- SM-Encoder Output Plus
- SM-I/O 32
- SM-I/O Timer
- SM-I/O 120V
- 15-way D-type converter

List of figures

List of tables

Index

S

T

V

W

0476-0000-04